

# ***Stormwater Report***

***Greenmont Commons  
Dracut, MA***

*Prepared for*

***Riverbank Properties  
908 Lawrence Street  
Lowell, MA 01852***

*May 18, 2023*

**CORNERSTONE  
Land Associates, LLC**  
Civil Engineering - Land Planning

---

25 Dean Avenue - Dracut, MA 01826 - (978) 835-0102  
kmconsultants@comcast.net

## **Forward**

This Stormwater Report is required by the Massachusetts Wetland Protection Act (MGL Ch. 131, Sect. 40); provisions of the Mass DEP Stormwater Management Standards per 310 CMR 10.05(6)(k)-(q); and the Town of Dracut General By Laws Chapter 24 and Town of Dracut Stormwater Management Rules and Regulations.



## Table of Contents

|                                                        |           |
|--------------------------------------------------------|-----------|
| <b>SECTION 1 SITE &amp; CONTACTS.....</b>              | <b>6</b>  |
| 1.1 Project & Site Information.....                    | 6         |
| 1.2 Application Information.....                       | 6         |
| 1.3 Preparer Information.....                          | 6         |
| 1.4 Project Type.....                                  | 6         |
| 1.5 Drainage Narrative.....                            | 6         |
| <b>SECTION 2 STORMWATER CHECKLIST.....</b>             | <b>9</b>  |
| <b>SECTION 3 LOW IMPACT DEVELOPMENT.....</b>           | <b>17</b> |
| <b>SECTION 4 STORMWATER STANDARDS.....</b>             | <b>19</b> |
| 4.1 Standard 1: No New Untreated Discharges .....      | 19        |
| 4.2 Standard 2: Peak Rate Attenuation .....            | 19        |
| 4.3 Standard 3: Recharge .....                         | 24        |
| 4.4 Standard 4: Water Quality .....                    | 26        |
| 4.5 Standard 5: Higher Potential Pollution Loads ..... | 27        |
| 4.6 Standard 6: Critical Areas.....                    | 28        |
| 4.7 Standard 7 Redevelopment .....                     | 28        |
| 4.8 Standard 8: Construction Period Controls .....     | 28        |
| 4.9 Standard 9: Operation & Maintenance .....          | 28        |
| 4.10 Standard 10: Illicit Discharge .....              | 28        |
| <b>Appendix A: Background Data .....</b>               | <b>31</b> |
| A.1 USGS Quadrangle Map .....                          | 32        |
| A.2 Assessors Map .....                                | 33        |
| A.3 Aerial Photography .....                           | 37        |
| A.4 Soils Data .....                                   | 38        |
| <b>Appendix B: BMP Designs .....</b>                   | <b>43</b> |
| B.1 Pre-Treatment BMP's .....                          | 43        |
| B.2 Treatment BMP's.....                               | 44        |
| B.3 Infiltration BMP's.....                            | 47        |
| <b>Appendix C: Hydrologic Analysis.....</b>            | <b>51</b> |
| C.1 Pre-Development Analysis .....                     | 52        |
| C.2 Post-Development Analysis.....                     | 83        |

## SECTION 1: SITE & CONTACT DATA

### 1.1 Project & Site Information

Project/Site Name: Greenmont Commons  
Project Street/Location: 135 Greenmont Avenue  
City: Dracut State: MA ZIP Code: 01826  
County or Similar Subdivision: \_\_\_\_\_  
Applicant Name: Riverbank Properties  
Applicant Address: 908 Lawrence Street City: Lowell State: MA ZIP Code: 01852

### 1.2 Applicant Information

Name: Riverbank Properties  
Address: 908 Lawrence Street City: Lowell State: MA ZIP Code: 01852  
Contact: Branco Perego Phone: (978) 771-3205

### 1.3 Preparer Information

Name: Kenneth M. Lania, E.I.T., Cornerstone Land Associates, LLC.  
Address: 25 Dean Avenue City: Dracut State: MA ZIP Code: 01826  
Registered P.E.: John A. Visniewski, P.E. Email: kmconsultants@comcast.net  
Phone: (978) 835-0102 Fax: \_\_\_\_\_

### 1.4 Project Type

Scope of Work: Development of an existing vacant lot including retaining walls, drainage, utilities, and parking lot.  
Function: ☒ Residential ☐ Commercial ☐ Industrial ☐ Other: \_\_\_\_\_  
☒ New ☐ Redevelopment ☐ Industrial ☐ Mix of New & Redevelopment  
Estimated Start Date.: Upon Approvals Estimated Completion Date: September 2024

### 1.5 Drainage Narrative

The proposed project is to construct 28 Townhouse Rental Units on the 2.45 Acre parcel utilizing the State's Comprehensive Permit Statute (M.G.L. c. 40B, Sections 20-23 enacted as Chapter 774 of the Acts of 1969) known as "Chapter 40B". The property is rectangle in shape with 240 LF of frontage along Greenmont Avenue and a depth of approximately 430 LF from the road. The property contains one single family dwelling located approximately 85 ft from Greenmont Avenue with associated driveway, rear deck and patio, as well as an in-ground pool with

concrete apron. The remainder of the property is a well established lawn with Bordering Vegetated Wetlands (BVW) in the southwestern corner of the property. The BVW was established on the property with flagging and is shown as WF-1 to WF-7. The majority of the property, approximately 2.22 acres, drains from north to south to the existing BVW area with the remainder 0.23 acres draining to Greenmont Avenue.

The proposed conditions utilize Low Impact Development techniques to mimic the existing drainage patterns. Two Detention/Recharge Basins are proposed within the Common Driveway design area to mitigate for stormwater events. The grading design allows stormwater to sheet flow into these basins through swales and forebays for the removal of large pollutant particles. The Basins are designed with a gravel bottom that promotes infiltration of stormwater.

The proposed drainage system mitigates for the Peak Flow and Peak Volume for each storm event, 2 year to 100 year. There is no increase in post-development runoff from pre-development runoff.

## **SECTION 2: STORMWATER CHECKLIST**



Massachusetts Department of Environmental Protection  
Bureau of Resource Protection - Wetlands Program

# Checklist for Stormwater Report

## A. Introduction

**Important:** When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.



A Stormwater Report must be submitted with the Notice of Intent permit application to document compliance with the Stormwater Management Standards. The following checklist is NOT a substitute for the Stormwater Report (which should provide more substantive and detailed information) but is offered here as a tool to help the applicant organize their Stormwater Management documentation for their Report and for the reviewer to assess this information in a consistent format. As noted in the Checklist, the Stormwater Report must contain the engineering computations and supporting information set forth in Volume 3 of the [Massachusetts Stormwater Handbook](#). The Stormwater Report must be prepared and certified by a Registered Professional Engineer (RPE) licensed in the Commonwealth.

The Stormwater Report must include:

- The Stormwater Checklist completed and stamped by a Registered Professional Engineer (see page 2) that certifies that the Stormwater Report contains all required submittals.<sup>1</sup> This Checklist is to be used as the cover for the completed Stormwater Report.
- Applicant/Project Name
- Project Address
- Name of Firm and Registered Professional Engineer that prepared the Report
- Long-Term Pollution Prevention Plan required by Standards 4-6
- Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan required by Standard 8<sup>2</sup>
- Operation and Maintenance Plan required by Standard 9

In addition to all plans and supporting information, the Stormwater Report must include a brief narrative describing stormwater management practices, including environmentally sensitive site design and LID techniques, along with a diagram depicting runoff through the proposed BMP treatment train. Plans are required to show existing and proposed conditions, identify all wetland resource areas, NRCS soil types, critical areas, Land Uses with Higher Potential Pollutant Loads (LUHPPL), and any areas on the site where infiltration rate is greater than 2.4 inches per hour. The Plans shall identify the drainage areas for both existing and proposed conditions at a scale that enables verification of supporting calculations.

As noted in the Checklist, the Stormwater Management Report shall document compliance with each of the Stormwater Management Standards as provided in the Massachusetts Stormwater Handbook. The soils evaluation and calculations shall be done using the methodologies set forth in Volume 3 of the Massachusetts Stormwater Handbook.

To ensure that the Stormwater Report is complete, applicants are required to fill in the Stormwater Report Checklist by checking the box to indicate that the specified information has been included in the Stormwater Report. If any of the information specified in the checklist has not been submitted, the applicant must provide an explanation. The completed Stormwater Report Checklist and Certification must be submitted with the Stormwater Report.

<sup>1</sup> The Stormwater Report may also include the Illicit Discharge Compliance Statement required by Standard 10. If not included in the Stormwater Report, the Illicit Discharge Compliance Statement must be submitted prior to the discharge of stormwater runoff to the post-construction best management practices.

<sup>2</sup> For some complex projects, it may not be possible to include the Construction Period Erosion and Sedimentation Control Plan in the Stormwater Report. In that event, the issuing authority has the discretion to issue an Order of Conditions that approves the project and includes a condition requiring the proponent to submit the Construction Period Erosion and Sedimentation Control Plan before commencing any land disturbance activity on the site.





Massachusetts Department of Environmental Protection  
Bureau of Resource Protection - Wetlands Program

## Checklist for Stormwater Report

### B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.


**Note:** Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

#### Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

Registered Professional Engineer Block and Signature



*John A. Visniewski* 1/5/23  
Signature and Date

### Checklist

**Project Type:** Is the application for new development, redevelopment, or a mix of new and redevelopment?

- ☒ New development
- ☐ Redevelopment
- ☐ Mix of New Development and Redevelopment



## Checklist for Stormwater Report

### Checklist (continued)

**LID Measures:** Stormwater Standards require LID measures to be considered. Document what environmentally sensitive design and LID Techniques were considered during the planning and design of the project:

- ☐ No disturbance to any Wetland Resource Areas
- ☐ Site Design Practices (e.g. clustered development, reduced frontage setbacks)
- ☐ Reduced Impervious Area (Redevelopment Only)
- ☐ Minimizing disturbance to existing trees and shrubs
- ☐ LID Site Design Credit Requested:
  - ☐ Credit 1
  - ☐ Credit 2
  - ☐ Credit 3
- ☒ Use of "country drainage" versus curb and gutter conveyance and pipe
- ☐ Bioretention Cells (includes Rain Gardens)
- ☐ Constructed Stormwater Wetlands (includes Gravel Wetlands designs)
- ☐ Treebox Filter
- ☒ Water Quality Swale
- ☒ Grass Channel
- ☐ Green Roof
- ☐ Other (describe): \_\_\_\_\_

### Standard 1: No New Untreated Discharges

- ☒ No new untreated discharges
- ☒ Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
- ☒ Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.





Massachusetts Department of Environmental Protection  
Bureau of Resource Protection - Wetlands Program

# Checklist for Stormwater Report

## Checklist (continued)

### Standard 2: Peak Rate Attenuation

- ☐ Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding.
- ☐ Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm.
- ☒ Calculations provided to show that post-development peak discharge rates do not exceed pre-development rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24-hour storm.

### Standard 3: Recharge

- ☒ Soil Analysis provided.
- ☐ Required Recharge Volume calculation provided.
- ☐ Required Recharge volume reduced through use of the LID site Design Credits.
- ☒ Sizing the infiltration, BMPs is based on the following method: Check the method used.
  - ☒ Static
  - ☐ Simple Dynamic
  - ☐ Dynamic Field<sup>1</sup>
- ☐ Runoff from all impervious areas at the site discharging to the infiltration BMP.
- ☒ Runoff from all impervious areas at the site is *not* discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume.
- ☐ Recharge BMPs have been sized to infiltrate the Required Recharge Volume.
- ☒ Recharge BMPs have been sized to infiltrate the Required Recharge Volume *only* to the maximum extent practicable for the following reason:
  - ☒ Site is comprised solely of C and D soils and/or bedrock at the land surface
  - ☐ M.G.L. c. 21E sites pursuant to 310 CMR 40.0000
  - ☐ Solid Waste Landfill pursuant to 310 CMR 19.000
  - ☐ Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable.
- ☐ Calculations showing that the infiltration BMPs will drain in 72 hours are provided.
- ☐ Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

<sup>1</sup> 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.





# Checklist for Stormwater Report

---

## Checklist (continued)

### Standard 3: Recharge (continued)

- ☐ The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10-year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.
- ☐ Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.

### Standard 4: Water Quality

The Long-Term Pollution Prevention Plan typically includes the following:

- Good housekeeping practices;
  - Provisions for storing materials and waste products inside or under cover;
  - Vehicle washing controls;
  - Requirements for routine inspections and maintenance of stormwater BMPs;
  - Spill prevention and response plans;
  - Provisions for maintenance of lawns, gardens, and other landscaped areas;
  - Requirements for storage and use of fertilizers, herbicides, and pesticides;
  - Pet waste management provisions;
  - Provisions for operation and management of septic systems;
  - Provisions for solid waste management;
  - Snow disposal and plowing plans relative to Wetland Resource Areas;
  - Winter Road Salt and/or Sand Use and Storage restrictions;
  - Street sweeping schedules;
  - Provisions for prevention of illicit discharges to the stormwater management system;
  - Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL;
  - Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan;
  - List of Emergency contacts for implementing Long-Term Pollution Prevention Plan.
- ☐ A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent.
  - ☐ Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge:
    - ☐ is within the Zone II or Interim Wellhead Protection Area
    - ☐ is near or to other critical areas
    - ☐ is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
    - ☐ involves runoff from land uses with higher potential pollutant loads.
  - ☐ The Required Water Quality Volume is reduced through use of the LID site Design Credits.
  - ☐ Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if applicable, the 44% TSS removal pretreatment requirement, are provided.



## Checklist for Stormwater Report

### Checklist (continued)

#### Standard 4: Water Quality (continued)

- ☒ The BMP is sized (and calculations provided) based on:
  - ☒ The ½" or 1" Water Quality Volume or
  - ☐ The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume.
- ☐ The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs.
- ☐ A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided.

#### Standard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs)

- ☐ The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report.
- ☐ The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted *prior* to the discharge of stormwater to the post-construction stormwater BMPs.
- ☐ The NPDES Multi-Sector General Permit does *not* cover the land use.
- ☐ LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan.
- ☐ All exposure has been eliminated.
- ☐ All exposure has *not* been eliminated and all BMPs selected are on MassDEP LUHPPL list.
- ☐ The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.

#### Standard 6: Critical Areas

- ☐ The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.
- ☐ Critical areas and BMPs are identified in the Stormwater Report.



# Checklist for Stormwater Report

## Checklist (continued)

### Standard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum extent practicable

- ☐ The project is subject to the Stormwater Management Standards only to the maximum Extent Practicable as a:
  - ☐ Limited Project
  - ☐ Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area.
  - ☐ Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area
  - ☐ Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff
  - ☐ Bike Path and/or Foot Path
  - ☐ Redevelopment Project
  - ☐ Redevelopment portion of mix of new and redevelopment.
- ☐ Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report.
- ☐ The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist found in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions.

### Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
  - Construction Period Operation and Maintenance Plan;
  - Names of Persons or Entity Responsible for Plan Compliance;
  - Construction Period Pollution Prevention Measures;
  - Erosion and Sedimentation Control Plan Drawings;
  - Detail drawings and specifications for erosion control BMPs, including sizing calculations;
  - Vegetation Planning;
  - Site Development Plan;
  - Construction Sequencing Plan;
  - Sequencing of Erosion and Sedimentation Controls;
  - Operation and Maintenance of Erosion and Sedimentation Controls;
  - Inspection Schedule;
  - Maintenance Schedule;
  - Inspection and Maintenance Log Form.
- ☐ A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.





## Checklist for Stormwater Report

### Checklist (continued)

#### Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control (continued)

- ☒ The project is highly complex and information is included in the Stormwater Report that explains why it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and Erosion and Sedimentation Control has **not** been included in the Stormwater Report but will be submitted **before** land disturbance begins.
- ☐ The project is **not** covered by a NPDES Construction General Permit.
- ☐ The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the Stormwater Report.
- ☐ The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted **BEFORE** land disturbance begins.

#### Standard 9: Operation and Maintenance Plan

- ☐ The Post Construction Operation and Maintenance Plan is included in the Stormwater Report and includes the following information:
  - ☐ Name of the stormwater management system owners;
  - ☐ Party responsible for operation and maintenance;
  - ☐ Schedule for implementation of routine and non-routine maintenance tasks;
  - ☐ Plan showing the location of all stormwater BMPs maintenance access areas;
  - ☐ Description and delineation of public safety features;
  - ☐ Estimated operation and maintenance budget; and
  - ☐ Operation and Maintenance Log Form.
- ☒ The responsible party is **not** the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions:
  - ☒ A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs;
  - ☐ A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions.

#### Standard 10: Prohibition of Illicit Discharges

- ☐ The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;
- ☐ An Illicit Discharge Compliance Statement is attached;
- ☒ NO Illicit Discharge Compliance Statement is attached but will be submitted **prior to** the discharge of any stormwater to post-construction BMPs.

### **SECTION 3: LOW IMPACT DEVELOPMENT (LID)**

Credits for LID have not been taken since the site does not comply with certain aspects of each credit item required. However, small portions of LID practices have been incorporated into the overall design. These practices are small in nature and include the utilization of Sheet Flow and a combination of multiple Best Management Practices for stormwater treatment of the entire proposed impervious surface up to and including the 100 Year Storm event to promote the use of earth basins and swales for infiltration to groundwater and pollutant removal.





## **SECTION 4: STORMWATER STANDARDS**

### ***4.1 Standard 1: No New Untreated Discharges***

New stormwater conveyances (e.g. outfalls) will not discharge untreated stormwater directly to or cause erosion in wetlands or waters of the Commonwealth.

#### ***Rip Rap Sizing at Spillways***

Stormwater calculations utilizing sheet flow to Grassed Lined Swales, Sediment Forebays and Detention/Recharge Basins throughout the development areas attenuates the Peak Flow and Peak Volume for all storm events 2 yr to 100 yr.


The design utilizes Low Impact Development techniques to promote as much infiltration of runoff back into the ground as possible. Proposed flow in large storm events travels to the two Detention/Recharge basins that utilize stone lined spillways for outlet protection of flow leaving the property.

### ***4.2 Standard 2: Peak Rate Attenuation***

Stormwater management systems have been designed so that the post-development peak discharge rates do not exceed pre-development peak discharge rates.

#### ***Soils Evaluation***

Soils on the site are classified on the USDA Natural Resources Conservation Service (NRCS) Soil Map that is shown below as an overlay on the MASS GIS Aerial Photography with NRCS Soils Overlay Layer. These soil classifications have been further assigned to Hydraulic Soil Groups (HSG) by the NRCS as shown on the map. Hydraulic soil groups range from A, sandy soils, to D, clayey soils.



## Hydrologic Soil Group

| Map unit symbol             | Map unit name                                                     | Rating | Acres in AOI | Percent of AOI |
|-----------------------------|-------------------------------------------------------------------|--------|--------------|----------------|
| 71B                         | Ridgebury fine sandy loam, 3 to 8 percent slopes, extremely stony | D      | 3.5          | 26.3%          |
| 305B                        | Paxton fine sandy loam, 3 to 8 percent slopes                     | C      | 0.5          | 3.9%           |
| 310A                        | Woodbridge fine sandy loam, 0 to 3 percent slopes                 | C/D    | 9.2          | 69.8%          |
| Totals for Area of Interest |                                                                   |        | 13.2         | 100.0%         |

Soils have also been evaluated in the field as shown in the following table; and soil logs are also shown on the Grading & Drainage Plan. The table shows the textural classification in each location according to direct field observation. The Estimated Seasonal High Groundwater (ESHGW) depth was determined by field observation of redoximorphic features (mottles) within the soil profile. The Rawls Rate assigned to various Hydraulic Soil Groups and textural types is used for calculations relative to exfiltration of stormwater into subsurface soils within stormwater storage facilities. In addition, soil samples were taken and sent to a soils laboratory for analysis of particle size and permeability.

### **Soil Evaluation**

#### **ON-SITE SOILS EVALUATION**

| Deep<br>Hole<br>Number <sup>1.</sup> | Textural<br>Classification <sup>2.</sup> | HSG <sup>3.</sup> | Depth<br>to<br>Refusal<br>(ft) | ESHG<br>W <sup>4.</sup><br>(in) | Rawls<br>Rate<br>(in/hr) <sup>5.</sup> |
|--------------------------------------|------------------------------------------|-------------------|--------------------------------|---------------------------------|----------------------------------------|
| DH301                                | SL                                       | D                 | n/a                            | 24                              | 0.09                                   |
| DH302                                | SL                                       | D                 | n/a                            | 24                              | 0.09                                   |
| DH303                                | SL                                       | D                 | n/a                            | 24                              | 0.09                                   |

<sup>1.</sup> See Site Plan for Deep  
hole locations

<sup>2.</sup> Laboratory soil analysis; otherwise field  
observation

<sup>3.</sup> Hydraulic Soil Group; USDA  
NRCS

<sup>4.</sup> Estimated seasonal high groundwater  
depth

<sup>5.</sup> DEP Stormwater Handbook, Table  
2.3.3.

### **USDA Soils Description**

| Map Unit<br># | Soil<br>Name              | HSG |
|---------------|---------------------------|-----|
| 71B           | Ridgebury Fine Sandy Loam | D   |
|               | Woodbridge Fine           |     |
| 310A          | Sandy Loam                | C/D |

The following Table shows land areas associated with the hydraulic soil group for each type of ground coverage within each drainage area. Hydraulic Soil Group designations are shown as provided by the NRCS for the soil types found on this site. Curve Number (CN) values have been assigned based on the ground cover type and condition, and HSG. The curve number values are weighted according to NRCS criteria and used in the calculations for peak rate attenuation



provided in Appendix C. The Pre-Development and Post-Development Drainage Maps provided in Appendix C show the relationship between the drainage areas and surface cover types.

### Drainage Areas & Curve Numbers

## PRE-DEVELOPMENT

### Drainage Area 1S - Flows to Eastern Wetlands

|                     |  | Hydraulic Soils Group (HSG) Area (sf) & Curve Number (CN) |    |   |    |   |    |         |    |
|---------------------|--|-----------------------------------------------------------|----|---|----|---|----|---------|----|
| Surface Description |  | A                                                         | CN | B | CN | C | CN | D       | CN |
| Meadow, Non-Grazed  |  |                                                           |    |   |    |   |    | 110,204 | 71 |
| Subtotal Area       |  |                                                           |    |   |    |   |    | 110,204 |    |
| Total Area          |  |                                                           |    |   |    |   |    | 110,204 |    |

### Drainage Area 2S - Flows to Eastern Wetlands

|                     |  | Hydraulic Soils Group (HSG) Area (sf) & Curve Number (CN) |    |   |    |   |    |         |    |
|---------------------|--|-----------------------------------------------------------|----|---|----|---|----|---------|----|
| Surface Description |  | A                                                         | CN | B | CN | C | CN | D       | CN |
| Woods, Fair         |  |                                                           |    |   |    |   |    | 148,804 | 73 |
| Subtotal Area       |  |                                                           |    |   |    |   |    | 148,804 |    |
| Total Area          |  |                                                           |    |   |    |   |    | 148,804 |    |

## POST-DEVELOPMENT

### Drainage Area 1S - Flows to Eastern Wetlands

[illegible]

### Drainage Area 5S - Flows to Eastern Wetlands

Drainage Area 55 - Flows to Eastern Wetland

|                     |  | Hydraulic Soils Group (HSG) Area (sf) & Curve Number (CN) |    |   |    |   |    |        |    |
|---------------------|--|-----------------------------------------------------------|----|---|----|---|----|--------|----|
| Surface Description |  | A                                                         | CN | B | CN | C | CN | D      | CN |
| Driveway            |  |                                                           |    |   |    |   |    | 10,727 | 98 |
| Lawn, mulch, stone  |  |                                                           |    |   |    |   |    | 12,065 | 74 |
| Subtotal Area       |  |                                                           |    |   |    |   |    | 22,792 |    |
| Total Area          |  |                                                           |    |   |    |   |    | 22,792 |    |

Drainage Area 7S - Flows to Eastern Wetlands

| Surface Description | Hydraulic Soils Group (HSG) Area (sf) & Curve Number (CN) |    |   |    |   |    |        |    |
|---------------------|-----------------------------------------------------------|----|---|----|---|----|--------|----|
|                     | A                                                         | CN | B | CN | C | CN | D      | CN |
| Woods/Grass combo   |                                                           |    |   |    |   |    | 49,547 | 72 |
| Subtotal Area       |                                                           |    |   |    |   |    | 49,547 |    |
| Total Area          |                                                           |    |   |    |   |    | 49,547 |    |

Drainage Area 8S - Flows to Eastern Wetlands

| Surface Description | Hydraulic Soils Group (HSG) Area (sf) & Curve Number (CN) |    |   |    |   |    |        |    |
|---------------------|-----------------------------------------------------------|----|---|----|---|----|--------|----|
|                     | A                                                         | CN | B | CN | C | CN | D      | CN |
| Woods/Grass combo   |                                                           |    |   |    |   |    | 46,076 | 72 |
| Subtotal Area       |                                                           |    |   |    |   |    | 46,076 |    |
| Total Area          |                                                           |    |   |    |   |    | 46,076 |    |

Drainage Area 9S - Flows to Eastern Wetlands

| Surface Description | Hydraulic Soils Group (HSG) Area (sf) & Curve Number (CN) |    |   |    |   |    |        |    |
|---------------------|-----------------------------------------------------------|----|---|----|---|----|--------|----|
|                     | A                                                         | CN | B | CN | C | CN | D      | CN |
| Roofs               |                                                           |    |   |    |   |    | 4,611  | 98 |
| Driveway            |                                                           |    |   |    |   |    | 8,454  | 98 |
| Woods/Grass combo   |                                                           |    |   |    |   |    | 73,485 | 72 |
| Subtotal Area       |                                                           |    |   |    |   |    | 86,550 |    |
| Total Area          |                                                           |    |   |    |   |    | 86,550 |    |

Drainage Area 11S - Flows to Eastern Wetlands

| Surface Description | Hydraulic Soils Group (HSG) Area (sf) & Curve Number (CN) |    |   |    |   |    |       |    |
|---------------------|-----------------------------------------------------------|----|---|----|---|----|-------|----|
|                     | A                                                         | CN | B | CN | C | CN | D     | CN |
| Woods/Grass combo   |                                                           |    |   |    |   |    | 8,545 | 72 |
| Subtotal Area       |                                                           |    |   |    |   |    | 8,545 |    |
| Total Area          |                                                           |    |   |    |   |    | 8,545 |    |

Drainage Area 12S - Flows to Lot 6 BioRetention Recharge

| Surface Description | Hydraulic Soils Group (HSG) Area (sf) & Curve Number (CN) |    |   |    |   |    |        |    |
|---------------------|-----------------------------------------------------------|----|---|----|---|----|--------|----|
|                     | A                                                         | CN | B | CN | C | CN | D      | CN |
| Grass Cover Good    |                                                           |    |   |    |   |    | 46,955 | 80 |
| Subtotal Area       |                                                           |    |   |    |   |    | 46,955 |    |
| Total               |                                                           |    |   |    |   |    |        |    |

### Peak Flow Rate Attenuation

Once the soils and drainage areas were analyzed and classified, a detailed hydrologic analysis was performed in accordance with the NRCS Technical Release 55 (TR-55) by using the HydroCAD® Stormwater Modeling System. The following tables represent a summary and comparison of the flow and volume between the pre-development and the post-development conditions. The comparison shows that there will be a net decrease in the flow and volume of stormwater runoff from the site after the project is completed. The detailed HydroCAD analysis is provided in Appendix C.

#### Summary of Pre- and Post-Development Peak Flow Rates

##### PRE-DEVELOPMENT (Existing Conditions)

|                                     |        |       |       |       |
|-------------------------------------|--------|-------|-------|-------|
| Type III Storm Event:               | 100-yr | 25-yr | 10-yr | 2-yr  |
| Rainfall (in/24 hr):                | 6.4    | 5.3   | 4.5   | 3.0   |
| <b>FLOW TO EASTERN WETLAND AREA</b> |        |       |       |       |
| Flow Rate (cfs):                    | 20.29  | 14.76 | 10.93 | 5.28  |
| Volume (acre-ft):                   | 1.537  | 1.120 | 0.835 | 0.422 |

##### POST-DEVELOPMENT (Proposed Conditions)

|                                     |        |       |       |       |
|-------------------------------------|--------|-------|-------|-------|
| Type III Storm Event:               | 100-yr | 25-yr | 10-yr | 2-yr  |
| Rainfall (in/24 hr):                | 6.4    | 5.3   | 4.5   | 3.0   |
| <b>FLOW TO EASTERN WETLAND AREA</b> |        |       |       |       |
| Flow Rate (cfs):                    | 13.70  | 8.46  | 5.95  | 3.11  |
| Volume (acre-ft):                   | 2.137  | 1.537 | 1.120 | 0.494 |

##### PRE & POST DEVELOPMENT COMPARISON

|                                   |        |       |       |       |
|-----------------------------------|--------|-------|-------|-------|
| Type III Storm Event:             | 100-yr | 25-yr | 10-yr | 2-yr  |
| Rainfall (in/24 hr):              | 6.4    | 5.3   | 4.5   | 3.0   |
| <b>TOTAL FLOW TO RIVER STREET</b> |        |       |       |       |
| Flow Rate (cfs):                  | -6.59  | -6.30 | -4.98 | -2.17 |
| Volume (acre-ft):                 | 0.600  | 0.417 | 0.285 | 0.72  |

### 4.3 Standard 3: Recharge

Loss of annual recharge to groundwater has been eliminated or minimized by recharging runoff.



## Recharge Volume

### RECHARGE VOLUME REQUIRED

The following calculations show the required volume of runoff that must be recharged to replenish the groundwater supply.

### Required Recharge Volume

Required Recharge Volume,  $R_v = F \times A$ ; where

Target depth factor, F for various NRCS Hydraulic Soil Groups (HSG), is taken from SWM Guidelines, Table 2.3.2 as follows:

| HSG | A    | B    | C    | D    |
|-----|------|------|------|------|
| F   | 0.60 | 0.35 | 0.25 | 0.10 |

Impervious Area, A is from Standard 2

Required Recharge Volume,  $R_v$  is tabulated below

| Drainage Area #               | HSG | F (in) | A (sf)        | $R_v$ (cf) | 2.5% CIA (sf) | Comment |
|-------------------------------|-----|--------|---------------|------------|---------------|---------|
| 1S                            | D   | 0.10   | 15,907        | 133        | 398           |         |
| 5S                            | D   | 0.10   | 11,222        | 94         | 281           |         |
| 7S                            | D   | 0.10   | -             | -          | 0             |         |
| 8S                            | D   | 0.10   | -             | -          | 0             |         |
| 9S                            | D   | 0.10   | 13,065        | 109        | 327           |         |
| 11S                           | D   | 0.10   | -             | -          | 0             |         |
| 12S                           | D   | 0.10   | -             | -          | 0             |         |
| <i>Subtotal</i>               |     |        | <i>40,194</i> | <i>335</i> |               |         |
| <i>Total</i>                  |     |        | <i>40,194</i> | <i>335</i> |               |         |
| <i>Area to be recharged</i>   |     |        | <i>40,194</i> |            |               |         |
| <i>Volume to be recharged</i> |     |        |               | <i>335</i> |               |         |

### RECHARGE VOLUME PROVIDED

The following table shows the total volume of runoff water that will be recharged by the proposed Best Management Practices (BMP's). The total proposed recharge volume exceeds the volume that is required. Detailed design calculations for each BMP are provided in Appendix B.



### **Proposed Recharge Volume**

| Drainage Area # | BMP Description   | Rv (cf)    | Comment  |
|-----------------|-------------------|------------|----------|
| 1S              | None              | -          |          |
| 5S              | None              | -          |          |
| 7S              | None              | -          |          |
| 8S              | None              | -          |          |
| 9S              | None              | -          |          |
| 11S             | None              | -          |          |
| 12S             | BioRetention Cell | 985        |          |
| <b>Subtotal</b> |                   | <b>985</b> |          |
| <b>Total</b>    |                   | <b>985</b> | ; OK>335 |

## **4.4 Standard 4: Water Quality**

Stormwater management systems must remove 80% of the average annual post-construction load of Total Suspended Solids (TSS).

### **Water Quality Volume**

#### **WATER QUALITY VOLUME REQUIRED**

The runoff volume that requires treatment to remove TSS is referred to as the water quality volume.

#### **Required Water Quality Volume**

Water Quality Volume required,  $WQV = d/12 \times I$ ; where

Water Quality runoff depth required,  $d = 0.5$  in

Total impervious area, incl. roof tops,  $I$

The required Water Quality Volume, WQV is tabulated below

| Drainage Area #           | I (sf)        | WQV (cf)     | Comment |
|---------------------------|---------------|--------------|---------|
| 1S                        | 15,907        | 663          |         |
| 5S                        | 11,222        | 468          |         |
| 9S                        | 13,065        | 544          |         |
| <b>Subtotal</b>           | <b>40,194</b> | <b>1,675</b> |         |
| <b>Total</b>              | <b>40,194</b> | <b>1,675</b> |         |
| <b>Area to be treated</b> | <b>40,194</b> |              |         |

### **Proposed Water Quality Volume**

| Drainage Area # | BMP Description                     | WQV (cf) | Comment |
|-----------------|-------------------------------------|----------|---------|
| 1S              | Extended Detention Wetland Basin #1 | 2,259    |         |
| 5S, 7S, 8S      | Extended Detention Wetland Basin #2 | 1,629    |         |

---

*Subtotal*    3,888

---

**Total**    3,888        OK>1675

### ***Total Suspended Solids (TSS)***

#### ***TSS TO BE REMOVED***

Stormwater management systems have been designed to remove 80% of the average annual post-construction load of Total Suspended Solids (TSS) as shown in the Treatment Train Forms Attached.

### ***4.5 Standard 5: Higher Potential Pollutant Loads***

Land Uses with Higher Potential Pollution Loads (LUHPPL) will include source controls and pollution prevention Proprietary Best Management Practices (BMPS) to ensure that the discharge of stormwater runoff from the impervious areas are treated to meet the Standard prior to conveyance to Infiltration BMPS. The project does not classify as a LUHPPL.

### ***4.6 Standard 6: Critical Areas***

Stormwater discharges to critical areas will utilize source controls, pollution prevention measures and approved Best Management Practices (BMP's). There are no stormwater discharges within the Zone II, Interim Wellhead Protection Areas of a public water supply or near an Outstanding Resource Water (ORW) or cold water fishery

### ***4.7 Standard 7: Redevelopment***

The project is proposed as new development due to the separation of the lots. An overall decrease in impervious area is proposed within the developed portion of the two lots.

### ***4.8 Standard 8: Construction Period Controls***

A plan to control construction-related impacts including erosion, sedimentation and other pollutant sources during construction has been developed.

#### ***Erosion Control Plan***

An Erosion Control Plan has been provided within the Site Plan Set

### ***Stormwater Pollution Prevention Plan***

A National Pollution Discharge Elimination System (NPDES) Construction General Permit (CGP) is required for this project. CGP applications are required to be developed and submitted by the Owner/Applicant/Contractor seven (7) days prior to the commencement of construction. Due to the complex nature of this project, the Owner/Applicant will coordinate with this office and the selected contractor for the project to complete the application filing. The application, when filed, will contain a Stormwater Pollution Prevention Plan that will be kept on site and reviewed and updated weekly. The application shall be completed and submitted to the Town of Southborough Conservation Commission thirty (30) days prior to the commencement of construction for review.

### ***4.9 Standard 9: Operation & Maintenance***

A long term operation and maintenance plan has been developed to insure that the stormwater management systems function as designed.

#### ***Operation & Maintenance Manual***

An Operation and Maintenance Manual has been provided under separate cover.

### ***4.10 Standard 10: Illicit Discharges***


There are no known current illicit discharges of wastewater, stormwater contaminated with process wastes, raw materials, toxic pollutants, hazardous substances, oil or grease from the site. The discharge of any of these illicit materials is prohibited from the proposed stormwater management system.

## APPENDICES



## USGS Locus Map

REF.: MassGIS Website



SCALE: Not to Scale

REF.: Tyngsborough Official Website

↑

Site

MAP 47 LOT 126

SCALE: 1" = 50 FT

REF.: Tyngsborough Official Website

↑

Site

MAP 47 LOT 126

SCALE: 1" = 50 FT



REF.: Tyngsborough Official Website

↑

Site

MAP 47 LOT 126

SCALE: 1" = 50 FT

REF.: Tyngsborough Official Website

↑

Site

MAP 47 LOT 126

SCALE: 1" = 50 FT

## Aerial Photography

REF.: MassGIS Website




SCALE: 1" = 100 FT



# NRCS Soil Map

REF.: NRCS Website




**Hydrologic Soil Group**

| Map unit symbol             | Map unit name                                                     | Rating | Acres in AOI | Percent of AOI |
|-----------------------------|-------------------------------------------------------------------|--------|--------------|----------------|
| 71B                         | Ridgebury fine sandy loam, 3 to 8 percent slopes, extremely stony | D      | 3.5          | 26.3%          |
| 305B                        | Paxton fine sandy loam, 3 to 8 percent slopes                     | C      | 0.5          | 3.9%           |
| 310A                        | Woodbridge fine sandy loam, 0 to 3 percent slopes                 | C/D    | 9.2          | 69.8%          |
| Totals for Area of Interest |                                                                   |        | 13.2         | 100.0%         |

SCALE: Not to Scale

DIMENSIONS PRECEDED BY " " ARE CRITICAL AND MAY NOT BE MODIFIED WITHOUT CONSULTING CONTECH






INTERNAL PIPE CONFIGURATION MAY VARY DEPENDING ON VAULT SIZE

### FTBSV CONFIGURATION

| OPTIONS: BASIN "B", GREEN INFRASTRUCTURE INLET "I", PIPE INLET "P", SLOTTED THROAT INLET "T" |                 |                                   |                                    |                             |                 |
|----------------------------------------------------------------------------------------------|-----------------|-----------------------------------|------------------------------------|-----------------------------|-----------------|
| VAULT SIZE (L x W)                                                                           | MEDIA AREA (SF) | LONG SIDE INLET DESIG. / PART NO. | SHORT SIDE INLET DESIG. / PART NO. | AVAILABILITY                | OUTLET PIPE DIA |
| 4 x 4                                                                                        | 16              | FTBSV0404                         | FTBSV0404                          | ALL                         | 4" SDR 35       |
| 5 x 4                                                                                        | 24              | FTBSV0504                         | FTBSV0506                          | ALL                         | 4" SDR 35       |
| 8 x 4                                                                                        | 32              | FTBSV0804                         | FTBSV0408                          | ALL (EXCEPT CA, TX, WA, NY) | 4" SDR 35       |
| 7.83 x 4.5                                                                                   | 35              | FTBSV078045                       | FTBSV045078                        | DE, MO, NJ, PA, VA, WV ONLY | 4" SDR 35       |
| 6 x 6                                                                                        | 36              | FTBSV0606                         | FTBSV0606                          | ALL (EXCEPT CA, TX)         | 4" SDR 35       |
| 8 x 6                                                                                        | 48              | FTBSV0806                         | FTBSV0806                          | ALL                         | 4" SDR 35       |
| 10 x 6                                                                                       | 60              | FTBSV1006                         | FTBSV0610                          | ALL (EXCEPT CA, TX)         | 6" SDR 35       |
| 8 x 8                                                                                        | 64              | FTBSV0808                         | FTBSV0808                          | CA, TX ONLY                 | 6" SDR 35       |
| 12 x 6                                                                                       | 72              | FTBSV1206                         | FTBSV0612                          | ALL (EXCEPT TX)             | 6" SDR 35       |
| 10 x 8                                                                                       | 80              | FTBSV1008                         | FTBSV0810                          | CA, TX ONLY                 | 6" SDR 35       |
| 13 x 7                                                                                       | 91              | FTBSV1307                         | FTBSV0713                          | ALL (EXCEPT CA, TX)         | 6" SDR 35       |
| 12 x 8                                                                                       | 96              | FTBSV1208                         | FTBSV0812                          | CA, TX ONLY                 | 6" SDR 35       |
| 14 x 8                                                                                       | 112             | FTBSV1408 <sup>1</sup>            | N/A                                | ALL                         | 6" SDR 35       |
| 16 x 8                                                                                       | 128             | FTBSV1608 <sup>1</sup>            | N/A                                | ALL (EXCEPT WA)             | 6" SDR 35       |
| 15 x 9                                                                                       | 135             | FTBSV1509 <sup>1</sup>            | N/A                                | OR, WA ONLY                 | 6" SDR 35       |
| 18 x 8                                                                                       | 144             | FTBSV1808 <sup>1</sup>            | N/A                                | CALL CONTECH                | 6" SDR 35       |
| 20 x 8                                                                                       | 160             | FTBSV2008 <sup>1</sup>            | N/A                                | CALL CONTECH                | 6" SDR 35       |
| 22 x 8                                                                                       | 176             | FTBSV2208 <sup>1</sup>            | N/A                                | CALL CONTECH                | 6" SDR 35       |

<sup>1</sup> UTILIZES (2) CURB OPENINGS WITH MIN 1" SPACING



AS WITH ALL OPEN TOP BIORETENTION SYSTEMS, FILTERRA BIOSCAPE IS OPEN TO THE ATMOSPHERE WITH A MEDIA SURFACE RECESSED BELOW FINISHED GRADE. CONTRACTOR OR OWNER IS RESPONSIBLE FOR PROVIDING ANY REQUIRED SAFETY MEASURES AROUND SYSTEM PERIMETER, TO MAINTAIN AESTHETICS, REMOVAL OF HEAVY STORMWATER DEBRIS MAY BE NECESSARY BETWEEN REGULAR FILTERRA SYSTEM MAINTENANCE EVENTS.



This design and installation shall be in accordance with the Filterra Bioscape System Manual, which is available at [www.filterra.com](http://www.filterra.com). The design and installation shall be in accordance with the Filterra Bioscape System Manual, which is available at [www.filterra.com](http://www.filterra.com). The design and installation shall be in accordance with the Filterra Bioscape System Manual, which is available at [www.filterra.com](http://www.filterra.com).

**CONTECH**  
ENGINEERED SOLUTIONS LLC

9100 Centre Pointe Dr., Suite 400, West Chester, OH 45388  
800-338-1122 513-645-7000 513-645-7988 FAX

**FILTERRA BIOSCAPE VAULT STANDARD OFFLINE (FTBSV) CONFIGURATION DETAIL**






9100 Centre Point Dr., Suite 400, West Chester, OH 45389  
800-338-1122 513-545-7000 513-545-7993 FAX

FILTERRA BIOSCAPE VAULT STANDARD OFFLINE (FTBSV)  
SITE LAYOUT DETAIL

This design and specification document is the property of Contech Engineering and Construction, Inc. and is not to be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Contech Engineering and Construction, Inc. The design and specification document is provided for the use of the client and is not to be used for any other purpose. The design and specification document is provided for the use of the client and is not to be used for any other purpose. The design and specification document is provided for the use of the client and is not to be used for any other purpose.

DIMENSIONS PRECEDED BY " " ARE CRITICAL AND MAY NOT BE MODIFIED WITHOUT CONSULTING CONTECH



PLAN VIEW


SECTION A-A

SLOTTED THROAT INLET - TOP EXTENDS 4" ABOVE CURB FOR ADJACENT SIDEWALKS (-T)

| FTBSVIB CONFIGURATION                                                                                  |                 |                                   |                                    |                                          |                                |                        |                               |                                   |  |
|--------------------------------------------------------------------------------------------------------|-----------------|-----------------------------------|------------------------------------|------------------------------------------|--------------------------------|------------------------|-------------------------------|-----------------------------------|--|
| (OPTIONS: BASIN "B", GREEN INFRASTRUCTURE (GI) INLET "-I", PIPE INLET "-P", SLOTTED THROAT INLET "-T") |                 |                                   |                                    |                                          |                                |                        |                               |                                   |  |
| VAULT SIZE (L x W)                                                                                     | MEDIA AREA (SF) | LONG SIDE INLET DESIG. / PART NO. | SHORT SIDE INLET DESIG. / PART NO. | AVAILABILITY                             | MAX. OUTLET / BYPASS PIPE DIA. | MAX. BYPASS FLOW (CFS) | UNDER- DRAIN PIPE DIA. (PERF) | MIN. NO. OF INLET PIPES (-P ONLY) |  |
| 4 x 4                                                                                                  | 16              | FTBSVIB0404                       | FTBSVIB0404                        | ALL                                      | 8" SDR 35                      | 1.42                   | 4" SDR 35                     | 1                                 |  |
| 8 x 4                                                                                                  | 24              | FTBSVIB0604                       | FTBSVIB0604                        | ALL                                      | 8" SDR 35                      | 1.89                   | 4" SDR 35                     | 1                                 |  |
| 8 x 4                                                                                                  | 32              | FTBSVIB0804                       | FTBSVIB0804                        | ALL (EXCEPT DE, MO, NJ, PA, VA, WV ONLY) | 8" SDR 35                      | 1.89                   | 4" SDR 35                     | 1                                 |  |
| 7.83 x 4.5                                                                                             | 35              | FTBSVIB078045                     | FTBSVIB045078                      | DE, MO, NJ, PA, VA, WV ONLY              | 8" SDR 35                      | 1.89                   | 4" SDR 35                     | 1                                 |  |
| 8 x 6                                                                                                  | 36              | FTBSVIB0606                       | FTBSVIB0606                        | ALL (EXCEPT CA, TX)                      | 8" SDR 35                      | 2.37                   | 4" SDR 35                     | 1                                 |  |
| 8 x 6                                                                                                  | 48              | FTBSVIB0806                       | FTBSVIB0608                        | ALL                                      | 10" SDR 35                     | 2.37                   | 4" SDR 35                     | 1                                 |  |
| 10 x 6                                                                                                 | 60              | FTBSVIB1006                       | FTBSVIB0810                        | ALL (EXCEPT CA, TX)                      | 10" SDR 35                     | 2.37                   | 6" SDR 35                     | 2                                 |  |
| 8 x 8                                                                                                  | 64              | FTBSVIB0808                       | FTBSVIB0608                        | CA, TX ONLY                              | 10" SDR 35                     | 2.37                   | 6" SDR 35                     | 2                                 |  |
| 12 x 6                                                                                                 | 72              | FTBSVIB1206                       | FTBSVIB0612                        | ALL (EXCEPT TX)                          | 10" SDR 35                     | 2.37                   | 6" SDR 35                     | 2                                 |  |
| 10 x 8                                                                                                 | 80              | FTBSVIB1008                       | FTBSVIB0810                        | CA, TX ONLY                              | 10" SDR 35                     | 2.37                   | 6" SDR 35                     | 2                                 |  |
| 13 x 7                                                                                                 | 91              | FTBSVIB1307                       | FTBSVIB0713                        | ALL (EXCEPT CA, TX)                      | 10" SDR 35                     | 2.37                   | 6" SDR 35                     | 2                                 |  |
| 12 x 8                                                                                                 | 96              | FTBSVIB1208                       | FTBSVIB0812                        | CA, TX ONLY                              | 10" SDR 35                     | 2.37                   | 6" SDR 35                     | 2                                 |  |
| 14 x 8                                                                                                 | 112             | FTBSVIB1408                       | N/A                                | ALL                                      | 10" SDR 35                     | 2.37                   | 6" SDR 35                     | 3                                 |  |
| 16 x 8                                                                                                 | 128             | FTBSVIB1608 <sup>1</sup>          | N/A                                | ALL (EXCEPT OR, WA)                      | 10" SDR 35                     | 2.37                   | 6" SDR 35                     | 3                                 |  |
| 15 x 9                                                                                                 | 135             | FTBSVIB1509 <sup>1</sup>          | N/A                                | OR, WA ONLY                              | 10" SDR 35                     | 2.37                   | 6" SDR 35                     | 3                                 |  |
| 18 x 8                                                                                                 | 144             | FTBSVIB1808 <sup>1</sup>          | N/A                                | CALL CONTECH                             | 10" SDR 35                     | 2.37                   | 6" SDR 35                     | 3                                 |  |
| 20 x 8                                                                                                 | 160             | FTBSVIB2008 <sup>1</sup>          | N/A                                | CALL CONTECH                             | 10" SDR 35                     | 2.37                   | 6" SDR 35                     | 4                                 |  |
| 22 x 8                                                                                                 | 176             | FTBSVIB2208 <sup>1</sup>          | N/A                                | CALL CONTECH                             | 10" SDR 35                     | 2.37                   | 6" SDR 35                     | 4                                 |  |


<sup>1</sup>UTILIZES (2) CURB OPENINGS WITH MIN 1" SPACING

INTERNAL PIPE CONFIGURATION MAY VARY DEPENDING ON VAULT SIZE




SECTION A-A

GREEN INFRASTRUCTURE INLET - TOP FLUSH WITH TOP OF CURB, NOT INTENDED FOR SIDEWALK APPLICATIONS (-I)



SECTION A-A

BASIN - CURB INLET OR PIPE INLETS OPTIONAL (-B)



SECTION A-A

PIPE INLET (-P)

AS WITH ALL OPEN TOP BIORETENTION SYSTEMS, FILTERRA BIOSCAPE IS OPEN TO THE ATMOSPHERE WITH A MEDIA SURFACE RECESSED BELOW FINISHED GRADE. CONTRACTOR OR OWNER IS RESPONSIBLE FOR PROVIDING ANY REQUIRED SAFETY MEASURES AROUND SYSTEM PERIMETER. TO MAINTAIN AESTHETICS, REMOVAL OF HEAVY STORMWATER DEBRIS MAY BE NECESSARY TO MAINTAIN REGULAR FILTERRA SYSTEM MAINTENANCE EVENTS.




**CONTECH**  
ENGINEERED SOLUTIONS LLC


www.contech-engineering.com  
8100 Centre Pointe Dr., Suite 400, West Chester, OH 45388  
800-338-1122 912-695-7000 912-695-7993 FAX

The design and construction shown on this drawing is intended to be a general guide. The engineer, designer, and contractor shall be responsible for all details and specifications. The engineer, designer, and contractor shall be responsible for all details and specifications. The engineer, designer, and contractor shall be responsible for all details and specifications.



Filterra is a registered trademark of Contech Engineering Solutions LLC. All other trademarks are the property of their respective owners. ©2023 Contech Engineering Solutions LLC. All rights reserved.




**FTBSVIB - A**  
SLOTTED THROAT INLET - TOP EXTENDS 4"  
ABOVE CURB FOR ADJACENT SIDEWALKS



**FTBSVIB - I**  
GREEN INFRASTRUCTURE INLET - TOP  
FLUSH WITH TOP OF CURB, NOT INTENDED  
FOR SIDEWALK APPLICATIONS



**FTBSVIB - B**  
BASIN - CURB INLET OR PIPE INLET OPTIONAL



**FTBSVIB - P**  
PIPE INLET



FOR INLET INFORMATION, GO TO WWW.CONTECHES.COM

**CONTECH**  
ENGINEERED SOLUTIONS LLC  
www.conteches.com

9100 Centre Pointe Dr., Suite 400, West Chester, OH 45069  
800-338-1122 513-945-7000 513-945-7981 FAX

**FILTERRA BIOSCAPE VAULT INTERNAL BYPASS  
(FTBSVIB)  
SITE LAYOUT DETAIL**

The design and information shown on this drawing is provided as a service to the project owner. Engineer will not be responsible for any errors or omissions in the design or information shown on this drawing. The user of this drawing is responsible for verifying the accuracy of the information shown on this drawing. The user of this drawing is responsible for obtaining all necessary permits and approvals for the project. The user of this drawing is responsible for ensuring that the project is completed in accordance with all applicable laws and regulations. The user of this drawing is responsible for ensuring that the project is completed in accordance with all applicable laws and regulations. The user of this drawing is responsible for ensuring that the project is completed in accordance with all applicable laws and regulations.

### ***C.1: Pre-Development Analysis***

[ Existing Watershed Plan & HydroCAD calculations ]





DP#1-GREENMONT



DP#2-REAR  
WETLANDS



**Routing Diagram for Ex-Conditions**

Prepared by Cornerstone Land Associates, LLC, Printed 6/1/2023  
HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

## Ex-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 2


### Summary for Subcatchment 1S: DP#1-GREENMONT

Runoff = 0.62 cfs @ 12.00 hrs, Volume= 0.036 af, Depth> 1.79"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
Type III 24-hr 2-YR Rainfall=3.20"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 981       | 98 | Roofs, HSG D                  |
| 2,843     | 98 | Paved parking, HSG D          |
| 6,585     | 80 | >75% Grass cover, Good, HSG D |
| 10,409    | 87 | Weighted Average              |
| 6,585     |    | 63.26% Pervious Area          |
| 3,824     |    | 36.74% Impervious Area        |

### Subcatchment 1S: DP#1-GREENMONT



## Ex-Conditions

Prepared by Cornerstone Land Associates, LLC  
HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 3


### Summary for Subcatchment 2S: DP#2-REAR WETLANDS

Runoff = 4.35 cfs @ 12.01 hrs, Volume= 0.251 af, Depth> 1.36"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
Type III 24-hr 2-YR Rainfall=3.20"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 1,008     | 98 | Roofs, HSG D                  |
| 4,356     | 98 | Paved parking, HSG D          |
| 90,993    | 80 | >75% Grass cover, Good, HSG D |
| 96,357    | 81 | Weighted Average              |
| 90,993    |    | 94.43% Pervious Area          |
| 5,364     |    | 5.57% Impervious Area         |

### Subcatchment 2S: DP#2-REAR WETLANDS





## Ex-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 4

### Summary for Subcatchment 1S: DP#1-GREENMONT


Runoff = 0.81 cfs @ 12.00 hrs, Volume= 0.048 af, Depth> 2.39"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type III 24-hr 5-YR Rainfall=3.90"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 981       | 98 | Roofs, HSG D                  |
| 2,843     | 98 | Paved parking, HSG D          |
| 6,585     | 80 | >75% Grass cover, Good, HSG D |
| 10,409    | 87 | Weighted Average              |
| 6,585     |    | 63.26% Pervious Area          |
| 3,824     |    | 36.74% Impervious Area        |

### Subcatchment 1S: DP#1-GREENMONT



## Ex-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 5


### Summary for Subcatchment 2S: DP#2-REAR WETLANDS

Runoff = 6.07 cfs @ 12.00 hrs, Volume= 0.350 af, Depth> 1.90"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
Type III 24-hr 5-YR Rainfall=3.90"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 1,008     | 98 | Roofs, HSG D                  |
| 4,356     | 98 | Paved parking, HSG D          |
| 90,993    | 80 | >75% Grass cover, Good, HSG D |
| 96,357    | 81 | Weighted Average              |
| 90,993    |    | 94.43% Pervious Area          |
| 5,364     |    | 5.57% Impervious Area         |

### Subcatchment 2S: DP#2-REAR WETLANDS





## Ex-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 6


### Summary for Subcatchment 1S: DP#1-GREENMONT

Runoff = 0.98 cfs @ 12.00 hrs, Volume= 0.058 af, Depth> 2.92"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-YR Rainfall=4.50"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 981       | 98 | Roofs, HSG D                  |
| 2,843     | 98 | Paved parking, HSG D          |
| 6,585     | 80 | >75% Grass cover, Good, HSG D |
| 10,409    | 87 | Weighted Average              |
| 6,585     |    | 63.26% Pervious Area          |
| 3,824     |    | 36.74% Impervious Area        |

### Subcatchment 1S: DP#1-GREENMONT



## Ex-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 7


### Summary for Subcatchment 2S: DP#2-REAR WETLANDS

Runoff = 7.60 cfs @ 12.00 hrs, Volume= 0.439 af, Depth> 2.38"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-YR Rainfall=4.50"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 1,008     | 98 | Roofs, HSG D                  |
| 4,356     | 98 | Paved parking, HSG D          |
| 90,993    | 80 | >75% Grass cover, Good, HSG D |
| 96,357    | 81 | Weighted Average              |
| 90,993    |    | 94.43% Pervious Area          |
| 5,364     |    | 5.57% Impervious Area         |

### Subcatchment 2S: DP#2-REAR WETLANDS



## Ex-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 8


### Summary for Subcatchment 1S: DP#1-GREENMONT

Runoff = 1.21 cfs @ 12.00 hrs, Volume= 0.072 af, Depth> 3.64"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-YR Rainfall=5.30"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 981       | 98 | Roofs, HSG D                  |
| 2,843     | 98 | Paved parking, HSG D          |
| 6,585     | 80 | >75% Grass cover, Good, HSG D |
| 10,409    | 87 | Weighted Average              |
| 6,585     |    | 63.26% Pervious Area          |
| 3,824     |    | 36.74% Impervious Area        |

### Subcatchment 1S: DP#1-GREENMONT





## Ex-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 9


### Summary for Subcatchment 2S: DP#2-REAR WETLANDS

Runoff = 9.66 cfs @ 12.00 hrs, Volume= 0.562 af, Depth> 3.05"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-YR Rainfall=5.30"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 1,008     | 98 | Roofs, HSG D                  |
| 4,356     | 98 | Paved parking, HSG D          |
| 90,993    | 80 | >75% Grass cover, Good, HSG D |
| 96,357    | 81 | Weighted Average              |
| 90,993    |    | 94.43% Pervious Area          |
| 5,364     |    | 5.57% Impervious Area         |

### Subcatchment 2S: DP#2-REAR WETLANDS





## Ex-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 10

### Summary for Subcatchment 1S: DP#1-GREENMONT


Runoff = 1.38 cfs @ 12.00 hrs, Volume= 0.083 af, Depth> 4.18"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type III 24-hr 50-YR Rainfall=5.90"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 981       | 98 | Roofs, HSG D                  |
| 2,843     | 98 | Paved parking, HSG D          |
| 6,585     | 80 | >75% Grass cover, Good, HSG D |
| 10,409    | 87 | Weighted Average              |
| 6,585     |    | 63.26% Pervious Area          |
| 3,824     |    | 36.74% Impervious Area        |

### Subcatchment 1S: DP#1-GREENMONT



## Ex-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 11

### Summary for Subcatchment 2S: DP#2-REAR WETLANDS


Runoff = 11.23 cfs @ 12.00 hrs, Volume= 0.657 af, Depth> 3.56"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type III 24-hr 50-YR Rainfall=5.90"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 1,008     | 98 | Roofs, HSG D                  |
| 4,356     | 98 | Paved parking, HSG D          |
| 90,993    | 80 | >75% Grass cover, Good, HSG D |
| 96,357    | 81 | Weighted Average              |
| 90,993    |    | 94.43% Pervious Area          |
| 5,364     |    | 5.57% Impervious Area         |

### Subcatchment 2S: DP#2-REAR WETLANDS



**Ex-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023


Page 12

**Summary for Subcatchment 1S: DP#1-GREENMONT**

Runoff = 1.52 cfs @ 12.00 hrs, Volume= 0.092 af, Depth&gt; 4.64"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs  
Type III 24-hr 100-YR Rainfall=6.40"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 981       | 98 | Roofs, HSG D                  |
| 2,843     | 98 | Paved parking, HSG D          |
| 6,585     | 80 | >75% Grass cover, Good, HSG D |
| 10,409    | 87 | Weighted Average              |
| 6,585     |    | 63.26% Pervious Area          |
| 3,824     |    | 36.74% Impervious Area        |

**Subcatchment 1S: DP#1-GREENMONT**



## Ex-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 13

### Summary for Subcatchment 2S: DP#2-REAR WETLANDS


Runoff = 12.54 cfs @ 12.00 hrs, Volume= 0.737 af, Depth> 4.00"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Type III 24-hr 100-YR Rainfall=6.40"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 1,008     | 98 | Roofs, HSG D                  |
| 4,356     | 98 | Paved parking, HSG D          |
| 90,993    | 80 | >75% Grass cover, Good, HSG D |
| 96,357    | 81 | Weighted Average              |
| 90,993    |    | 94.43% Pervious Area          |
| 5,364     |    | 5.57% Impervious Area         |


### Subcatchment 2S: DP#2-REAR WETLANDS





## ***C.2: Post-Development Analysis***

[ Proposed Watershed Plan & HydroCAD calculations ]



Subcat



Reach



Pond



Link

**Routing Diagram for Prop-Conditions**  
 Prepared by Cornerstone Land Associates, LLC, Printed 6/1/2023  
 HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 2


### Summary for Subcatchment 1S: DP#1-GREENMONT

Runoff = 0.11 cfs @ 12.00 hrs, Volume= 0.007 af, Depth= 1.76"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 2-YR Rainfall=3.20"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 569       | 98 | Paved parking, HSG D          |
| 1,380     | 80 | >75% Grass cover, Good, HSG D |
| 1,949     | 85 | Weighted Average              |
| 1,380     |    | 70.81% Pervious Area          |
| 569       |    | 29.19% Impervious Area        |

### Subcatchment 1S: DP#1-GREENMONT



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 3

**Summary for Subcatchment 3S: PWS#2**

Runoff = 0.37 cfs @ 12.07 hrs, Volume= 0.027 af, Depth= 2.45"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 2-YR Rainfall=3.20"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 4,094     | 98 | Paved parking, HSG D          |
| 1,678     | 80 | >75% Grass cover, Good, HSG D |
| 5,772     | 93 | Weighted Average              |
| 1,678     |    | 29.07% Pervious Area          |
| 4,094     |    | 70.93% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 3S: PWS#2**

Hydrograph





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 4

**Summary for Subcatchment 5S: ROOFS 15 - 28**

Runoff = 0.72 cfs @ 12.07 hrs, Volume= 0.057 af, Depth= 2.97"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 2-YR Rainfall=3.20"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 10,080    | 98 | Roofs, HSG D            |
| 10,080    |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 5S: ROOFS 15 - 28**

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 5


**Summary for Subcatchment 6S: PWS#3**

Runoff = 1.06 cfs @ 12.08 hrs, Volume= 0.076 af, Depth= 1.40"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 2-YR Rainfall=3.20"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 18,244    | 80 | >75% Grass cover, Good, HSG D |
| * 10,097  | 80 |                               |
| 28,341    | 80 | Weighted Average              |
| 28,341    |    | 100.00% Pervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 6S: PWS#3**



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 6

### Summary for Subcatchment 7S: PWS#4

Runoff = 0.54 cfs @ 12.07 hrs, Volume= 0.043 af, Depth= 2.97"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 2-YR Rainfall=3.20"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 7,586     | 98 | Paved parking, HSG D    |
| 7,586     |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 7S: PWS#4



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 7

**Summary for Subcatchment 9S: PWS#5**

Runoff = 0.37 cfs @ 12.07 hrs, Volume= 0.027 af, Depth= 2.45"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 2-YR Rainfall=3.20"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 4,090     | 98 | Paved parking, HSG D          |
| 1,677     | 80 | >75% Grass cover, Good, HSG D |
| 5,767     | 93 | Weighted Average              |
| 1,677     |    | 29.08% Pervious Area          |
| 4,090     |    | 70.92% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 9S: PWS#5**

Hydrograph





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 8

**Summary for Subcatchment 11S: PWS#6**


Runoff = 1.12 cfs @ 12.08 hrs, Volume= 0.080 af, Depth= 1.40"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 2-YR Rainfall=3.20"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 21,412    | 80 | >75% Grass cover, Good, HSG D |
| * 8,403   | 80 |                               |
| 29,815    | 80 | Weighted Average              |
| 29,815    |    | 100.00% Pervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 11S: PWS#6**

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 9

### Summary for Subcatchment 13S: PWS#7


Runoff = 0.53 cfs @ 12.07 hrs, Volume= 0.042 af, Depth= 2.97"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 2-YR Rainfall=3.20"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 7,376     | 98 | Paved parking, HSG D    |
| 7,376     |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 13S: PWS#7





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 10

**Summary for Subcatchment 18S: ROOFS 1 - 14**

Runoff = 0.72 cfs @ 12.07 hrs, Volume= 0.057 af, Depth= 2.97"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 2-YR Rainfall=3.20"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 10,080    | 98 | Roofs, HSG D            |
| 10,080    |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 18S: ROOFS 1 - 14**

Hydrograph



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 11

### Summary for Reach 4R: GRASS LINED SWALE #1

Inflow Area = 1.015 ac, 32.07% Impervious, Inflow Depth = 1.22" for 2-YR event  
Inflow = 1.54 cfs @ 12.10 hrs, Volume= 0.103 af  
Outflow = 1.38 cfs @ 12.21 hrs, Volume= 0.103 af, Atten= 10%, Lag= 6.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.36 fps, Min. Travel Time= 3.4 min

Avg. Velocity = 0.42 fps, Avg. Travel Time= 11.0 min

Peak Storage= 282 cf @ 12.15 hrs

Average Depth at Peak Storage= 0.18'

Bank-Full Depth= 1.00' Flow Area= 14.0 sf, Capacity= 50.43 cfs

4.00' x 1.00' deep channel, n= 0.030 Earth, grassed & winding

Side Slope Z-value= 10.0 '/' Top Width= 24.00'


Length= 275.0' Slope= 0.0109 '/'

Inlet Invert= 99.00', Outlet Invert= 96.00'



### Reach 4R: GRASS LINED SWALE #1

Hydrograph





## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC  
HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 12

### Summary for Reach 12R: GRASS LINED SWALE #2

Inflow Area = 1.048 ac, 31.03% Impervious, Inflow Depth = 1.23" for 2-YR event  
Inflow = 1.60 cfs @ 12.10 hrs, Volume= 0.107 af  
Outflow = 1.43 cfs @ 12.20 hrs, Volume= 0.107 af, Atten= 10%, Lag= 6.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Max. Velocity= 1.35 fps, Min. Travel Time= 3.3 min  
Avg. Velocity = 0.42 fps, Avg. Travel Time= 10.7 min


Peak Storage= 289 cf @ 12.15 hrs  
Average Depth at Peak Storage= 0.18'  
Bank-Full Depth= 1.00' Flow Area= 15.5 sf, Capacity= 55.70 cfs

4.00' x 1.00' deep channel, n= 0.030 Earth, grassed & winding  
Side Slope Z-value= 4.0 19.0 '/' Top Width= 27.00'  
Length= 270.0' Slope= 0.0111 '/'  
Inlet Invert= 99.00', Outlet Invert= 96.00'



### Reach 12R: GRASS LINED SWALE #2

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC  
 HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 13

### Summary for Pond 8P: DETENTION POND #1

Inflow Area = 1.189 ac, 42.02% Impervious, Inflow Depth = 1.47" for 2-YR event  
 Inflow = 1.68 cfs @ 12.19 hrs, Volume= 0.145 af  
 Outflow = 0.09 cfs @ 15.64 hrs, Volume= 0.142 af, Atten= 95%, Lag= 207.3 min  
 Discarded = 0.09 cfs @ 15.64 hrs, Volume= 0.142 af  
 Primary = 0.00 cfs @ 0.10 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 94.62' @ 15.64 hrs Surf.Area= 3,002 sf Storage= 3,700 cf

Plug-Flow detention time= 498.3 min calculated for 0.142 af (98% of inflow)  
 Center-of-Mass det. time= 486.1 min ( 1,306.0 - 820.0 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 93.00' | 8,773 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 93.00               | 1,640                | 257.0            | 0                         | 0                         | 1,640               |
| 94.00               | 2,440                | 276.0            | 2,027                     | 2,027                     | 2,489               |
| 95.00               | 3,381                | 308.0            | 2,898                     | 4,925                     | 4,004               |
| 96.00               | 4,335                | 329.0            | 3,848                     | 8,773                     | 5,115               |

| Device | Routing   | Invert | Outlet Devices                                                                                                                                                                                                                                               |
|--------|-----------|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | Primary   | 95.50' | <b>6.0' long x 3.0' breadth Broad-Crested Rectangular Weir</b><br>Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00<br>2.50 3.00 3.50 4.00 4.50<br>Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68<br>2.72 2.81 2.92 2.97 3.07 3.32 |
| #2     | Primary   | 94.75' | <b>6.0" Vert. Orifice/Grate C= 0.600</b>                                                                                                                                                                                                                     |
| #3     | Discarded | 93.00' | <b>1.080 in/hr Exfiltration over Wetted area</b>                                                                                                                                                                                                             |

**Discarded OutFlow** Max=0.09 cfs @ 15.64 hrs HW=94.62' (Free Discharge)  
 ↳ **3=Exfiltration** (Exfiltration Controls 0.09 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.10 hrs HW=93.00' (Free Discharge)  
 ↳ **1=Broad-Crested Rectangular Weir** ( Controls 0.00 cfs)  
 ↳ **2=Orifice/Grate** ( Controls 0.00 cfs)

**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 14

**Pond 8P: DETENTION POND #1**

Hydrograph



**Prop-Conditions**

Type III 24-hr 2-YR Rainfall=3.20"

Prepared by Cornerstone Land Associates, LLC

Printed 6/1/2023

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Page 15

**Summary for Pond 14P: DETENTION POND #2**

Inflow Area = 1.218 ac, 40.62% Impervious, Inflow Depth = 1.46" for 2-YR event  
 Inflow = 1.72 cfs @ 12.19 hrs, Volume= 0.148 af  
 Outflow = 0.43 cfs @ 12.66 hrs, Volume= 0.095 af, Atten= 75%, Lag= 28.6 min  
 Discarded = 0.01 cfs @ 12.66 hrs, Volume= 0.012 af  
 Primary = 0.43 cfs @ 12.66 hrs, Volume= 0.083 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 95.07' @ 12.66 hrs Surf.Area= 2,281 sf Storage= 3,170 cf

Plug-Flow detention time= 257.3 min calculated for 0.095 af (64% of inflow)  
 Center-of-Mass det. time= 157.4 min ( 978.6 - 821.2 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 93.00' | 5,654 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 93.00               | 933                  | 130.0            | 0                         | 0                         | 933                 |
| 94.00               | 1,451                | 245.0            | 1,183                     | 1,183                     | 4,370               |
| 95.00               | 2,221                | 267.0            | 1,822                     | 3,005                     | 5,302               |
| 96.00               | 3,102                | 296.0            | 2,649                     | 5,654                     | 6,632               |

| Device | Routing   | Invert | Outlet Devices                                    |
|--------|-----------|--------|---------------------------------------------------|
| #1     | Primary   | 94.75' | <b>12.0" Vert. Orifice/Grate</b> C= 0.600         |
| #2     | Discarded | 93.00' | <b>0.110 in/hr Exfiltration over Surface area</b> |

**Discarded OutFlow** Max=0.01 cfs @ 12.66 hrs HW=95.07' (Free Discharge)  
 ↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.42 cfs @ 12.66 hrs HW=95.07' (Free Discharge)  
 ↑ **1=Orifice/Grate** (Orifice Controls 0.42 cfs @ 1.93 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 16

### Pond 14P: DETENTION POND #2



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 17

**Summary for Pond 20P: RECHARGE 1 - 8**

Inflow Area = 0.231 ac, 100.00% Impervious, Inflow Depth = 2.97" for 2-YR event  
 Inflow = 0.72 cfs @ 12.07 hrs, Volume = 0.057 af  
 Outflow = 0.55 cfs @ 12.15 hrs, Volume = 0.047 af, Atten = 24%, Lag = 4.5 min  
 Discarded = 0.01 cfs @ 12.15 hrs, Volume = 0.020 af  
 Primary = 0.54 cfs @ 12.15 hrs, Volume = 0.027 af

Routing by Stor-Ind method, Time Span = 0.10-36.00 hrs, dt = 0.05 hrs

Peak Elev = 99.33' @ 12.15 hrs Surf.Area = 540 sf Storage = 933 cf

Plug-Flow detention time = 286.7 min calculated for 0.047 af (83% of inflow)

Center-of-Mass det. time = 216.6 min ( 972.1 - 755.5 )

| Volume | Invert | Avail.Storage | Storage Description                                                                                                                                                                                                       |
|--------|--------|---------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | 96.50' | 646 cf        | <b>12.00'W x 45.00'L x 4.00'H Prismaoid</b><br>2,160 cf Overall - 544 cf Embedded = 1,616 cf x 40.0% Voids                                                                                                                |
| #2     | 97.00' | 544 cf        | <b>Cultec R-330XL</b> x 10 Inside #1<br>Effective Size = 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf<br>Overall Size = 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap<br>Row Length Adjustment = +1.50' x 7.45 sf x 2 rows |
|        |        | 1,190 cf      | Total Available Storage                                                                                                                                                                                                   |

| Device | Routing   | Invert | Outlet Devices                                   |
|--------|-----------|--------|--------------------------------------------------|
| #1     | Primary   | 98.75' | <b>6.0" Vert. Orifice/Grate</b> C = 0.600        |
| #2     | Discarded | 96.50' | <b>0.440 in/hr Exfiltration over Wetted area</b> |

**Discarded OutFlow** Max = 0.01 cfs @ 12.15 hrs HW = 99.32' (Free Discharge)↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max = 0.54 cfs @ 12.15 hrs HW = 99.32' (Free Discharge)↑ **1=Orifice/Grate** (Orifice Controls 0.54 cfs @ 2.73 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 18

### Pond 20P: RECHARGE 1 - 8

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 19

**Summary for Pond 23P: RECHARGE 15-28**

Inflow Area = 0.231 ac, 100.00% Impervious, Inflow Depth = 2.97" for 2-YR event  
 Inflow = 0.72 cfs @ 12.07 hrs, Volume = 0.057 af  
 Outflow = 0.55 cfs @ 12.15 hrs, Volume = 0.047 af, Atten = 24%, Lag = 4.5 min  
 Discarded = 0.01 cfs @ 12.15 hrs, Volume = 0.020 af  
 Primary = 0.54 cfs @ 12.15 hrs, Volume = 0.027 af

Routing by Stor-Ind method, Time Span = 0.10-36.00 hrs, dt = 0.05 hrs

Peak Elev = 99.33' @ 12.15 hrs Surf.Area = 540 sf Storage = 933 cf

Plug-Flow detention time = 286.7 min calculated for 0.047 af (83% of inflow)

Center-of-Mass det. time = 216.6 min ( 972.1 - 755.5 )

| Volume | Invert | Avail.Storage | Storage Description                                                                                                                                                                                                       |
|--------|--------|---------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | 96.50' | 646 cf        | <b>12.00'W x 45.00'L x 4.00'H Prismaoid</b><br>2,160 cf Overall - 544 cf Embedded = 1,616 cf x 40.0% Voids                                                                                                                |
| #2     | 97.00' | 544 cf        | <b>Cultec R-330XL</b> x 10 Inside #1<br>Effective Size = 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf<br>Overall Size = 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap<br>Row Length Adjustment = +1.50' x 7.45 sf x 2 rows |
|        |        | 1,190 cf      | Total Available Storage                                                                                                                                                                                                   |

| Device | Routing   | Invert | Outlet Devices                                   |
|--------|-----------|--------|--------------------------------------------------|
| #1     | Primary   | 98.75' | <b>6.0" Vert. Orifice/Grate</b> C = 0.600        |
| #2     | Discarded | 96.50' | <b>0.440 in/hr Exfiltration over Wetted area</b> |

**Discarded OutFlow** Max = 0.01 cfs @ 12.15 hrs HW = 99.32' (Free Discharge)↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max = 0.54 cfs @ 12.15 hrs HW = 99.32' (Free Discharge)↑ **1=Orifice/Grate** (Orifice Controls 0.54 cfs @ 2.73 fps)



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 20

**Pond 23P: RECHARGE 15-28**

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 21

**Summary for Pond 25P: BIORETENTION BASIN**

Inflow Area = 0.133 ac, 70.93% Impervious, Inflow Depth = 2.45" for 2-YR event  
 Inflow = 0.37 cfs @ 12.07 hrs, Volume= 0.027 af  
 Outflow = 0.00 cfs @ 8.65 hrs, Volume= 0.007 af, Atten= 99%, Lag= 0.0 min  
 Discarded = 0.00 cfs @ 8.65 hrs, Volume= 0.007 af  
 Primary = 0.00 cfs @ 0.10 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Peak Elev= 98.78' @ 24.03 hrs Surf.Area= 302 sf Storage= 991 cf

Plug-Flow detention time= 659.2 min calculated for 0.007 af (27% of inflow)

Center-of-Mass det. time= 507.3 min ( 1,299.0 - 791.7 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.50' | 1,538 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 95.50               | 302                  | 122.0            | 0                         | 0                         | 302                 |
| 96.00               | 302                  | 122.0            | 151                       | 151                       | 363                 |
| 98.75               | 302                  | 122.0            | 831                       | 982                       | 699                 |
| 99.00               | 302                  | 122.0            | 76                        | 1,057                     | 729                 |
| 100.00              | 685                  | 146.0            | 481                       | 1,538                     | 1,258               |

| Device | Routing   | Invert | Outlet Devices                                                                                         |
|--------|-----------|--------|--------------------------------------------------------------------------------------------------------|
| #1     | Primary   | 99.75' | <b>2.0' long x 2.00' rise Sharp-Crested Rectangular Weir</b><br>2 End Contraction(s) 0.7' Crest Height |
| #2     | Discarded | 95.50' | <b>0.440 in/hr Exfiltration over Surface area</b>                                                      |

**Discarded OutFlow** Max=0.00 cfs @ 8.65 hrs HW=95.56' (Free Discharge)↑**2=Exfiltration** (Exfiltration Controls 0.00 cfs)**Primary OutFlow** Max=0.00 cfs @ 0.10 hrs HW=95.50' (Free Discharge)↑**1=Sharp-Crested Rectangular Weir** ( Controls 0.00 cfs)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 22

### Pond 25P: BIORETENTION BASIN

Hydrograph



**Prop-Conditions**

Type III 24-hr 2-YR Rainfall=3.20"

Prepared by Cornerstone Land Associates, LLC

Printed 6/1/2023

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Page 23

**Summary for Pond 26P: BIORETENTION BASIN**

Inflow Area = 0.132 ac, 70.92% Impervious, Inflow Depth = 2.45" for 2-YR event  
 Inflow = 0.37 cfs @ 12.07 hrs, Volume= 0.027 af  
 Outflow = 0.01 cfs @ 17.60 hrs, Volume= 0.014 af, Atten= 98%, Lag= 331.7 min  
 Discarded = 0.01 cfs @ 17.60 hrs, Volume= 0.014 af  
 Primary = 0.00 cfs @ 0.10 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Peak Elev= 99.53' @ 17.60 hrs Surf.Area= 736 sf Storage= 844 cf

Plug-Flow detention time= 612.0 min calculated for 0.014 af (53% of inflow)

Center-of-Mass det. time= 502.3 min ( 1,294.0 - 791.7 )

| Volume              | Invert               | Avail.Storage    | Storage Description                                        |                           |                           |                     |
|---------------------|----------------------|------------------|------------------------------------------------------------|---------------------------|---------------------------|---------------------|
| #1                  | 95.50'               | 2,456 cf         | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |                           |                           |                     |
| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Voids<br>(%)                                               | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
| 95.50               | 425                  | 167.0            | 0.0                                                        | 0                         | 0                         | 425                 |
| 96.00               | 425                  | 167.0            | 40.0                                                       | 85                        | 85                        | 509                 |
| 98.75               | 425                  | 167.0            | 30.0                                                       | 351                       | 436                       | 968                 |
| 99.00               | 425                  | 167.0            | 100.0                                                      | 106                       | 542                       | 1,010               |
| 100.00              | 1,088                | 213.0            | 100.0                                                      | 731                       | 1,273                     | 2,413               |
| 101.00              | 1,281                | 181.0            | 100.0                                                      | 1,183                     | 2,456                     | 3,436               |

| Device | Routing   | Invert | Outlet Devices                                                 |  |  |  |  |  |  |  |  |  |  |  |
|--------|-----------|--------|----------------------------------------------------------------|--|--|--|--|--|--|--|--|--|--|--|
| #1     | Primary   | 99.75' | <b>2.0' long x 2.0' breadth Broad-Crested Rectangular Weir</b> |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00  |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | 2.50 3.00 3.50                                                 |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | Coef. (English) 2.54 2.61 2.61 2.60 2.66 2.70 2.77 2.89 2.88   |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | 2.85 3.07 3.20 3.32                                            |  |  |  |  |  |  |  |  |  |  |  |
| #2     | Discarded | 95.50' | <b>0.440 in/hr Exfiltration over Surface area</b>              |  |  |  |  |  |  |  |  |  |  |  |

**Discarded OutFlow** Max=0.01 cfs @ 17.60 hrs HW=99.53' (Free Discharge)

↑2=Exfiltration (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.10 hrs HW=95.50' (Free Discharge)

↑1=Broad-Crested Rectangular Weir ( Controls 0.00 cfs)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 24

### Pond 26P: BIORETENTION BASIN



**Prop-Conditions**

Type III 24-hr 2-YR Rainfall=3.20"

Prepared by Cornerstone Land Associates, LLC

Printed 6/1/2023

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Page 25

**Summary for Pond 29P: TREE BOX FILTER**

Inflow Area = 0.174 ac, 100.00% Impervious, Inflow Depth = 2.97" for 2-YR event  
 Inflow = 0.54 cfs @ 12.07 hrs, Volume= 0.043 af  
 Outflow = 0.54 cfs @ 12.08 hrs, Volume= 0.042 af, Atten= 1%, Lag= 0.7 min  
 Primary = 0.54 cfs @ 12.08 hrs, Volume= 0.042 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 97.84' @ 12.08 hrs Surf.Area= 60 sf Storage= 69 cf

Plug-Flow detention time= 30.4 min calculated for 0.042 af (97% of inflow)  
 Center-of-Mass det. time= 14.6 min ( 770.1 - 755.5 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.00' | 93 cf         | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Voids<br>(%) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) |
|---------------------|----------------------|--------------|---------------------------|---------------------------|
| 95.00               | 60                   | 0.0          | 0                         | 0                         |
| 95.50               | 60                   | 40.0         | 12                        | 12                        |
| 97.50               | 60                   | 30.0         | 36                        | 48                        |
| 98.25               | 60                   | 100.0        | 45                        | 93                        |

| Device | Routing  | Invert | Outlet Devices                                               |
|--------|----------|--------|--------------------------------------------------------------|
| #1     | Device 2 | 95.00' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600                     |
| #2     | Primary  | 97.50' | <b>1.0" W x 18.0" H Vert. Orifice/Grate X 10.00</b> C= 0.600 |

**Primary OutFlow** Max=0.52 cfs @ 12.08 hrs HW=97.84' (Free Discharge)

↑ **2=Orifice/Grate** (Orifice Controls 0.52 cfs @ 1.86 fps)

↑ **1=Orifice/Grate** (Passes 0.52 cfs of 0.55 cfs potential flow)

**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC  
HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 26

**Pond 29P: TREE BOX FILTER**

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 27

**Summary for Pond 33P: TREE BOX FILTER**

Inflow Area = 0.169 ac, 100.00% Impervious, Inflow Depth = 2.97" for 2-YR event  
 Inflow = 0.53 cfs @ 12.07 hrs, Volume = 0.042 af  
 Outflow = 0.53 cfs @ 12.08 hrs, Volume = 0.041 af, Atten = 1%, Lag = 0.7 min  
 Primary = 0.53 cfs @ 12.08 hrs, Volume = 0.041 af

Routing by Stor-Ind method, Time Span = 0.10-36.00 hrs, dt = 0.05 hrs  
 Peak Elev = 97.84' @ 12.08 hrs Surf.Area = 60 sf Storage = 68 cf

Plug-Flow detention time = 31.4 min calculated for 0.041 af (97% of inflow)  
 Center-of-Mass det. time = 15.0 min ( 770.4 - 755.5 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.00' | 93 cf         | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Voids<br>(%) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) |
|---------------------|----------------------|--------------|---------------------------|---------------------------|
| 95.00               | 60                   | 0.0          | 0                         | 0                         |
| 95.50               | 60                   | 40.0         | 12                        | 12                        |
| 97.50               | 60                   | 30.0         | 36                        | 48                        |
| 98.25               | 60                   | 100.0        | 45                        | 93                        |

| Device | Routing  | Invert | Outlet Devices                                                |
|--------|----------|--------|---------------------------------------------------------------|
| #1     | Device 2 | 95.00' | <b>6.0" Vert. Orifice/Grate</b> C = 0.600                     |
| #2     | Primary  | 97.50' | <b>1.0" W x 18.0" H Vert. Orifice/Grate X 10.00</b> C = 0.600 |

**Primary OutFlow** Max = 0.51 cfs @ 12.08 hrs HW = 97.83' (Free Discharge)

↑ **2=Orifice/Grate** (Orifice Controls 0.51 cfs @ 1.85 fps)

↑ **1=Orifice/Grate** (Passes 0.51 cfs of 0.54 cfs potential flow)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023

Page 28

### Pond 33P: TREE BOX FILTER

Hydrograph



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.20"

Printed 6/1/2023


Page 29

### Summary for Link 15L: DP#2-REAR WETLANDS

Inflow Area = 2.406 ac, 41.32% Impervious, Inflow Depth = 0.41" for 2-YR event  
Inflow = 0.43 cfs @ 12.66 hrs, Volume= 0.083 af  
Primary = 0.43 cfs @ 12.66 hrs, Volume= 0.083 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

### Link 15L: DP#2-REAR WETLANDS



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 30

**Summary for Subcatchment 1S: DP#1-GREENMONT**

Runoff = 0.14 cfs @ 12.00 hrs, Volume= 0.009 af, Depth= 2.37"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 5-YR Rainfall=3.90"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 569       | 98 | Paved parking, HSG D          |
| 1,380     | 80 | >75% Grass cover, Good, HSG D |
| 1,949     | 85 | Weighted Average              |
| 1,380     |    | 70.81% Pervious Area          |
| 569       |    | 29.19% Impervious Area        |

**Subcatchment 1S: DP#1-GREENMONT**

Hydrograph





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 31

**Summary for Subcatchment 3S: PWS#2**

Runoff = 0.47 cfs @ 12.07 hrs, Volume= 0.034 af, Depth= 3.12"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 5-YR Rainfall=3.90"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 4,094     | 98 | Paved parking, HSG D          |
| 1,678     | 80 | >75% Grass cover, Good, HSG D |
| 5,772     | 93 | Weighted Average              |
| 1,678     |    | 29.07% Pervious Area          |
| 4,094     |    | 70.93% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 3S: PWS#2**

Hydrograph





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 32

**Summary for Subcatchment 5S: ROOFS 15 - 28**

Runoff = 0.89 cfs @ 12.07 hrs, Volume= 0.071 af, Depth= 3.67"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 5-YR Rainfall=3.90"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 10,080    | 98 | Roofs, HSG D            |
| 10,080    |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 5S: ROOFS 15 - 28**

Hydrograph



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 33

### Summary for Subcatchment 6S: PWS#3

Runoff = 1.49 cfs @ 12.08 hrs, Volume= 0.106 af, Depth= 1.96"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs


Type III 24-hr 5-YR Rainfall=3.90"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 18,244    | 80 | >75% Grass cover, Good, HSG D |
| * 10,097  | 80 |                               |
| 28,341    | 80 | Weighted Average              |
| 28,341    |    | 100.00% Pervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 6S: PWS#3

Hydrograph





## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 34

### Summary for Subcatchment 7S: PWS#4

Runoff = 0.67 cfs @ 12.07 hrs, Volume= 0.053 af, Depth= 3.67"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs


Type III 24-hr 5-YR Rainfall=3.90"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 7,586     | 98 | Paved parking, HSG D    |
| 7,586     |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 7S: PWS#4

Hydrograph



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 35

### Summary for Subcatchment 9S: PWS#5

Runoff = 0.47 cfs @ 12.07 hrs, Volume= 0.034 af, Depth= 3.12"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs


Type III 24-hr 5-YR Rainfall=3.90"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 4,090     | 98 | Paved parking, HSG D          |
| 1,677     | 80 | >75% Grass cover, Good, HSG D |
| 5,767     | 93 | Weighted Average              |
| 1,677     |    | 29.08% Pervious Area          |
| 4,090     |    | 70.92% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 9S: PWS#5

Hydrograph





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 36

**Summary for Subcatchment 11S: PWS#6**

Runoff = 1.57 cfs @ 12.08 hrs, Volume= 0.112 af, Depth= 1.96"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs


Type III 24-hr 5-YR Rainfall=3.90"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 21,412    | 80 | >75% Grass cover, Good, HSG D |
| * 8,403   | 80 |                               |
| 29,815    | 80 | Weighted Average              |
| 29,815    |    | 100.00% Pervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 11S: PWS#6**

Hydrograph



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 37

### Summary for Subcatchment 13S: PWS#7

Runoff = 0.65 cfs @ 12.07 hrs, Volume= 0.052 af, Depth= 3.67"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 5-YR Rainfall=3.90"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 7,376     | 98 | Paved parking, HSG D    |
| 7,376     |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 13S: PWS#7





## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 38

### Summary for Subcatchment 18S: ROOFS 1 - 14

Runoff = 0.89 cfs @ 12.07 hrs, Volume= 0.071 af, Depth= 3.67"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 5-YR Rainfall=3.90"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 10,080    | 98 | Roofs, HSG D            |
| 10,080    |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 18S: ROOFS 1 - 14



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC  
HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 39

### Summary for Reach 4R: GRASS LINED SWALE #1

Inflow Area = 1.015 ac, 32.07% Impervious, Inflow Depth = 1.73" for 5-YR event  
Inflow = 2.16 cfs @ 12.09 hrs, Volume= 0.146 af  
Outflow = 2.00 cfs @ 12.18 hrs, Volume= 0.146 af, Atten= 7%, Lag= 5.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Max. Velocity= 1.51 fps, Min. Travel Time= 3.0 min  
Avg. Velocity = 0.45 fps, Avg. Travel Time= 10.1 min


Peak Storage= 363 cf @ 12.13 hrs  
Average Depth at Peak Storage= 0.21'  
Bank-Full Depth= 1.00' Flow Area= 14.0 sf, Capacity= 50.43 cfs

4.00' x 1.00' deep channel, n= 0.030 Earth, grassed & winding  
Side Slope Z-value= 10.0 '/' Top Width= 24.00'  
Length= 275.0' Slope= 0.0109 '/'  
Inlet Invert= 99.00', Outlet Invert= 96.00'



### Reach 4R: GRASS LINED SWALE #1

Hydrograph





## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC  
HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 40

### Summary for Reach 12R: GRASS LINED SWALE #2

Inflow Area = 1.048 ac, 31.03% Impervious, Inflow Depth = 1.76" for 5-YR event  
Inflow = 2.23 cfs @ 12.09 hrs, Volume= 0.153 af  
Outflow = 2.07 cfs @ 12.18 hrs, Volume= 0.153 af, Atten= 7%, Lag= 5.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Max. Velocity= 1.50 fps, Min. Travel Time= 3.0 min  
Avg. Velocity = 0.46 fps, Avg. Travel Time= 9.8 min


Peak Storage= 373 cf @ 12.13 hrs  
Average Depth at Peak Storage= 0.21'  
Bank-Full Depth= 1.00' Flow Area= 15.5 sf, Capacity= 55.70 cfs

4.00' x 1.00' deep channel, n= 0.030 Earth, grassed & winding  
Side Slope Z-value= 4.0 19.0 '/' Top Width= 27.00'  
Length= 270.0' Slope= 0.0111 '/'  
Inlet Invert= 99.00', Outlet Invert= 96.00'



### Reach 12R: GRASS LINED SWALE #2

Hydrograph



**Prop-Conditions**

Type III 24-hr 5-YR Rainfall=3.90"

Prepared by Cornerstone Land Associates, LLC

Printed 6/1/2023

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Page 41

**Summary for Pond 8P: DETENTION POND #1**

Inflow Area = 1.189 ac, 42.02% Impervious, Inflow Depth = 2.00" for 5-YR event  
 Inflow = 2.49 cfs @ 12.16 hrs, Volume= 0.199 af  
 Outflow = 0.20 cfs @ 13.81 hrs, Volume= 0.185 af, Atten= 92%, Lag= 99.2 min  
 Discarded = 0.10 cfs @ 13.81 hrs, Volume= 0.162 af  
 Primary = 0.10 cfs @ 13.81 hrs, Volume= 0.023 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 94.94' @ 13.81 hrs Surf.Area= 3,319 sf Storage= 4,720 cf

Plug-Flow detention time= 460.3 min calculated for 0.185 af (93% of inflow)  
 Center-of-Mass det. time= 426.5 min ( 1,240.4 - 813.9 )

| Volume              | Invert               | Avail.Storage    | Storage Description                                        |                           |                     |
|---------------------|----------------------|------------------|------------------------------------------------------------|---------------------------|---------------------|
| #1                  | 93.00'               | 8,773 cf         | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |                           |                     |
| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet)                                  | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
| 93.00               | 1,640                | 257.0            | 0                                                          | 0                         | 1,640               |
| 94.00               | 2,440                | 276.0            | 2,027                                                      | 2,027                     | 2,489               |
| 95.00               | 3,381                | 308.0            | 2,898                                                      | 4,925                     | 4,004               |
| 96.00               | 4,335                | 329.0            | 3,848                                                      | 8,773                     | 5,115               |

| Device | Routing   | Invert | Outlet Devices                                                 |  |  |  |  |  |  |  |  |  |  |  |
|--------|-----------|--------|----------------------------------------------------------------|--|--|--|--|--|--|--|--|--|--|--|
| #1     | Primary   | 95.50' | <b>6.0' long x 3.0' breadth Broad-Crested Rectangular Weir</b> |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00  |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | 2.50 3.00 3.50 4.00 4.50                                       |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68   |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | 2.72 2.81 2.92 2.97 3.07 3.32                                  |  |  |  |  |  |  |  |  |  |  |  |
| #2     | Primary   | 94.75' | <b>6.0" Vert. Orifice/Grate C= 0.600</b>                       |  |  |  |  |  |  |  |  |  |  |  |
| #3     | Discarded | 93.00' | <b>1.080 in/hr Exfiltration over Wetted area</b>               |  |  |  |  |  |  |  |  |  |  |  |

**Discarded OutFlow** Max=0.10 cfs @ 13.81 hrs HW=94.94' (Free Discharge)

↑ **3=Exfiltration** (Exfiltration Controls 0.10 cfs)

**Primary OutFlow** Max=0.10 cfs @ 13.81 hrs HW=94.94' (Free Discharge)

↑ **1=Broad-Crested Rectangular Weir** ( Controls 0.00 cfs)

↑ **2=Orifice/Grate** (Orifice Controls 0.10 cfs @ 1.48 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 42

### Pond 8P: DETENTION POND #1



**Prop-Conditions**

Type III 24-hr 5-YR Rainfall=3.90"

Prepared by Cornerstone Land Associates, LLC

Printed 6/1/2023

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Page 43

**Summary for Pond 14P: DETENTION POND #2**

Inflow Area = 1.218 ac, 40.62% Impervious, Inflow Depth = 2.01" for 5-YR event  
 Inflow = 2.55 cfs @ 12.16 hrs, Volume= 0.204 af  
 Outflow = 1.09 cfs @ 12.46 hrs, Volume= 0.150 af, Atten= 57%, Lag= 18.0 min  
 Discarded = 0.01 cfs @ 12.46 hrs, Volume= 0.012 af  
 Primary = 1.09 cfs @ 12.46 hrs, Volume= 0.139 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 95.29' @ 12.46 hrs Surf.Area= 2,462 sf Storage= 3,686 cf

Plug-Flow detention time= 197.1 min calculated for 0.150 af (74% of inflow)  
 Center-of-Mass det. time= 111.4 min ( 927.3 - 815.9 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 93.00' | 5,654 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 93.00               | 933                  | 130.0            | 0                         | 0                         | 933                 |
| 94.00               | 1,451                | 245.0            | 1,183                     | 1,183                     | 4,370               |
| 95.00               | 2,221                | 267.0            | 1,822                     | 3,005                     | 5,302               |
| 96.00               | 3,102                | 296.0            | 2,649                     | 5,654                     | 6,632               |

| Device | Routing   | Invert | Outlet Devices                                    |
|--------|-----------|--------|---------------------------------------------------|
| #1     | Primary   | 94.75' | <b>12.0" Vert. Orifice/Grate</b> C= 0.600         |
| #2     | Discarded | 93.00' | <b>0.110 in/hr Exfiltration over Surface area</b> |

**Discarded OutFlow** Max=0.01 cfs @ 12.46 hrs HW=95.29' (Free Discharge)  
 ↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=1.08 cfs @ 12.46 hrs HW=95.29' (Free Discharge)  
 ↑ **1=Orifice/Grate** (Orifice Controls 1.08 cfs @ 2.50 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 44

### Pond 14P: DETENTION POND #2

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 45

**Summary for Pond 20P: RECHARGE 1 - 8**

Inflow Area = 0.231 ac, 100.00% Impervious, Inflow Depth = 3.67" for 5-YR event  
 Inflow = 0.89 cfs @ 12.07 hrs, Volume = 0.071 af  
 Outflow = 0.71 cfs @ 12.13 hrs, Volume = 0.061 af, Atten = 19%, Lag = 3.7 min  
 Discarded = 0.01 cfs @ 12.13 hrs, Volume = 0.020 af  
 Primary = 0.70 cfs @ 12.13 hrs, Volume = 0.040 af

Routing by Stor-Ind method, Time Span = 0.10-36.00 hrs, dt = 0.05 hrs

Peak Elev = 99.55' @ 12.13 hrs Surf.Area = 540 sf Storage = 986 cf

Plug-Flow detention time = 240.1 min calculated for 0.061 af (86% of inflow)

Center-of-Mass det. time = 178.9 min ( 930.5 - 751.5 )

| Volume | Invert | Avail.Storage | Storage Description                                                                                                                                                                                                       |
|--------|--------|---------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | 96.50' | 646 cf        | <b>12.00'W x 45.00'L x 4.00'H Prismaoid</b><br>2,160 cf Overall - 544 cf Embedded = 1,616 cf x 40.0% Voids                                                                                                                |
| #2     | 97.00' | 544 cf        | <b>Cultec R-330XL</b> x 10 Inside #1<br>Effective Size = 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf<br>Overall Size = 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap<br>Row Length Adjustment = +1.50' x 7.45 sf x 2 rows |
|        |        | 1,190 cf      | Total Available Storage                                                                                                                                                                                                   |

| Device | Routing   | Invert | Outlet Devices                                   |
|--------|-----------|--------|--------------------------------------------------|
| #1     | Primary   | 98.75' | <b>6.0" Vert. Orifice/Grate</b> C = 0.600        |
| #2     | Discarded | 96.50' | <b>0.440 in/hr Exfiltration over Wetted area</b> |

**Discarded OutFlow** Max = 0.01 cfs @ 12.13 hrs HW = 99.54' (Free Discharge)↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max = 0.69 cfs @ 12.13 hrs HW = 99.54' (Free Discharge)↑ **1=Orifice/Grate** (Orifice Controls 0.69 cfs @ 3.54 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 46

### Pond 20P: RECHARGE 1 - 8

Hydrograph



**Prop-Conditions**

Type III 24-hr 5-YR Rainfall=3.90"

Prepared by Cornerstone Land Associates, LLC

Printed 6/1/2023

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Page 47

**Summary for Pond 23P: RECHARGE 15-28**

Inflow Area = 0.231 ac, 100.00% Impervious, Inflow Depth = 3.67" for 5-YR event  
 Inflow = 0.89 cfs @ 12.07 hrs, Volume = 0.071 af  
 Outflow = 0.71 cfs @ 12.13 hrs, Volume = 0.061 af, Atten = 19%, Lag = 3.7 min  
 Discarded = 0.01 cfs @ 12.13 hrs, Volume = 0.020 af  
 Primary = 0.70 cfs @ 12.13 hrs, Volume = 0.040 af

Routing by Stor-Ind method, Time Span = 0.10-36.00 hrs, dt = 0.05 hrs

Peak Elev = 99.55' @ 12.13 hrs Surf.Area = 540 sf Storage = 986 cf

Plug-Flow detention time = 240.1 min calculated for 0.061 af (86% of inflow)

Center-of-Mass det. time = 178.9 min ( 930.5 - 751.5 )

| Volume | Invert | Avail.Storage | Storage Description                                                                                                                                                                                                       |
|--------|--------|---------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | 96.50' | 646 cf        | <b>12.00'W x 45.00'L x 4.00'H Prismaoid</b><br>2,160 cf Overall - 544 cf Embedded = 1,616 cf x 40.0% Voids                                                                                                                |
| #2     | 97.00' | 544 cf        | <b>Cultec R-330XL</b> x 10 Inside #1<br>Effective Size = 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf<br>Overall Size = 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap<br>Row Length Adjustment = +1.50' x 7.45 sf x 2 rows |
|        |        | 1,190 cf      | Total Available Storage                                                                                                                                                                                                   |

| Device | Routing   | Invert | Outlet Devices                                   |
|--------|-----------|--------|--------------------------------------------------|
| #1     | Primary   | 98.75' | <b>6.0" Vert. Orifice/Grate</b> C = 0.600        |
| #2     | Discarded | 96.50' | <b>0.440 in/hr Exfiltration over Wetted area</b> |

**Discarded OutFlow** Max = 0.01 cfs @ 12.13 hrs HW = 99.54' (Free Discharge)↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)**Primary OutFlow** Max = 0.69 cfs @ 12.13 hrs HW = 99.54' (Free Discharge)↑ **1=Orifice/Grate** (Orifice Controls 0.69 cfs @ 3.54 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 48

### Pond 23P: RECHARGE 15-28

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 49

**Summary for Pond 25P: BIORETENTION BASIN**

Inflow Area = 0.133 ac, 70.93% Impervious, Inflow Depth = 3.12" for 5-YR event  
 Inflow = 0.47 cfs @ 12.07 hrs, Volume= 0.034 af  
 Outflow = 0.00 cfs @ 23.08 hrs, Volume= 0.010 af, Atten= 99%, Lag= 660.4 min  
 Discarded = 0.00 cfs @ 23.08 hrs, Volume= 0.010 af  
 Primary = 0.00 cfs @ 0.10 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 99.51' @ 23.08 hrs Surf.Area= 478 sf Storage= 1,255 cf

Plug-Flow detention time= 674.6 min calculated for 0.010 af (28% of inflow)  
 Center-of-Mass det. time= 520.7 min ( 1,305.8 - 785.1 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.50' | 1,538 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 95.50               | 302                  | 122.0            | 0                         | 0                         | 302                 |
| 96.00               | 302                  | 122.0            | 151                       | 151                       | 363                 |
| 98.75               | 302                  | 122.0            | 831                       | 982                       | 699                 |
| 99.00               | 302                  | 122.0            | 76                        | 1,057                     | 729                 |
| 100.00              | 685                  | 146.0            | 481                       | 1,538                     | 1,258               |

| Device | Routing   | Invert | Outlet Devices                                                                                         |
|--------|-----------|--------|--------------------------------------------------------------------------------------------------------|
| #1     | Primary   | 99.75' | <b>2.0' long x 2.00' rise Sharp-Crested Rectangular Weir</b><br>2 End Contraction(s) 0.7' Crest Height |
| #2     | Discarded | 95.50' | <b>0.440 in/hr Exfiltration over Surface area</b>                                                      |

**Discarded OutFlow** Max=0.00 cfs @ 23.08 hrs HW=99.51' (Free Discharge)  
 ↑ **2=Exfiltration** (Exfiltration Controls 0.00 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.10 hrs HW=95.50' (Free Discharge)  
 ↑ **1=Sharp-Crested Rectangular Weir** ( Controls 0.00 cfs)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 50

### Pond 25P: BIORETENTION BASIN

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 51

**Summary for Pond 26P: BIORETENTION BASIN**

Inflow Area = 0.132 ac, 70.92% Impervious, Inflow Depth = 3.12" for 5-YR event  
 Inflow = 0.47 cfs @ 12.07 hrs, Volume= 0.034 af  
 Outflow = 0.02 cfs @ 14.95 hrs, Volume= 0.019 af, Atten= 96%, Lag= 172.7 min  
 Discarded = 0.01 cfs @ 14.95 hrs, Volume= 0.018 af  
 Primary = 0.01 cfs @ 14.95 hrs, Volume= 0.002 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 99.76' @ 14.95 hrs Surf.Area= 901 sf Storage= 1,035 cf

Plug-Flow detention time= 589.9 min calculated for 0.019 af (56% of inflow)  
 Center-of-Mass det. time= 482.5 min ( 1,267.7 - 785.1 )

| Volume              | Invert               | Avail.Storage    | Storage Description                                        |                           |                           |                     |
|---------------------|----------------------|------------------|------------------------------------------------------------|---------------------------|---------------------------|---------------------|
| #1                  | 95.50'               | 2,456 cf         | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |                           |                           |                     |
| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Voids<br>(%)                                               | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
| 95.50               | 425                  | 167.0            | 0.0                                                        | 0                         | 0                         | 425                 |
| 96.00               | 425                  | 167.0            | 40.0                                                       | 85                        | 85                        | 509                 |
| 98.75               | 425                  | 167.0            | 30.0                                                       | 351                       | 436                       | 968                 |
| 99.00               | 425                  | 167.0            | 100.0                                                      | 106                       | 542                       | 1,010               |
| 100.00              | 1,088                | 213.0            | 100.0                                                      | 731                       | 1,273                     | 2,413               |
| 101.00              | 1,281                | 181.0            | 100.0                                                      | 1,183                     | 2,456                     | 3,436               |

| Device | Routing   | Invert | Outlet Devices                                                 |  |  |  |  |  |  |  |  |  |  |  |
|--------|-----------|--------|----------------------------------------------------------------|--|--|--|--|--|--|--|--|--|--|--|
| #1     | Primary   | 99.75' | <b>2.0' long x 2.0' breadth Broad-Crested Rectangular Weir</b> |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00  |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | 2.50 3.00 3.50                                                 |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | Coef. (English) 2.54 2.61 2.61 2.60 2.66 2.70 2.77 2.89 2.88   |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | 2.85 3.07 3.20 3.32                                            |  |  |  |  |  |  |  |  |  |  |  |
| #2     | Discarded | 95.50' | <b>0.440 in/hr Exfiltration over Surface area</b>              |  |  |  |  |  |  |  |  |  |  |  |

**Discarded OutFlow** Max=0.01 cfs @ 14.95 hrs HW=99.76' (Free Discharge)

↑**2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.01 cfs @ 14.95 hrs HW=99.76' (Free Discharge)

↑**1=Broad-Crested Rectangular Weir** (Weir Controls 0.01 cfs @ 0.26 fps)



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 52

**Pond 26P: BIORETENTION BASIN**

Hydrograph



**Prop-Conditions**

Type III 24-hr 5-YR Rainfall=3.90"

Prepared by Cornerstone Land Associates, LLC

Printed 6/1/2023

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Page 53

**Summary for Pond 29P: TREE BOX FILTER**

Inflow Area = 0.174 ac, 100.00% Impervious, Inflow Depth = 3.67" for 5-YR event  
 Inflow = 0.67 cfs @ 12.07 hrs, Volume = 0.053 af  
 Outflow = 0.65 cfs @ 12.09 hrs, Volume = 0.052 af, Atten = 3%, Lag = 1.0 min  
 Primary = 0.65 cfs @ 12.09 hrs, Volume = 0.052 af

Routing by Stor-Ind method, Time Span = 0.10-36.00 hrs, dt = 0.05 hrs  
 Peak Elev = 97.96' @ 12.09 hrs Surf.Area = 60 sf Storage = 76 cf

Plug-Flow detention time = 25.8 min calculated for 0.052 af (98% of inflow)  
 Center-of-Mass det. time = 12.7 min ( 764.2 - 751.5 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.00' | 93 cf         | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Voids<br>(%) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) |
|---------------------|----------------------|--------------|---------------------------|---------------------------|
| 95.00               | 60                   | 0.0          | 0                         | 0                         |
| 95.50               | 60                   | 40.0         | 12                        | 12                        |
| 97.50               | 60                   | 30.0         | 36                        | 48                        |
| 98.25               | 60                   | 100.0        | 45                        | 93                        |

| Device | Routing  | Invert | Outlet Devices                                                |
|--------|----------|--------|---------------------------------------------------------------|
| #1     | Device 2 | 95.00' | <b>6.0" Vert. Orifice/Grate</b> C = 0.600                     |
| #2     | Primary  | 97.50' | <b>1.0" W x 18.0" H Vert. Orifice/Grate X 10.00</b> C = 0.600 |

**Primary OutFlow** Max = 0.63 cfs @ 12.09 hrs HW = 97.95' (Free Discharge)

↑ **2=Orifice/Grate** (Passes 0.63 cfs of 0.80 cfs potential flow)

↑ **1=Orifice/Grate** (Orifice Controls 0.63 cfs @ 3.22 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 54

### Pond 29P: TREE BOX FILTER

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 55

**Summary for Pond 33P: TREE BOX FILTER**

Inflow Area = 0.169 ac, 100.00% Impervious, Inflow Depth = 3.67" for 5-YR event  
 Inflow = 0.65 cfs @ 12.07 hrs, Volume= 0.052 af  
 Outflow = 0.63 cfs @ 12.09 hrs, Volume= 0.051 af, Atten= 3%, Lag= 0.9 min  
 Primary = 0.63 cfs @ 12.09 hrs, Volume= 0.051 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 97.94' @ 12.09 hrs Surf.Area= 60 sf Storage= 74 cf

Plug-Flow detention time= 26.6 min calculated for 0.051 af (98% of inflow)  
 Center-of-Mass det. time= 13.0 min ( 764.5 - 751.5 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.00' | 93 cf         | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Voids<br>(%) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) |
|---------------------|----------------------|--------------|---------------------------|---------------------------|
| 95.00               | 60                   | 0.0          | 0                         | 0                         |
| 95.50               | 60                   | 40.0         | 12                        | 12                        |
| 97.50               | 60                   | 30.0         | 36                        | 48                        |
| 98.25               | 60                   | 100.0        | 45                        | 93                        |

| Device | Routing  | Invert | Outlet Devices                                               |
|--------|----------|--------|--------------------------------------------------------------|
| #1     | Device 2 | 95.00' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600                     |
| #2     | Primary  | 97.50' | <b>1.0" W x 18.0" H Vert. Orifice/Grate X 10.00</b> C= 0.600 |

**Primary OutFlow** Max=0.62 cfs @ 12.09 hrs HW=97.92' (Free Discharge)

↑ **2=Orifice/Grate** (Passes 0.62 cfs of 0.74 cfs potential flow)

↑ **1=Orifice/Grate** (Orifice Controls 0.62 cfs @ 3.13 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023

Page 56

### Pond 33P: TREE BOX FILTER

Hydrograph



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 5-YR Rainfall=3.90"

Printed 6/1/2023


Page 57

### Summary for Link 15L: DP#2-REAR WETLANDS

Inflow Area = 2.406 ac, 41.32% Impervious, Inflow Depth = 0.81" for 5-YR event  
Inflow = 1.09 cfs @ 12.46 hrs, Volume= 0.162 af  
Primary = 1.09 cfs @ 12.46 hrs, Volume= 0.162 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

### Link 15L: DP#2-REAR WETLANDS



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023


Page 58

**Summary for Subcatchment 1S: DP#1-GREENMONT**

Runoff = 0.17 cfs @ 12.00 hrs, Volume= 0.011 af, Depth= 2.91"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-YR Rainfall=4.50"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 569       | 98 | Paved parking, HSG D          |
| 1,380     | 80 | >75% Grass cover, Good, HSG D |
| 1,949     | 85 | Weighted Average              |
| 1,380     |    | 70.81% Pervious Area          |
| 569       |    | 29.19% Impervious Area        |

**Subcatchment 1S: DP#1-GREENMONT**



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 59

### Summary for Subcatchment 3S: PWS#2

Runoff = 0.55 cfs @ 12.07 hrs, Volume= 0.041 af, Depth= 3.71"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs


Type III 24-hr 10-YR Rainfall=4.50"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 4,094     | 98 | Paved parking, HSG D          |
| 1,678     | 80 | >75% Grass cover, Good, HSG D |
| 5,772     | 93 | Weighted Average              |
| 1,678     |    | 29.07% Pervious Area          |
| 4,094     |    | 70.93% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 3S: PWS#2

Hydrograph





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 60

**Summary for Subcatchment 5S: ROOFS 15 - 28**

Runoff = 1.02 cfs @ 12.07 hrs, Volume= 0.082 af, Depth= 4.26"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-YR Rainfall=4.50"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 10,080    | 98 | Roofs, HSG D            |
| 10,080    |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 5S: ROOFS 15 - 28**

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 61

**Summary for Subcatchment 6S: PWS#3**


Runoff = 1.88 cfs @ 12.08 hrs, Volume= 0.133 af, Depth= 2.46"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 10-YR Rainfall=4.50"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 18,244    | 80 | >75% Grass cover, Good, HSG D |
| * 10,097  | 80 |                               |
| 28,341    | 80 | Weighted Average              |
| 28,341    |    | 100.00% Pervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 6S: PWS#3**



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 62

### Summary for Subcatchment 7S: PWS#4

Runoff = 0.77 cfs @ 12.07 hrs, Volume= 0.062 af, Depth= 4.26"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-YR Rainfall=4.50"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 7,586     | 98 | Paved parking, HSG D    |
| 7,586     |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 7S: PWS#4

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 63

**Summary for Subcatchment 9S: PWS#5**

Runoff = 0.55 cfs @ 12.07 hrs, Volume= 0.041 af, Depth= 3.71"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs


Type III 24-hr 10-YR Rainfall=4.50"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 4,090     | 98 | Paved parking, HSG D          |
| 1,677     | 80 | >75% Grass cover, Good, HSG D |
| 5,767     | 93 | Weighted Average              |
| 1,677     |    | 29.08% Pervious Area          |
| 4,090     |    | 70.92% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 9S: PWS#5**

Hydrograph





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 64


**Summary for Subcatchment 11S: PWS#6**

Runoff = 1.98 cfs @ 12.08 hrs, Volume= 0.140 af, Depth= 2.46"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 10-YR Rainfall=4.50"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 21,412    | 80 | >75% Grass cover, Good, HSG D |
| * 8,403   | 80 |                               |
| 29,815    | 80 | Weighted Average              |
| 29,815    |    | 100.00% Pervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 11S: PWS#6**

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 65

### Summary for Subcatchment 13S: PWS#7

Runoff = 0.75 cfs @ 12.07 hrs, Volume= 0.060 af, Depth= 4.26"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 10-YR Rainfall=4.50"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 7,376     | 98 | Paved parking, HSG D    |
| 7,376     |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 13S: PWS#7





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 66

**Summary for Subcatchment 18S: ROOFS 1 - 14**


Runoff = 1.02 cfs @ 12.07 hrs, Volume= 0.082 af, Depth= 4.26"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 10-YR Rainfall=4.50"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 10,080    | 98 | Roofs, HSG D            |
| 10,080    |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 18S: ROOFS 1 - 14**

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 67

### Summary for Reach 4R: GRASS LINED SWALE #1

Inflow Area = 1.015 ac, 32.07% Impervious, Inflow Depth = 2.21" for 10-YR event  
Inflow = 2.63 cfs @ 12.09 hrs, Volume= 0.187 af  
Outflow = 2.48 cfs @ 12.17 hrs, Volume= 0.187 af, Atten= 6%, Lag= 4.9 min

Routing by Stor-Ind+Trans method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.61 fps, Min. Travel Time= 2.9 min

Avg. Velocity = 0.49 fps, Avg. Travel Time= 9.4 min

Peak Storage= 424 cf @ 12.12 hrs

Average Depth at Peak Storage= 0.24'

Bank-Full Depth= 1.00' Flow Area= 14.0 sf, Capacity= 50.43 cfs

4.00' x 1.00' deep channel, n= 0.030 Earth, grassed & winding

Side Slope Z-value= 10.0 ' Top Width= 24.00'


Length= 275.0' Slope= 0.0109 '/'

Inlet Invert= 99.00', Outlet Invert= 96.00'



### Reach 4R: GRASS LINED SWALE #1

Hydrograph





## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 68

### Summary for Reach 12R: GRASS LINED SWALE #2

Inflow Area = 1.048 ac, 31.03% Impervious, Inflow Depth = 2.28" for 10-YR event  
Inflow = 2.73 cfs @ 12.09 hrs, Volume= 0.199 af  
Outflow = 2.57 cfs @ 12.17 hrs, Volume= 0.199 af, Atten= 6%, Lag= 4.9 min

Routing by Stor-Ind+Trans method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.59 fps, Min. Travel Time= 2.8 min

Avg. Velocity = 0.49 fps, Avg. Travel Time= 9.1 min

Peak Storage= 436 cf @ 12.12 hrs

Average Depth at Peak Storage= 0.24'

Bank-Full Depth= 1.00' Flow Area= 15.5 sf, Capacity= 55.70 cfs

4.00' x 1.00' deep channel, n= 0.030 Earth, grassed & winding

Side Slope Z-value= 4.0 19.0 '/' Top Width= 27.00'


Length= 270.0' Slope= 0.0111 '/'

Inlet Invert= 99.00', Outlet Invert= 96.00'



### Reach 12R: GRASS LINED SWALE #2

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 69

**Summary for Pond 8P: DETENTION POND #1**

Inflow Area = 1.189 ac, 42.02% Impervious, Inflow Depth = 2.50" for 10-YR event  
 Inflow = 3.07 cfs @ 12.15 hrs, Volume= 0.248 af  
 Outflow = 0.42 cfs @ 12.87 hrs, Volume= 0.231 af, Atten= 86%, Lag= 43.0 min  
 Discarded = 0.10 cfs @ 12.87 hrs, Volume= 0.169 af  
 Primary = 0.32 cfs @ 12.87 hrs, Volume= 0.062 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 95.12' @ 12.87 hrs Surf.Area= 3,487 sf Storage= 5,327 cf

Plug-Flow detention time= 389.9 min calculated for 0.231 af (93% of inflow)  
 Center-of-Mass det. time= 355.8 min ( 1,167.7 - 812.0 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 93.00' | 8,773 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 93.00               | 1,640                | 257.0            | 0                         | 0                         | 1,640               |
| 94.00               | 2,440                | 276.0            | 2,027                     | 2,027                     | 2,489               |
| 95.00               | 3,381                | 308.0            | 2,898                     | 4,925                     | 4,004               |
| 96.00               | 4,335                | 329.0            | 3,848                     | 8,773                     | 5,115               |

| Device | Routing   | Invert | Outlet Devices                                                                                                                                                                                                                                               |
|--------|-----------|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | Primary   | 95.50' | <b>6.0' long x 3.0' breadth Broad-Crested Rectangular Weir</b><br>Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00<br>2.50 3.00 3.50 4.00 4.50<br>Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68<br>2.72 2.81 2.92 2.97 3.07 3.32 |
| #2     | Primary   | 94.75' | <b>6.0" Vert. Orifice/Grate C= 0.600</b>                                                                                                                                                                                                                     |
| #3     | Discarded | 93.00' | <b>1.080 in/hr Exfiltration over Wetted area</b>                                                                                                                                                                                                             |

**Discarded OutFlow** Max=0.10 cfs @ 12.87 hrs HW=95.12' (Free Discharge)↑ **3=Exfiltration** (Exfiltration Controls 0.10 cfs)**Primary OutFlow** Max=0.32 cfs @ 12.87 hrs HW=95.12' (Free Discharge)↑ **1=Broad-Crested Rectangular Weir** ( Controls 0.00 cfs)↑ **2=Orifice/Grate** (Orifice Controls 0.32 cfs @ 2.06 fps)

**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 70

**Pond 8P: DETENTION POND #1**

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 71

**Summary for Pond 14P: DETENTION POND #2**

Inflow Area = 1.218 ac, 40.62% Impervious, Inflow Depth = 2.54" for 10-YR event  
 Inflow = 3.14 cfs @ 12.15 hrs, Volume= 0.258 af  
 Outflow = 1.70 cfs @ 12.37 hrs, Volume= 0.204 af, Atten= 46%, Lag= 12.8 min  
 Discarded = 0.01 cfs @ 12.37 hrs, Volume= 0.012 af  
 Primary = 1.69 cfs @ 12.37 hrs, Volume= 0.192 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 95.45' @ 12.37 hrs Surf.Area= 2,603 sf Storage= 4,100 cf

Plug-Flow detention time= 164.6 min calculated for 0.204 af (79% of inflow)  
 Center-of-Mass det. time= 90.2 min ( 902.2 - 812.0 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 93.00' | 5,654 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 93.00               | 933                  | 130.0            | 0                         | 0                         | 933                 |
| 94.00               | 1,451                | 245.0            | 1,183                     | 1,183                     | 4,370               |
| 95.00               | 2,221                | 267.0            | 1,822                     | 3,005                     | 5,302               |
| 96.00               | 3,102                | 296.0            | 2,649                     | 5,654                     | 6,632               |

| Device | Routing   | Invert | Outlet Devices                                    |
|--------|-----------|--------|---------------------------------------------------|
| #1     | Primary   | 94.75' | <b>12.0" Vert. Orifice/Grate</b> C= 0.600         |
| #2     | Discarded | 93.00' | <b>0.110 in/hr Exfiltration over Surface area</b> |

**Discarded OutFlow** Max=0.01 cfs @ 12.37 hrs HW=95.45' (Free Discharge)  
 ↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=1.68 cfs @ 12.37 hrs HW=95.45' (Free Discharge)  
 ↑ **1=Orifice/Grate** (Orifice Controls 1.68 cfs @ 2.85 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 72

### Pond 14P: DETENTION POND #2



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 73

**Summary for Pond 20P: RECHARGE 1 - 8**

Inflow Area = 0.231 ac, 100.00% Impervious, Inflow Depth = 4.26" for 10-YR event  
 Inflow = 1.02 cfs @ 12.07 hrs, Volume= 0.082 af  
 Outflow = 0.82 cfs @ 12.13 hrs, Volume= 0.072 af, Atten= 20%, Lag= 3.8 min  
 Discarded = 0.01 cfs @ 12.13 hrs, Volume= 0.021 af  
 Primary = 0.81 cfs @ 12.13 hrs, Volume= 0.051 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 99.73' @ 12.13 hrs Surf.Area= 540 sf Storage= 1,024 cf

Plug-Flow detention time= 215.4 min calculated for 0.072 af (88% of inflow)  
 Center-of-Mass det. time= 158.1 min ( 907.0 - 748.9 )

| Volume | Invert | Avail.Storage | Storage Description                                                                                                                                                                                                    |
|--------|--------|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | 96.50' | 646 cf        | <b>12.00'W x 45.00'L x 4.00'H Prismatic</b><br>2,160 cf Overall - 544 cf Embedded = 1,616 cf x 40.0% Voids                                                                                                             |
| #2     | 97.00' | 544 cf        | <b>Cultec R-330XL</b> x 10 Inside #1<br>Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf<br>Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap<br>Row Length Adjustment= +1.50' x 7.45 sf x 2 rows |
|        |        | 1,190 cf      | Total Available Storage                                                                                                                                                                                                |

| Device | Routing   | Invert | Outlet Devices                                   |
|--------|-----------|--------|--------------------------------------------------|
| #1     | Primary   | 98.75' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600         |
| #2     | Discarded | 96.50' | <b>0.440 in/hr Exfiltration over Wetted area</b> |

**Discarded OutFlow** Max=0.01 cfs @ 12.13 hrs HW=99.71' (Free Discharge)  
 ↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.80 cfs @ 12.13 hrs HW=99.71' (Free Discharge)  
 ↑ **1=Orifice/Grate** (Orifice Controls 0.80 cfs @ 4.06 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 74

### Pond 20P: RECHARGE 1 - 8

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 75

**Summary for Pond 23P: RECHARGE 15-28**

Inflow Area = 0.231 ac, 100.00% Impervious, Inflow Depth = 4.26" for 10-YR event  
 Inflow = 1.02 cfs @ 12.07 hrs, Volume= 0.082 af  
 Outflow = 0.82 cfs @ 12.13 hrs, Volume= 0.072 af, Atten= 20%, Lag= 3.8 min  
 Discarded = 0.01 cfs @ 12.13 hrs, Volume= 0.021 af  
 Primary = 0.81 cfs @ 12.13 hrs, Volume= 0.051 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 99.73' @ 12.13 hrs Surf.Area= 540 sf Storage= 1,024 cf

Plug-Flow detention time= 215.4 min calculated for 0.072 af (88% of inflow)  
 Center-of-Mass det. time= 158.1 min ( 907.0 - 748.9 )

| Volume | Invert | Avail.Storage | Storage Description                                                                                                                                                                                                    |
|--------|--------|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | 96.50' | 646 cf        | <b>12.00'W x 45.00'L x 4.00'H Prismaoid</b><br>2,160 cf Overall - 544 cf Embedded = 1,616 cf x 40.0% Voids                                                                                                             |
| #2     | 97.00' | 544 cf        | <b>Cultec R-330XL x 10 Inside #1</b><br>Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf<br>Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap<br>Row Length Adjustment= +1.50' x 7.45 sf x 2 rows |
|        |        | 1,190 cf      | Total Available Storage                                                                                                                                                                                                |

| Device | Routing   | Invert | Outlet Devices                                   |
|--------|-----------|--------|--------------------------------------------------|
| #1     | Primary   | 98.75' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600         |
| #2     | Discarded | 96.50' | <b>0.440 in/hr Exfiltration over Wetted area</b> |

**Discarded OutFlow** Max=0.01 cfs @ 12.13 hrs HW=99.71' (Free Discharge)  
 ↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.80 cfs @ 12.13 hrs HW=99.71' (Free Discharge)  
 ↑ **1=Orifice/Grate** (Orifice Controls 0.80 cfs @ 4.06 fps)



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 76

**Pond 23P: RECHARGE 15-28**

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 77

**Summary for Pond 25P: BIORETENTION BASIN**

Inflow Area = 0.133 ac, 70.93% Impervious, Inflow Depth = 3.71" for 10-YR event  
 Inflow = 0.55 cfs @ 12.07 hrs, Volume= 0.041 af  
 Outflow = 0.02 cfs @ 15.80 hrs, Volume= 0.014 af, Atten= 97%, Lag= 223.9 min  
 Discarded = 0.01 cfs @ 15.80 hrs, Volume= 0.012 af  
 Primary = 0.01 cfs @ 15.80 hrs, Volume= 0.002 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 99.76' @ 15.80 hrs Surf.Area= 578 sf Storage= 1,384 cf

Plug-Flow detention time= 626.0 min calculated for 0.014 af (35% of inflow)  
 Center-of-Mass det. time= 484.4 min ( 1,265.0 - 780.6 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.50' | 1,538 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 95.50               | 302                  | 122.0            | 0                         | 0                         | 302                 |
| 96.00               | 302                  | 122.0            | 151                       | 151                       | 363                 |
| 98.75               | 302                  | 122.0            | 831                       | 982                       | 699                 |
| 99.00               | 302                  | 122.0            | 76                        | 1,057                     | 729                 |
| 100.00              | 685                  | 146.0            | 481                       | 1,538                     | 1,258               |

| Device | Routing   | Invert | Outlet Devices                                                                                         |
|--------|-----------|--------|--------------------------------------------------------------------------------------------------------|
| #1     | Primary   | 99.75' | <b>2.0' long x 2.00' rise Sharp-Crested Rectangular Weir</b><br>2 End Contraction(s) 0.7' Crest Height |
| #2     | Discarded | 95.50' | <b>0.440 in/hr Exfiltration over Surface area</b>                                                      |

**Discarded OutFlow** Max=0.01 cfs @ 15.80 hrs HW=99.76' (Free Discharge)  
 ↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.00 cfs @ 15.80 hrs HW=99.76' (Free Discharge)  
 ↑ **1=Sharp-Crested Rectangular Weir** (Weir Controls 0.00 cfs @ 0.27 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 78

### Pond 25P: BIORETENTION BASIN

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 79

**Summary for Pond 26P: BIORETENTION BASIN**

Inflow Area = 0.132 ac, 70.92% Impervious, Inflow Depth = 3.71" for 10-YR event  
 Inflow = 0.55 cfs @ 12.07 hrs, Volume= 0.041 af  
 Outflow = 0.05 cfs @ 12.94 hrs, Volume= 0.025 af, Atten= 91%, Lag= 52.1 min  
 Discarded = 0.01 cfs @ 12.94 hrs, Volume= 0.018 af  
 Primary = 0.04 cfs @ 12.94 hrs, Volume= 0.007 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 99.79' @ 12.94 hrs Surf.Area= 923 sf Storage= 1,062 cf

Plug-Flow detention time= 484.1 min calculated for 0.025 af (62% of inflow)  
 Center-of-Mass det. time= 383.0 min ( 1,163.6 - 780.6 )

| Volume              | Invert               | Avail.Storage    | Storage Description                                        |                           |                           |                     |
|---------------------|----------------------|------------------|------------------------------------------------------------|---------------------------|---------------------------|---------------------|
| #1                  | 95.50'               | 2,456 cf         | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |                           |                           |                     |
| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Voids<br>(%)                                               | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
| 95.50               | 425                  | 167.0            | 0.0                                                        | 0                         | 0                         | 425                 |
| 96.00               | 425                  | 167.0            | 40.0                                                       | 85                        | 85                        | 509                 |
| 98.75               | 425                  | 167.0            | 30.0                                                       | 351                       | 436                       | 968                 |
| 99.00               | 425                  | 167.0            | 100.0                                                      | 106                       | 542                       | 1,010               |
| 100.00              | 1,088                | 213.0            | 100.0                                                      | 731                       | 1,273                     | 2,413               |
| 101.00              | 1,281                | 181.0            | 100.0                                                      | 1,183                     | 2,456                     | 3,436               |

| Device | Routing   | Invert | Outlet Devices                                                 |  |  |  |  |  |  |  |  |  |  |  |
|--------|-----------|--------|----------------------------------------------------------------|--|--|--|--|--|--|--|--|--|--|--|
| #1     | Primary   | 99.75' | <b>2.0' long x 2.0' breadth Broad-Crested Rectangular Weir</b> |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00  |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | 2.50 3.00 3.50                                                 |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | Coef. (English) 2.54 2.61 2.61 2.60 2.66 2.70 2.77 2.89 2.88   |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | 2.85 3.07 3.20 3.32                                            |  |  |  |  |  |  |  |  |  |  |  |
| #2     | Discarded | 95.50' | <b>0.440 in/hr Exfiltration over Surface area</b>              |  |  |  |  |  |  |  |  |  |  |  |

**Discarded OutFlow** Max=0.01 cfs @ 12.94 hrs HW=99.79' (Free Discharge)

↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.04 cfs @ 12.94 hrs HW=99.79' (Free Discharge)

↑ **1=Broad-Crested Rectangular Weir** (Weir Controls 0.04 cfs @ 0.51 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 80

### Pond 26P: BIORETENTION BASIN

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 81

**Summary for Pond 29P: TREE BOX FILTER**

Inflow Area = 0.174 ac, 100.00% Impervious, Inflow Depth = 4.26" for 10-YR event  
 Inflow = 0.77 cfs @ 12.07 hrs, Volume = 0.062 af  
 Outflow = 0.74 cfs @ 12.09 hrs, Volume = 0.061 af, Atten = 4%, Lag = 1.5 min  
 Primary = 0.74 cfs @ 12.09 hrs, Volume = 0.061 af

Routing by Stor-Ind method, Time Span = 0.10-36.00 hrs, dt = 0.05 hrs  
 Peak Elev = 98.11' @ 12.09 hrs Surf.Area = 60 sf Storage = 85 cf

Plug-Flow detention time = 22.8 min calculated for 0.061 af (98% of inflow)  
 Center-of-Mass det. time = 11.4 min ( 760.3 - 748.9 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.00' | 93 cf         | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Voids<br>(%) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) |
|---------------------|----------------------|--------------|---------------------------|---------------------------|
| 95.00               | 60                   | 0.0          | 0                         | 0                         |
| 95.50               | 60                   | 40.0         | 12                        | 12                        |
| 97.50               | 60                   | 30.0         | 36                        | 48                        |
| 98.25               | 60                   | 100.0        | 45                        | 93                        |

| Device | Routing  | Invert | Outlet Devices                                                |
|--------|----------|--------|---------------------------------------------------------------|
| #1     | Device 2 | 95.00' | <b>6.0" Vert. Orifice/Grate</b> C = 0.600                     |
| #2     | Primary  | 97.50' | <b>1.0" W x 18.0" H Vert. Orifice/Grate X 10.00</b> C = 0.600 |

**Primary OutFlow** Max = 0.73 cfs @ 12.09 hrs HW = 98.10' (Free Discharge)

↑ **2=Orifice/Grate** (Passes 0.73 cfs of 1.24 cfs potential flow)

↑ **1=Orifice/Grate** (Orifice Controls 0.73 cfs @ 3.73 fps)

**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC  
HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 82

**Pond 29P: TREE BOX FILTER**

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 83

**Summary for Pond 33P: TREE BOX FILTER**

Inflow Area = 0.169 ac, 100.00% Impervious, Inflow Depth = 4.26" for 10-YR event  
 Inflow = 0.75 cfs @ 12.07 hrs, Volume= 0.060 af  
 Outflow = 0.72 cfs @ 12.09 hrs, Volume= 0.059 af, Atten= 4%, Lag= 1.4 min  
 Primary = 0.72 cfs @ 12.09 hrs, Volume= 0.059 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 98.08' @ 12.09 hrs Surf.Area= 60 sf Storage= 83 cf

Plug-Flow detention time= 23.5 min calculated for 0.059 af (98% of inflow)  
 Center-of-Mass det. time= 11.7 min ( 760.6 - 748.9 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.00' | 93 cf         | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Voids<br>(%) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) |
|---------------------|----------------------|--------------|---------------------------|---------------------------|
| 95.00               | 60                   | 0.0          | 0                         | 0                         |
| 95.50               | 60                   | 40.0         | 12                        | 12                        |
| 97.50               | 60                   | 30.0         | 36                        | 48                        |
| 98.25               | 60                   | 100.0        | 45                        | 93                        |

| Device | Routing  | Invert | Outlet Devices                                               |
|--------|----------|--------|--------------------------------------------------------------|
| #1     | Device 2 | 95.00' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600                     |
| #2     | Primary  | 97.50' | <b>1.0" W x 18.0" H Vert. Orifice/Grate X 10.00</b> C= 0.600 |

**Primary OutFlow** Max=0.71 cfs @ 12.09 hrs HW=98.07' (Free Discharge)

↑ **2=Orifice/Grate** (Passes 0.71 cfs of 1.14 cfs potential flow)

↑ **1=Orifice/Grate** (Orifice Controls 0.71 cfs @ 3.62 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023

Page 84

### Pond 33P: TREE BOX FILTER



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=4.50"

Printed 6/1/2023


Page 85

### Summary for Link 15L: DP#2-REAR WETLANDS

Inflow Area = 2.406 ac, 41.32% Impervious, Inflow Depth = 1.27" for 10-YR event  
Inflow = 1.75 cfs @ 12.43 hrs, Volume= 0.254 af  
Primary = 1.75 cfs @ 12.43 hrs, Volume= 0.254 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

### Link 15L: DP#2-REAR WETLANDS



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 86


### Summary for Subcatchment 1S: DP#1-GREENMONT

Runoff = 0.22 cfs @ 12.00 hrs, Volume= 0.014 af, Depth= 3.65"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-YR Rainfall=5.30"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 569       | 98 | Paved parking, HSG D          |
| 1,380     | 80 | >75% Grass cover, Good, HSG D |
| 1,949     | 85 | Weighted Average              |
| 1,380     |    | 70.81% Pervious Area          |
| 569       |    | 29.19% Impervious Area        |

### Subcatchment 1S: DP#1-GREENMONT





## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 87

### Summary for Subcatchment 3S: PWS#2


Runoff = 0.66 cfs @ 12.07 hrs, Volume= 0.050 af, Depth= 4.49"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-YR Rainfall=5.30"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 4,094     | 98 | Paved parking, HSG D          |
| 1,678     | 80 | >75% Grass cover, Good, HSG D |
| 5,772     | 93 | Weighted Average              |
| 1,678     |    | 29.07% Pervious Area          |
| 4,094     |    | 70.93% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 3S: PWS#2





## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 88

### Summary for Subcatchment 5S: ROOFS 15 - 28


Runoff = 1.21 cfs @ 12.07 hrs, Volume= 0.098 af, Depth= 5.06"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-YR Rainfall=5.30"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 10,080    | 98 | Roofs, HSG D            |
| 10,080    |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 5S: ROOFS 15 - 28



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 89

### Summary for Subcatchment 6S: PWS#3


Runoff = 2.40 cfs @ 12.08 hrs, Volume= 0.171 af, Depth= 3.16"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-YR Rainfall=5.30"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 18,244    | 80 | >75% Grass cover, Good, HSG D |
| * 10,097  | 80 |                               |
| 28,341    | 80 | Weighted Average              |
| 28,341    |    | 100.00% Pervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 6S: PWS#3





## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 90

### Summary for Subcatchment 7S: PWS#4

Runoff = 0.91 cfs @ 12.07 hrs, Volume= 0.073 af, Depth= 5.06"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 25-YR Rainfall=5.30"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 7,586     | 98 | Paved parking, HSG D    |
| 7,586     |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 7S: PWS#4



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 91

### Summary for Subcatchment 9S: PWS#5

Runoff = 0.66 cfs @ 12.07 hrs, Volume= 0.050 af, Depth= 4.49"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-YR Rainfall=5.30"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 4,090     | 98 | Paved parking, HSG D          |
| 1,677     | 80 | >75% Grass cover, Good, HSG D |
| 5,767     | 93 | Weighted Average              |
| 1,677     |    | 29.08% Pervious Area          |
| 4,090     |    | 70.92% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 9S: PWS#5

Hydrograph





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 92


**Summary for Subcatchment 11S: PWS#6**

Runoff = 2.53 cfs @ 12.08 hrs, Volume= 0.180 af, Depth= 3.16"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-YR Rainfall=5.30"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 21,412    | 80 | >75% Grass cover, Good, HSG D |
| * 8,403   | 80 |                               |
| 29,815    | 80 | Weighted Average              |
| 29,815    |    | 100.00% Pervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 11S: PWS#6**

**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 93

**Summary for Subcatchment 13S: PWS#7**

Runoff = 0.88 cfs @ 12.07 hrs, Volume= 0.071 af, Depth= 5.06"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-YR Rainfall=5.30"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 7,376     | 98 | Paved parking, HSG D    |
| 7,376     |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 13S: PWS#7**

Hydrograph





## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 94

### Summary for Subcatchment 18S: ROOFS 1 - 14


Runoff = 1.21 cfs @ 12.07 hrs, Volume= 0.098 af, Depth= 5.06"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 25-YR Rainfall=5.30"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 10,080    | 98 | Roofs, HSG D            |
| 10,080    |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 18S: ROOFS 1 - 14



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 95

### Summary for Reach 4R: GRASS LINED SWALE #1

Inflow Area = 1.015 ac, 32.07% Impervious, Inflow Depth = 2.93" for 25-YR event  
Inflow = 3.27 cfs @ 12.09 hrs, Volume= 0.248 af  
Outflow = 3.08 cfs @ 12.16 hrs, Volume= 0.248 af, Atten= 6%, Lag= 4.7 min

Routing by Stor-Ind+Trans method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.71 fps, Min. Travel Time= 2.7 min

Avg. Velocity = 0.52 fps, Avg. Travel Time= 8.7 min

Peak Storage= 497 cf @ 12.12 hrs

Average Depth at Peak Storage= 0.27'

Bank-Full Depth= 1.00' Flow Area= 14.0 sf, Capacity= 50.43 cfs

4.00' x 1.00' deep channel, n= 0.030 Earth, grassed & winding

Side Slope Z-value= 10.0 '/' Top Width= 24.00'


Length= 275.0' Slope= 0.0109 '/'

Inlet Invert= 99.00', Outlet Invert= 96.00'



### Reach 4R: GRASS LINED SWALE #1

Hydrograph





## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 96

### Summary for Reach 12R: GRASS LINED SWALE #2

Inflow Area = 1.048 ac, 31.03% Impervious, Inflow Depth = 2.99" for 25-YR event  
Inflow = 3.39 cfs @ 12.09 hrs, Volume= 0.261 af  
Outflow = 3.20 cfs @ 12.16 hrs, Volume= 0.261 af, Atten= 6%, Lag= 4.7 min

Routing by Stor-Ind+Trans method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.70 fps, Min. Travel Time= 2.7 min

Avg. Velocity = 0.53 fps, Avg. Travel Time= 8.5 min

Peak Storage= 513 cf @ 12.12 hrs

Average Depth at Peak Storage= 0.27'

Bank-Full Depth= 1.00' Flow Area= 15.5 sf, Capacity= 55.70 cfs

4.00' x 1.00' deep channel, n= 0.030 Earth, grassed & winding

Side Slope Z-value= 4.0 19.0 '/' Top Width= 27.00'


Length= 270.0' Slope= 0.0111 '/'

Inlet Invert= 99.00', Outlet Invert= 96.00'



### Reach 12R: GRASS LINED SWALE #2

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 97

**Summary for Pond 8P: DETENTION POND #1**

Inflow Area = 1.189 ac, 42.02% Impervious, Inflow Depth = 3.23" for 25-YR event  
 Inflow = 3.76 cfs @ 12.15 hrs, Volume= 0.320 af  
 Outflow = 0.72 cfs @ 12.67 hrs, Volume= 0.300 af, Atten= 81%, Lag= 31.2 min  
 Discarded = 0.11 cfs @ 12.67 hrs, Volume= 0.178 af  
 Primary = 0.61 cfs @ 12.67 hrs, Volume= 0.123 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 95.42' @ 12.67 hrs Surf.Area= 3,764 sf Storage= 6,413 cf

Plug-Flow detention time= 321.0 min calculated for 0.300 af (94% of inflow)  
 Center-of-Mass det. time= 287.9 min ( 1,096.7 - 808.8 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 93.00' | 8,773 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 93.00               | 1,640                | 257.0            | 0                         | 0                         | 1,640               |
| 94.00               | 2,440                | 276.0            | 2,027                     | 2,027                     | 2,489               |
| 95.00               | 3,381                | 308.0            | 2,898                     | 4,925                     | 4,004               |
| 96.00               | 4,335                | 329.0            | 3,848                     | 8,773                     | 5,115               |

| Device | Routing   | Invert | Outlet Devices                                                                                                                                                                                                                                               |
|--------|-----------|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | Primary   | 95.50' | <b>6.0' long x 3.0' breadth Broad-Crested Rectangular Weir</b><br>Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00<br>2.50 3.00 3.50 4.00 4.50<br>Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68<br>2.72 2.81 2.92 2.97 3.07 3.32 |
| #2     | Primary   | 94.75' | <b>6.0" Vert. Orifice/Grate C= 0.600</b>                                                                                                                                                                                                                     |
| #3     | Discarded | 93.00' | <b>1.080 in/hr Exfiltration over Wetted area</b>                                                                                                                                                                                                             |

**Discarded OutFlow** Max=0.11 cfs @ 12.67 hrs HW=95.42' (Free Discharge)

**3=Exfiltration** (Exfiltration Controls 0.11 cfs)
**Primary OutFlow** Max=0.61 cfs @ 12.67 hrs HW=95.42' (Free Discharge)

**1=Broad-Crested Rectangular Weir** ( Controls 0.00 cfs)


**2=Orifice/Grate** (Orifice Controls 0.61 cfs @ 3.11 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 98

### Pond 8P: DETENTION POND #1





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 99

**Summary for Pond 14P: DETENTION POND #2**

Inflow Area = 1.218 ac, 40.62% Impervious, Inflow Depth = 3.27" for 25-YR event  
 Inflow = 3.88 cfs @ 12.15 hrs, Volume= 0.332 af  
 Outflow = 2.44 cfs @ 12.32 hrs, Volume= 0.278 af, Atten= 37%, Lag= 9.9 min  
 Discarded = 0.01 cfs @ 12.32 hrs, Volume= 0.012 af  
 Primary = 2.43 cfs @ 12.32 hrs, Volume= 0.265 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 95.66' @ 12.32 hrs Surf.Area= 2,785 sf Storage= 4,652 cf

Plug-Flow detention time= 137.0 min calculated for 0.277 af (84% of inflow)  
 Center-of-Mass det. time= 74.5 min ( 881.3 - 806.8 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 93.00' | 5,654 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 93.00               | 933                  | 130.0            | 0                         | 0                         | 933                 |
| 94.00               | 1,451                | 245.0            | 1,183                     | 1,183                     | 4,370               |
| 95.00               | 2,221                | 267.0            | 1,822                     | 3,005                     | 5,302               |
| 96.00               | 3,102                | 296.0            | 2,649                     | 5,654                     | 6,632               |

| Device | Routing   | Invert | Outlet Devices                                    |
|--------|-----------|--------|---------------------------------------------------|
| #1     | Primary   | 94.75' | <b>12.0" Vert. Orifice/Grate</b> C= 0.600         |
| #2     | Discarded | 93.00' | <b>0.110 in/hr Exfiltration over Surface area</b> |

**Discarded OutFlow** Max=0.01 cfs @ 12.32 hrs HW=95.66' (Free Discharge)  
 ↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=2.43 cfs @ 12.32 hrs HW=95.66' (Free Discharge)  
 ↑ **1=Orifice/Grate** (Orifice Controls 2.43 cfs @ 3.24 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 100

### Pond 14P: DETENTION POND #2



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 101

**Summary for Pond 20P: RECHARGE 1 - 8**

Inflow Area = 0.231 ac, 100.00% Impervious, Inflow Depth = 5.06" for 25-YR event  
 Inflow = 1.21 cfs @ 12.07 hrs, Volume= 0.098 af  
 Outflow = 0.94 cfs @ 12.14 hrs, Volume= 0.088 af, Atten= 22%, Lag= 4.0 min  
 Discarded = 0.01 cfs @ 12.14 hrs, Volume= 0.021 af  
 Primary = 0.93 cfs @ 12.14 hrs, Volume= 0.066 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 99.97' @ 12.14 hrs Surf.Area= 540 sf Storage= 1,076 cf

Plug-Flow detention time= 190.2 min calculated for 0.088 af (90% of inflow)  
 Center-of-Mass det. time= 138.9 min ( 885.0 - 746.1 )

| Volume | Invert | Avail.Storage | Storage Description                                                                                                                                                                                                    |
|--------|--------|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | 96.50' | 646 cf        | <b>12.00'W x 45.00'L x 4.00'H Prismatic</b><br>2,160 cf Overall - 544 cf Embedded = 1,616 cf x 40.0% Voids                                                                                                             |
| #2     | 97.00' | 544 cf        | <b>Cultec R-330XL x 10 Inside #1</b><br>Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf<br>Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap<br>Row Length Adjustment= +1.50' x 7.45 sf x 2 rows |
|        |        | 1,190 cf      | Total Available Storage                                                                                                                                                                                                |

| Device | Routing   | Invert | Outlet Devices                                   |
|--------|-----------|--------|--------------------------------------------------|
| #1     | Primary   | 98.75' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600         |
| #2     | Discarded | 96.50' | <b>0.440 in/hr Exfiltration over Wetted area</b> |

**Discarded OutFlow** Max=0.01 cfs @ 12.14 hrs HW=99.95' (Free Discharge)

↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.92 cfs @ 12.14 hrs HW=99.95' (Free Discharge)

↑ **1=Orifice/Grate** (Orifice Controls 0.92 cfs @ 4.70 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 102

### Pond 20P: RECHARGE 1 - 8



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 103

**Summary for Pond 23P: RECHARGE 15-28**

Inflow Area = 0.231 ac, 100.00% Impervious, Inflow Depth = 5.06" for 25-YR event  
 Inflow = 1.21 cfs @ 12.07 hrs, Volume= 0.098 af  
 Outflow = 0.94 cfs @ 12.14 hrs, Volume= 0.088 af, Atten= 22%, Lag= 4.0 min  
 Discarded = 0.01 cfs @ 12.14 hrs, Volume= 0.021 af  
 Primary = 0.93 cfs @ 12.14 hrs, Volume= 0.066 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 99.97' @ 12.14 hrs Surf.Area= 540 sf Storage= 1,076 cf

Plug-Flow detention time= 190.2 min calculated for 0.088 af (90% of inflow)  
 Center-of-Mass det. time= 138.9 min ( 885.0 - 746.1 )

| Volume | Invert | Avail.Storage | Storage Description                                                                                                                                                                                                    |
|--------|--------|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | 96.50' | 646 cf        | <b>12.00'W x 45.00'L x 4.00'H Prismatic</b><br>2,160 cf Overall - 544 cf Embedded = 1,616 cf x 40.0% Voids                                                                                                             |
| #2     | 97.00' | 544 cf        | <b>Cultec R-330XL</b> x 10 Inside #1<br>Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf<br>Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap<br>Row Length Adjustment= +1.50' x 7.45 sf x 2 rows |
|        |        | 1,190 cf      | Total Available Storage                                                                                                                                                                                                |

| Device | Routing   | Invert | Outlet Devices                                   |
|--------|-----------|--------|--------------------------------------------------|
| #1     | Primary   | 98.75' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600         |
| #2     | Discarded | 96.50' | <b>0.440 in/hr Exfiltration over Wetted area</b> |

**Discarded OutFlow** Max=0.01 cfs @ 12.14 hrs HW=99.95' (Free Discharge)

↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.92 cfs @ 12.14 hrs HW=99.95' (Free Discharge)

↑ **1=Orifice/Grate** (Orifice Controls 0.92 cfs @ 4.70 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 104

### Pond 23P: RECHARGE 15-28





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC  
 HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 105

**Summary for Pond 25P: BIORETENTION BASIN**

Inflow Area = 0.133 ac, 70.93% Impervious, Inflow Depth = 4.49" for 25-YR event  
 Inflow = 0.66 cfs @ 12.07 hrs, Volume= 0.050 af  
 Outflow = 0.06 cfs @ 13.01 hrs, Volume= 0.023 af, Atten= 92%, Lag= 56.1 min  
 Discarded = 0.01 cfs @ 13.01 hrs, Volume= 0.012 af  
 Primary = 0.05 cfs @ 13.01 hrs, Volume= 0.010 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 99.78' @ 13.01 hrs Surf.Area= 587 sf Storage= 1,398 cf

Plug-Flow detention time= 460.7 min calculated for 0.023 af (46% of inflow)  
 Center-of-Mass det. time= 338.2 min ( 1,113.8 - 775.6 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.50' | 1,538 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 95.50               | 302                  | 122.0            | 0                         | 0                         | 302                 |
| 96.00               | 302                  | 122.0            | 151                       | 151                       | 363                 |
| 98.75               | 302                  | 122.0            | 831                       | 982                       | 699                 |
| 99.00               | 302                  | 122.0            | 76                        | 1,057                     | 729                 |
| 100.00              | 685                  | 146.0            | 481                       | 1,538                     | 1,258               |

| Device | Routing   | Invert | Outlet Devices                                                                                         |
|--------|-----------|--------|--------------------------------------------------------------------------------------------------------|
| #1     | Primary   | 99.75' | <b>2.0' long x 2.00' rise Sharp-Crested Rectangular Weir</b><br>2 End Contraction(s) 0.7' Crest Height |
| #2     | Discarded | 95.50' | <b>0.440 in/hr Exfiltration over Surface area</b>                                                      |

**Discarded OutFlow** Max=0.01 cfs @ 13.01 hrs HW=99.78' (Free Discharge)  
 ↳ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.03 cfs @ 13.01 hrs HW=99.78' (Free Discharge)  
 ↳ **1=Sharp-Crested Rectangular Weir** (Weir Controls 0.03 cfs @ 0.57 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 106

### Pond 25P: BIORETENTION BASIN



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 107

**Summary for Pond 26P: BIORETENTION BASIN**

Inflow Area = 0.132 ac, 70.92% Impervious, Inflow Depth = 4.49" for 25-YR event  
 Inflow = 0.66 cfs @ 12.07 hrs, Volume= 0.050 af  
 Outflow = 0.19 cfs @ 12.41 hrs, Volume= 0.034 af, Atten= 72%, Lag= 20.4 min  
 Discarded = 0.01 cfs @ 12.41 hrs, Volume= 0.019 af  
 Primary = 0.18 cfs @ 12.41 hrs, Volume= 0.015 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 99.85' @ 12.41 hrs Surf.Area= 973 sf Storage= 1,123 cf

Plug-Flow detention time= 391.9 min calculated for 0.034 af (68% of inflow)  
 Center-of-Mass det. time= 297.6 min ( 1,073.2 - 775.6 )

| Volume              | Invert               | Avail.Storage    | Storage Description                                        |                           |                           |                     |
|---------------------|----------------------|------------------|------------------------------------------------------------|---------------------------|---------------------------|---------------------|
| #1                  | 95.50'               | 2,456 cf         | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |                           |                           |                     |
| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Voids<br>(%)                                               | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
| 95.50               | 425                  | 167.0            | 0.0                                                        | 0                         | 0                         | 425                 |
| 96.00               | 425                  | 167.0            | 40.0                                                       | 85                        | 85                        | 509                 |
| 98.75               | 425                  | 167.0            | 30.0                                                       | 351                       | 436                       | 968                 |
| 99.00               | 425                  | 167.0            | 100.0                                                      | 106                       | 542                       | 1,010               |
| 100.00              | 1,088                | 213.0            | 100.0                                                      | 731                       | 1,273                     | 2,413               |
| 101.00              | 1,281                | 181.0            | 100.0                                                      | 1,183                     | 2,456                     | 3,436               |

| Device | Routing   | Invert | Outlet Devices                                                 |  |  |  |  |  |  |  |  |  |  |  |
|--------|-----------|--------|----------------------------------------------------------------|--|--|--|--|--|--|--|--|--|--|--|
| #1     | Primary   | 99.75' | <b>2.0' long x 2.0' breadth Broad-Crested Rectangular Weir</b> |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00  |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | 2.50 3.00 3.50                                                 |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | Coef. (English) 2.54 2.61 2.61 2.60 2.66 2.70 2.77 2.89 2.88   |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | 2.85 3.07 3.20 3.32                                            |  |  |  |  |  |  |  |  |  |  |  |
| #2     | Discarded | 95.50' | <b>0.440 in/hr Exfiltration over Surface area</b>              |  |  |  |  |  |  |  |  |  |  |  |

**Discarded OutFlow** Max=0.01 cfs @ 12.41 hrs HW=99.85' (Free Discharge)

↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.17 cfs @ 12.41 hrs HW=99.85' (Free Discharge)

↑ **1=Broad-Crested Rectangular Weir** (Weir Controls 0.17 cfs @ 0.82 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 108

### Pond 26P: BIORETENTION BASIN



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 109

**Summary for Pond 29P: TREE BOX FILTER**

Inflow Area = 0.174 ac, 100.00% Impervious, Inflow Depth = 5.06" for 25-YR event  
 Inflow = 0.91 cfs @ 12.07 hrs, Volume= 0.073 af  
 Outflow = 0.92 cfs @ 12.10 hrs, Volume= 0.072 af, Atten= 0%, Lag= 1.5 min  
 Primary = 0.92 cfs @ 12.10 hrs, Volume= 0.072 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 98.45' @ 12.10 hrs Surf.Area= 60 sf Storage= 93 cf

Plug-Flow detention time= 19.8 min calculated for 0.072 af (98% of inflow)  
 Center-of-Mass det. time= 10.1 min ( 756.2 - 746.1 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.00' | 93 cf         | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Voids<br>(%) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) |
|---------------------|----------------------|--------------|---------------------------|---------------------------|
| 95.00               | 60                   | 0.0          | 0                         | 0                         |
| 95.50               | 60                   | 40.0         | 12                        | 12                        |
| 97.50               | 60                   | 30.0         | 36                        | 48                        |
| 98.25               | 60                   | 100.0        | 45                        | 93                        |

| Device | Routing  | Invert | Outlet Devices                                               |
|--------|----------|--------|--------------------------------------------------------------|
| #1     | Device 2 | 95.00' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600                     |
| #2     | Primary  | 97.50' | <b>1.0" W x 18.0" H Vert. Orifice/Grate X 10.00</b> C= 0.600 |

**Primary OutFlow** Max=0.91 cfs @ 12.10 hrs HW=98.42' (Free Discharge)

↑ **2=Orifice/Grate** (Passes 0.91 cfs of 2.36 cfs potential flow)

↑ **1=Orifice/Grate** (Orifice Controls 0.91 cfs @ 4.62 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 110

### Pond 29P: TREE BOX FILTER

Hydrograph



**Prop-Conditions**

Type III 24-hr 25-YR Rainfall=5.30"

Prepared by Cornerstone Land Associates, LLC

Printed 6/1/2023

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Page 111

**Summary for Pond 33P: TREE BOX FILTER**

Inflow Area = 0.169 ac, 100.00% Impervious, Inflow Depth = 5.06" for 25-YR event  
 Inflow = 0.88 cfs @ 12.07 hrs, Volume= 0.071 af  
 Outflow = 0.87 cfs @ 12.10 hrs, Volume= 0.070 af, Atten= 2%, Lag= 1.6 min  
 Primary = 0.87 cfs @ 12.10 hrs, Volume= 0.070 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 98.34' @ 12.10 hrs Surf.Area= 60 sf Storage= 93 cf

Plug-Flow detention time= 20.4 min calculated for 0.070 af (98% of inflow)  
 Center-of-Mass det. time= 10.3 min ( 756.5 - 746.1 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.00' | 93 cf         | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Voids<br>(%) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) |
|---------------------|----------------------|--------------|---------------------------|---------------------------|
| 95.00               | 60                   | 0.0          | 0                         | 0                         |
| 95.50               | 60                   | 40.0         | 12                        | 12                        |
| 97.50               | 60                   | 30.0         | 36                        | 48                        |
| 98.25               | 60                   | 100.0        | 45                        | 93                        |

| Device | Routing  | Invert | Outlet Devices                                               |
|--------|----------|--------|--------------------------------------------------------------|
| #1     | Device 2 | 95.00' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600                     |
| #2     | Primary  | 97.50' | <b>1.0" W x 18.0" H Vert. Orifice/Grate X 10.00</b> C= 0.600 |

**Primary OutFlow** Max=0.86 cfs @ 12.10 hrs HW=98.33' (Free Discharge)

↑ **2=Orifice/Grate** (Passes 0.86 cfs of 2.01 cfs potential flow)

↑ **1=Orifice/Grate** (Orifice Controls 0.86 cfs @ 4.38 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023

Page 112

### Pond 33P: TREE BOX FILTER

Hydrograph



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=5.30"

Printed 6/1/2023


Page 113

### Summary for Link 15L: DP#2-REAR WETLANDS

Inflow Area = 2.406 ac, 41.32% Impervious, Inflow Depth = 1.94" for 25-YR event  
Inflow = 2.86 cfs @ 12.38 hrs, Volume= 0.388 af  
Primary = 2.86 cfs @ 12.38 hrs, Volume= 0.388 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

### Link 15L: DP#2-REAR WETLANDS



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 114


### Summary for Subcatchment 1S: DP#1-GREENMONT

Runoff = 0.25 cfs @ 12.00 hrs, Volume= 0.016 af, Depth= 4.21"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 50-YR Rainfall=5.90"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 569       | 98 | Paved parking, HSG D          |
| 1,380     | 80 | >75% Grass cover, Good, HSG D |
| 1,949     | 85 | Weighted Average              |
| 1,380     |    | 70.81% Pervious Area          |
| 569       |    | 29.19% Impervious Area        |

### Subcatchment 1S: DP#1-GREENMONT





## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 115

### Summary for Subcatchment 3S: PWS#2

Runoff = 0.74 cfs @ 12.07 hrs, Volume= 0.056 af, Depth= 5.08"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs


Type III 24-hr 50-YR Rainfall=5.90"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 4,094     | 98 | Paved parking, HSG D          |
| 1,678     | 80 | >75% Grass cover, Good, HSG D |
| 5,772     | 93 | Weighted Average              |
| 1,678     |    | 29.07% Pervious Area          |
| 4,094     |    | 70.93% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 3S: PWS#2

Hydrograph





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 116


**Summary for Subcatchment 5S: ROOFS 15 - 28**

Runoff = 1.35 cfs @ 12.07 hrs, Volume= 0.109 af, Depth= 5.66"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 50-YR Rainfall=5.90"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 10,080    | 98 | Roofs, HSG D            |
| 10,080    |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 5S: ROOFS 15 - 28**

**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 117

**Summary for Subcatchment 6S: PWS#3**

Runoff = 2.80 cfs @ 12.08 hrs, Volume= 0.200 af, Depth= 3.69"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs


Type III 24-hr 50-YR Rainfall=5.90"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 18,244    | 80 | >75% Grass cover, Good, HSG D |
| * 10,097  | 80 |                               |
| 28,341    | 80 | Weighted Average              |
| 28,341    |    | 100.00% Pervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 6S: PWS#3**

Hydrograph



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 118

### Summary for Subcatchment 7S: PWS#4

Runoff = 1.01 cfs @ 12.07 hrs, Volume= 0.082 af, Depth= 5.66"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 50-YR Rainfall=5.90"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 7,586     | 98 | Paved parking, HSG D    |
| 7,586     |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 7S: PWS#4





## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC  
HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 119

### Summary for Subcatchment 9S: PWS#5

Runoff = 0.74 cfs @ 12.07 hrs, Volume= 0.056 af, Depth= 5.08"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 50-YR Rainfall=5.90"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 4,090     | 98 | Paved parking, HSG D          |
| 1,677     | 80 | >75% Grass cover, Good, HSG D |
| 5,767     | 93 | Weighted Average              |
| 1,677     |    | 29.08% Pervious Area          |
| 4,090     |    | 70.92% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 9S: PWS#5

Hydrograph





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 120


**Summary for Subcatchment 11S: PWS#6**

Runoff = 2.95 cfs @ 12.08 hrs, Volume= 0.211 af, Depth= 3.69"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 50-YR Rainfall=5.90"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 21,412    | 80 | >75% Grass cover, Good, HSG D |
| * 8,403   | 80 |                               |
| 29,815    | 80 | Weighted Average              |
| 29,815    |    | 100.00% Pervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 11S: PWS#6**

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 121

### Summary for Subcatchment 13S: PWS#7

Runoff = 0.99 cfs @ 12.07 hrs, Volume= 0.080 af, Depth= 5.66"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 50-YR Rainfall=5.90"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 7,376     | 98 | Paved parking, HSG D    |
| 7,376     |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 13S: PWS#7





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 122

**Summary for Subcatchment 18S: ROOFS 1 - 14**


Runoff = 1.35 cfs @ 12.07 hrs, Volume= 0.109 af, Depth= 5.66"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 50-YR Rainfall=5.90"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 10,080    | 98 | Roofs, HSG D            |
| 10,080    |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 18S: ROOFS 1 - 14**



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 123

### Summary for Reach 4R: GRASS LINED SWALE #1

Inflow Area = 1.015 ac, 32.07% Impervious, Inflow Depth = 3.48" for 50-YR event  
Inflow = 3.74 cfs @ 12.08 hrs, Volume= 0.295 af  
Outflow = 3.54 cfs @ 12.16 hrs, Volume= 0.295 af, Atten= 6%, Lag= 4.6 min

Routing by Stor-Ind+Trans method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.78 fps, Min. Travel Time= 2.6 min

Avg. Velocity = 0.55 fps, Avg. Travel Time= 8.3 min

Peak Storage= 550 cf @ 12.12 hrs

Average Depth at Peak Storage= 0.29'

Bank-Full Depth= 1.00' Flow Area= 14.0 sf, Capacity= 50.43 cfs

4.00' x 1.00' deep channel, n= 0.030 Earth, grassed & winding

Side Slope Z-value= 10.0 '/' Top Width= 24.00'


Length= 275.0' Slope= 0.0109 '/'

Inlet Invert= 99.00', Outlet Invert= 96.00'



### Reach 4R: GRASS LINED SWALE #1

Hydrograph



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 124

### Summary for Reach 12R: GRASS LINED SWALE #2

Inflow Area = 1.048 ac, 31.03% Impervious, Inflow Depth = 3.54" for 50-YR event  
Inflow = 3.88 cfs @ 12.09 hrs, Volume= 0.309 af  
Outflow = 3.69 cfs @ 12.16 hrs, Volume= 0.309 af, Atten= 5%, Lag= 4.7 min

Routing by Stor-Ind+Trans method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.76 fps, Min. Travel Time= 2.6 min

Avg. Velocity = 0.55 fps, Avg. Travel Time= 8.2 min

Peak Storage= 569 cf @ 12.12 hrs

Average Depth at Peak Storage= 0.29'

Bank-Full Depth= 1.00' Flow Area= 15.5 sf, Capacity= 55.70 cfs

4.00' x 1.00' deep channel, n= 0.030 Earth, grassed & winding

Side Slope Z-value= 4.0 19.0 '/' Top Width= 27.00'


Length= 270.0' Slope= 0.0111 '/'

Inlet Invert= 99.00', Outlet Invert= 96.00'



### Reach 12R: GRASS LINED SWALE #2

Hydrograph



**Prop-Conditions**

Type III 24-hr 50-YR Rainfall=5.90"

Prepared by Cornerstone Land Associates, LLC

Printed 6/1/2023

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Page 125

**Summary for Pond 8P: DETENTION POND #1**

Inflow Area = 1.189 ac, 42.02% Impervious, Inflow Depth = 3.79" for 50-YR event  
 Inflow = 4.23 cfs @ 12.14 hrs, Volume= 0.376 af  
 Outflow = 1.37 cfs @ 12.56 hrs, Volume= 0.353 af, Atten= 68%, Lag= 25.0 min  
 Discarded = 0.12 cfs @ 12.56 hrs, Volume= 0.183 af  
 Primary = 1.25 cfs @ 12.56 hrs, Volume= 0.171 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 95.61' @ 12.56 hrs Surf.Area= 3,946 sf Storage= 7,147 cf

Plug-Flow detention time= 283.3 min calculated for 0.353 af (94% of inflow)  
 Center-of-Mass det. time= 252.6 min ( 1,058.2 - 805.6 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 93.00' | 8,773 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 93.00               | 1,640                | 257.0            | 0                         | 0                         | 1,640               |
| 94.00               | 2,440                | 276.0            | 2,027                     | 2,027                     | 2,489               |
| 95.00               | 3,381                | 308.0            | 2,898                     | 4,925                     | 4,004               |
| 96.00               | 4,335                | 329.0            | 3,848                     | 8,773                     | 5,115               |

| Device | Routing   | Invert | Outlet Devices                                                                                                                                                                                                                                               |
|--------|-----------|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | Primary   | 95.50' | <b>6.0' long x 3.0' breadth Broad-Crested Rectangular Weir</b><br>Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00<br>2.50 3.00 3.50 4.00 4.50<br>Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68<br>2.72 2.81 2.92 2.97 3.07 3.32 |
| #2     | Primary   | 94.75' | <b>6.0" Vert. Orifice/Grate C= 0.600</b>                                                                                                                                                                                                                     |
| #3     | Discarded | 93.00' | <b>1.080 in/hr Exfiltration over Wetted area</b>                                                                                                                                                                                                             |

**Discarded OutFlow** Max=0.12 cfs @ 12.56 hrs HW=95.61' (Free Discharge)  
 ↳ **3=Exfiltration** (Exfiltration Controls 0.12 cfs)

**Primary OutFlow** Max=1.24 cfs @ 12.56 hrs HW=95.61' (Free Discharge)  
 ↳ **1=Broad-Crested Rectangular Weir** (Weir Controls 0.51 cfs @ 0.80 fps)  
 ↳ **2=Orifice/Grate** (Orifice Controls 0.74 cfs @ 3.75 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 126

### Pond 8P: DETENTION POND #1



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 127

**Summary for Pond 14P: DETENTION POND #2**

Inflow Area = 1.218 ac, 40.62% Impervious, Inflow Depth = 3.82" for 50-YR event  
 Inflow = 4.35 cfs @ 12.15 hrs, Volume= 0.388 af  
 Outflow = 2.87 cfs @ 12.32 hrs, Volume= 0.334 af, Atten= 34%, Lag= 10.7 min  
 Discarded = 0.01 cfs @ 12.32 hrs, Volume= 0.013 af  
 Primary = 2.87 cfs @ 12.32 hrs, Volume= 0.322 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 95.82' @ 12.32 hrs Surf.Area= 2,937 sf Storage= 5,125 cf

Plug-Flow detention time= 124.2 min calculated for 0.334 af (86% of inflow)  
 Center-of-Mass det. time= 67.5 min ( 871.1 - 803.5 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 93.00' | 5,654 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 93.00               | 933                  | 130.0            | 0                         | 0                         | 933                 |
| 94.00               | 1,451                | 245.0            | 1,183                     | 1,183                     | 4,370               |
| 95.00               | 2,221                | 267.0            | 1,822                     | 3,005                     | 5,302               |
| 96.00               | 3,102                | 296.0            | 2,649                     | 5,654                     | 6,632               |

| Device | Routing   | Invert | Outlet Devices                                    |
|--------|-----------|--------|---------------------------------------------------|
| #1     | Primary   | 94.75' | <b>12.0" Vert. Orifice/Grate</b> C= 0.600         |
| #2     | Discarded | 93.00' | <b>0.110 in/hr Exfiltration over Surface area</b> |

**Discarded OutFlow** Max=0.01 cfs @ 12.32 hrs HW=95.82' (Free Discharge)  
 ↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=2.86 cfs @ 12.32 hrs HW=95.82' (Free Discharge)  
 ↑ **1=Orifice/Grate** (Orifice Controls 2.86 cfs @ 3.64 fps)

**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 128

**Pond 14P: DETENTION POND #2**

Hydrograph





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 129

**Summary for Pond 20P: RECHARGE 1 - 8**

Inflow Area = 0.231 ac, 100.00% Impervious, Inflow Depth = 5.66" for 50-YR event  
 Inflow = 1.35 cfs @ 12.07 hrs, Volume= 0.109 af  
 Outflow = 1.03 cfs @ 12.14 hrs, Volume= 0.099 af, Atten= 23%, Lag= 4.2 min  
 Discarded = 0.01 cfs @ 12.14 hrs, Volume= 0.021 af  
 Primary = 1.02 cfs @ 12.14 hrs, Volume= 0.078 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 100.16' @ 12.14 hrs Surf.Area= 540 sf Storage= 1,118 cf

Plug-Flow detention time= 175.7 min calculated for 0.099 af (91% of inflow)  
 Center-of-Mass det. time= 128.1 min ( 872.6 - 744.5 )

| Volume   | Invert | Avail.Storage | Storage Description                                                                                                                                                                                                    |
|----------|--------|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1       | 96.50' | 646 cf        | <b>12.00'W x 45.00'L x 4.00'H Prismatoid</b><br>2,160 cf Overall - 544 cf Embedded = 1,616 cf x 40.0% Voids                                                                                                            |
| #2       | 97.00' | 544 cf        | <b>Cultec R-330XL</b> x 10 Inside #1<br>Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf<br>Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap<br>Row Length Adjustment= +1.50' x 7.45 sf x 2 rows |
| 1,190 cf |        |               | Total Available Storage                                                                                                                                                                                                |

| Device | Routing   | Invert | Outlet Devices                                   |
|--------|-----------|--------|--------------------------------------------------|
| #1     | Primary   | 98.75' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600         |
| #2     | Discarded | 96.50' | <b>0.440 in/hr Exfiltration over Wetted area</b> |

**Discarded OutFlow** Max=0.01 cfs @ 12.14 hrs HW=100.15' (Free Discharge)  
 ↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=1.01 cfs @ 12.14 hrs HW=100.15' (Free Discharge)  
 ↑ **1=Orifice/Grate** (Orifice Controls 1.01 cfs @ 5.16 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 130

### Pond 20P: RECHARGE 1 - 8

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 131

**Summary for Pond 23P: RECHARGE 15-28**

Inflow Area = 0.231 ac, 100.00% Impervious, Inflow Depth = 5.66" for 50-YR event  
 Inflow = 1.35 cfs @ 12.07 hrs, Volume= 0.109 af  
 Outflow = 1.03 cfs @ 12.14 hrs, Volume= 0.099 af, Atten= 23%, Lag= 4.2 min  
 Discarded = 0.01 cfs @ 12.14 hrs, Volume= 0.021 af  
 Primary = 1.02 cfs @ 12.14 hrs, Volume= 0.078 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 100.16' @ 12.14 hrs Surf.Area= 540 sf Storage= 1,118 cf

Plug-Flow detention time= 175.7 min calculated for 0.099 af (91% of inflow)  
 Center-of-Mass det. time= 128.1 min ( 872.6 - 744.5 )

| Volume | Invert | Avail.Storage | Storage Description                                                                                                                                                                                                    |
|--------|--------|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | 96.50' | 646 cf        | <b>12.00'W x 45.00'L x 4.00'H Prismaoid</b><br>2,160 cf Overall - 544 cf Embedded = 1,616 cf x 40.0% Voids                                                                                                             |
| #2     | 97.00' | 544 cf        | <b>Cultec R-330XL x 10 Inside #1</b><br>Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf<br>Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap<br>Row Length Adjustment= +1.50' x 7.45 sf x 2 rows |
|        |        | 1,190 cf      | Total Available Storage                                                                                                                                                                                                |

| Device | Routing   | Invert | Outlet Devices                                   |
|--------|-----------|--------|--------------------------------------------------|
| #1     | Primary   | 98.75' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600         |
| #2     | Discarded | 96.50' | <b>0.440 in/hr Exfiltration over Wetted area</b> |

**Discarded OutFlow** Max=0.01 cfs @ 12.14 hrs HW=100.15' (Free Discharge)  
 ↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=1.01 cfs @ 12.14 hrs HW=100.15' (Free Discharge)  
 ↑ **1=Orifice/Grate** (Orifice Controls 1.01 cfs @ 5.16 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 132

### Pond 23P: RECHARGE 15-28



**Prop-Conditions**

Type III 24-hr 50-YR Rainfall=5.90"

Prepared by Cornerstone Land Associates, LLC

Printed 6/1/2023

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Page 133

**Summary for Pond 25P: BIORETENTION BASIN**

Inflow Area = 0.133 ac, 70.93% Impervious, Inflow Depth = 5.08" for 50-YR event  
 Inflow = 0.74 cfs @ 12.07 hrs, Volume= 0.056 af  
 Outflow = 0.16 cfs @ 12.48 hrs, Volume= 0.029 af, Atten= 78%, Lag= 24.3 min  
 Discarded = 0.01 cfs @ 12.48 hrs, Volume= 0.013 af  
 Primary = 0.16 cfs @ 12.48 hrs, Volume= 0.017 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 99.83' @ 12.48 hrs Surf.Area= 609 sf Storage= 1,428 cf

Plug-Flow detention time= 388.5 min calculated for 0.029 af (52% of inflow)  
 Center-of-Mass det. time= 274.2 min ( 1,046.8 - 772.5 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.50' | 1,538 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 95.50               | 302                  | 122.0            | 0                         | 0                         | 302                 |
| 96.00               | 302                  | 122.0            | 151                       | 151                       | 363                 |
| 98.75               | 302                  | 122.0            | 831                       | 982                       | 699                 |
| 99.00               | 302                  | 122.0            | 76                        | 1,057                     | 729                 |
| 100.00              | 685                  | 146.0            | 481                       | 1,538                     | 1,258               |

| Device | Routing   | Invert | Outlet Devices                                                                                         |
|--------|-----------|--------|--------------------------------------------------------------------------------------------------------|
| #1     | Primary   | 99.75' | <b>2.0' long x 2.00' rise Sharp-Crested Rectangular Weir</b><br>2 End Contraction(s) 0.7' Crest Height |
| #2     | Discarded | 95.50' | <b>0.440 in/hr Exfiltration over Surface area</b>                                                      |

**Discarded OutFlow** Max=0.01 cfs @ 12.48 hrs HW=99.83' (Free Discharge)  
 ↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.15 cfs @ 12.48 hrs HW=99.83' (Free Discharge)  
 ↑ **1=Sharp-Crested Rectangular Weir** (Weir Controls 0.15 cfs @ 0.93 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 134

### Pond 25P: BIORETENTION BASIN

Hydrograph





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 135

**Summary for Pond 26P: BIORETENTION BASIN**

Inflow Area = 0.132 ac, 70.92% Impervious, Inflow Depth = 5.08" for 50-YR event  
 Inflow = 0.74 cfs @ 12.07 hrs, Volume= 0.056 af  
 Outflow = 0.29 cfs @ 12.29 hrs, Volume= 0.040 af, Atten= 61%, Lag= 13.3 min  
 Discarded = 0.01 cfs @ 12.29 hrs, Volume= 0.019 af  
 Primary = 0.28 cfs @ 12.29 hrs, Volume= 0.021 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 99.89' @ 12.29 hrs Surf.Area= 1,003 sf Storage= 1,162 cf

Plug-Flow detention time= 344.5 min calculated for 0.040 af (72% of inflow)  
 Center-of-Mass det. time= 256.1 min ( 1,028.6 - 772.5 )

| Volume              | Invert               | Avail.Storage    | Storage Description                                        |                           |                           |                     |
|---------------------|----------------------|------------------|------------------------------------------------------------|---------------------------|---------------------------|---------------------|
| #1                  | 95.50'               | 2,456 cf         | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |                           |                           |                     |
| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Voids<br>(%)                                               | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
| 95.50               | 425                  | 167.0            | 0.0                                                        | 0                         | 0                         | 425                 |
| 96.00               | 425                  | 167.0            | 40.0                                                       | 85                        | 85                        | 509                 |
| 98.75               | 425                  | 167.0            | 30.0                                                       | 351                       | 436                       | 968                 |
| 99.00               | 425                  | 167.0            | 100.0                                                      | 106                       | 542                       | 1,010               |
| 100.00              | 1,088                | 213.0            | 100.0                                                      | 731                       | 1,273                     | 2,413               |
| 101.00              | 1,281                | 181.0            | 100.0                                                      | 1,183                     | 2,456                     | 3,436               |

| Device | Routing   | Invert | Outlet Devices                                                 |  |  |  |  |  |  |  |  |  |  |  |
|--------|-----------|--------|----------------------------------------------------------------|--|--|--|--|--|--|--|--|--|--|--|
| #1     | Primary   | 99.75' | <b>2.0' long x 2.0' breadth Broad-Crested Rectangular Weir</b> |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00  |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | 2.50 3.00 3.50                                                 |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | Coef. (English) 2.54 2.61 2.61 2.60 2.66 2.70 2.77 2.89 2.88   |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | 2.85 3.07 3.20 3.32                                            |  |  |  |  |  |  |  |  |  |  |  |
| #2     | Discarded | 95.50' | <b>0.440 in/hr Exfiltration over Surface area</b>              |  |  |  |  |  |  |  |  |  |  |  |

**Discarded OutFlow** Max=0.01 cfs @ 12.29 hrs HW=99.89' (Free Discharge)

↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.28 cfs @ 12.29 hrs HW=99.89' (Free Discharge)

↑ **1=Broad-Crested Rectangular Weir** (Weir Controls 0.28 cfs @ 0.96 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 136

### Pond 26P: BIORETENTION BASIN

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 137

**Summary for Pond 29P: TREE BOX FILTER**

Inflow Area = 0.174 ac, 100.00% Impervious, Inflow Depth = 5.66" for 50-YR event  
 Inflow = 1.01 cfs @ 12.07 hrs, Volume= 0.082 af  
 Outflow = 1.09 cfs @ 12.09 hrs, Volume= 0.081 af, Atten= 0%, Lag= 1.4 min  
 Primary = 1.09 cfs @ 12.09 hrs, Volume= 0.081 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 98.82' @ 12.09 hrs Surf.Area= 60 sf Storage= 93 cf

Plug-Flow detention time= 18.0 min calculated for 0.081 af (99% of inflow)  
 Center-of-Mass det. time= 9.3 min ( 753.8 - 744.5 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.00' | 93 cf         | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Voids<br>(%) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) |
|---------------------|----------------------|--------------|---------------------------|---------------------------|
| 95.00               | 60                   | 0.0          | 0                         | 0                         |
| 95.50               | 60                   | 40.0         | 12                        | 12                        |
| 97.50               | 60                   | 30.0         | 36                        | 48                        |
| 98.25               | 60                   | 100.0        | 45                        | 93                        |

| Device | Routing  | Invert | Outlet Devices                                               |
|--------|----------|--------|--------------------------------------------------------------|
| #1     | Device 2 | 95.00' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600                     |
| #2     | Primary  | 97.50' | <b>1.0" W x 18.0" H Vert. Orifice/Grate X 10.00</b> C= 0.600 |

**Primary OutFlow** Max=1.06 cfs @ 12.09 hrs HW=98.75' (Free Discharge)

↑ **2=Orifice/Grate** (Passes 1.06 cfs of 3.74 cfs potential flow)

↑ **1=Orifice/Grate** (Orifice Controls 1.06 cfs @ 5.38 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 138

### Pond 29P: TREE BOX FILTER



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 139

**Summary for Pond 33P: TREE BOX FILTER**

Inflow Area = 0.169 ac, 100.00% Impervious, Inflow Depth = 5.66" for 50-YR event  
 Inflow = 0.99 cfs @ 12.07 hrs, Volume= 0.080 af  
 Outflow = 1.08 cfs @ 12.09 hrs, Volume= 0.079 af, Atten= 0%, Lag= 1.5 min  
 Primary = 1.08 cfs @ 12.09 hrs, Volume= 0.079 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 98.80' @ 12.10 hrs Surf.Area= 60 sf Storage= 93 cf

Plug-Flow detention time= 18.6 min calculated for 0.079 af (99% of inflow)  
 Center-of-Mass det. time= 9.5 min ( 754.0 - 744.5 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.00' | 93 cf         | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Voids<br>(%) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) |
|---------------------|----------------------|--------------|---------------------------|---------------------------|
| 95.00               | 60                   | 0.0          | 0                         | 0                         |
| 95.50               | 60                   | 40.0         | 12                        | 12                        |
| 97.50               | 60                   | 30.0         | 36                        | 48                        |
| 98.25               | 60                   | 100.0        | 45                        | 93                        |

| Device | Routing  | Invert | Outlet Devices                                               |
|--------|----------|--------|--------------------------------------------------------------|
| #1     | Device 2 | 95.00' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600                     |
| #2     | Primary  | 97.50' | <b>1.0" W x 18.0" H Vert. Orifice/Grate X 10.00</b> C= 0.600 |

**Primary OutFlow** Max=1.05 cfs @ 12.09 hrs HW=98.74' (Free Discharge)

↑ **2=Orifice/Grate** (Passes 1.05 cfs of 3.67 cfs potential flow)

↑ **1=Orifice/Grate** (Orifice Controls 1.05 cfs @ 5.35 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC


Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023

Page 140

### Pond 33P: TREE BOX FILTER

Hydrograph



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=5.90"

Printed 6/1/2023


Page 141

### Summary for Link 15L: DP#2-REAR WETLANDS

Inflow Area = 2.406 ac, 41.32% Impervious, Inflow Depth = 2.45" for 50-YR event  
Inflow = 3.80 cfs @ 12.49 hrs, Volume= 0.492 af  
Primary = 3.80 cfs @ 12.49 hrs, Volume= 0.492 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

### Link 15L: DP#2-REAR WETLANDS





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 142

**Summary for Subcatchment 1S: DP#1-GREENMONT**


Runoff = 0.28 cfs @ 12.00 hrs, Volume= 0.017 af, Depth= 4.68"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 100-YR Rainfall=6.40"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 569       | 98 | Paved parking, HSG D          |
| 1,380     | 80 | >75% Grass cover, Good, HSG D |
| 1,949     | 85 | Weighted Average              |
| 1,380     |    | 70.81% Pervious Area          |
| 569       |    | 29.19% Impervious Area        |

**Subcatchment 1S: DP#1-GREENMONT**

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 143

**Summary for Subcatchment 3S: PWS#2**

Runoff = 0.81 cfs @ 12.07 hrs, Volume= 0.062 af, Depth= 5.58"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs


Type III 24-hr 100-YR Rainfall=6.40"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 4,094     | 98 | Paved parking, HSG D          |
| 1,678     | 80 | >75% Grass cover, Good, HSG D |
| 5,772     | 93 | Weighted Average              |
| 1,678     |    | 29.07% Pervious Area          |
| 4,094     |    | 70.93% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 3S: PWS#2**

Hydrograph





## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 144

### Summary for Subcatchment 5S: ROOFS 15 - 28

Runoff = 1.46 cfs @ 12.07 hrs, Volume= 0.119 af, Depth= 6.16"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 100-YR Rainfall=6.40"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 10,080    | 98 | Roofs, HSG D            |
| 10,080    |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

### Subcatchment 5S: ROOFS 15 - 28



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 145


**Summary for Subcatchment 6S: PWS#3**

Runoff = 3.16 cfs @ 12.07 hrs, Volume= 0.225 af, Depth= 4.14"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 100-YR Rainfall=6.40"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 18,244    | 80 | >75% Grass cover, Good, HSG D |
| * 10,097  | 80 |                               |
| 28,341    | 80 | Weighted Average              |
| 28,341    |    | 100.00% Pervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 6S: PWS#3**



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 146

**Summary for Subcatchment 7S: PWS#4**

Runoff = 1.10 cfs @ 12.07 hrs, Volume= 0.089 af, Depth= 6.16"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 100-YR Rainfall=6.40"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 7,586     | 98 | Paved parking, HSG D    |
| 7,586     |    | 100.00% Impervious Area |

| Tc<br>(min) | Length<br>(feet) | Slope<br>(ft/ft) | Velocity<br>(ft/sec) | Capacity<br>(cfs) | Description   |
|-------------|------------------|------------------|----------------------|-------------------|---------------|
| 5.0         |                  |                  |                      |                   | Direct Entry, |

**Subcatchment 7S: PWS#4**

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 147


**Summary for Subcatchment 9S: PWS#5**

Runoff = 0.81 cfs @ 12.07 hrs, Volume= 0.062 af, Depth= 5.58"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 100-YR Rainfall=6.40"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 4,090     | 98 | Paved parking, HSG D          |
| 1,677     | 80 | >75% Grass cover, Good, HSG D |
| 5,767     | 93 | Weighted Average              |
| 1,677     |    | 29.08% Pervious Area          |
| 4,090     |    | 70.92% Impervious Area        |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 9S: PWS#5**



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 148


**Summary for Subcatchment 11S: PWS#6**

Runoff = 3.32 cfs @ 12.07 hrs, Volume= 0.236 af, Depth= 4.14"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
Type III 24-hr 100-YR Rainfall=6.40"

| Area (sf) | CN | Description                   |
|-----------|----|-------------------------------|
| 21,412    | 80 | >75% Grass cover, Good, HSG D |
| * 8,403   | 80 |                               |
| 29,815    | 80 | Weighted Average              |
| 29,815    |    | 100.00% Pervious Area         |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 11S: PWS#6**



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 149

**Summary for Subcatchment 13S: PWS#7**


Runoff = 1.07 cfs @ 12.07 hrs, Volume= 0.087 af, Depth= 6.16"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 100-YR Rainfall=6.40"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 7,376     | 98 | Paved parking, HSG D    |
| 7,376     |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 13S: PWS#7**

**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 150

**Summary for Subcatchment 18S: ROOFS 1 - 14**


Runoff = 1.46 cfs @ 12.07 hrs, Volume= 0.119 af, Depth= 6.16"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Type III 24-hr 100-YR Rainfall=6.40"

| Area (sf) | CN | Description             |
|-----------|----|-------------------------|
| 10,080    | 98 | Roofs, HSG D            |
| 10,080    |    | 100.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description   |
|----------|---------------|---------------|-------------------|----------------|---------------|
| 5.0      |               |               |                   |                | Direct Entry, |

**Subcatchment 18S: ROOFS 1 - 14**



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 151

### Summary for Reach 4R: GRASS LINED SWALE #1

Inflow Area = 1.015 ac, 32.07% Impervious, Inflow Depth = 3.95" for 100-YR event  
Inflow = 4.14 cfs @ 12.08 hrs, Volume= 0.334 af  
Outflow = 3.91 cfs @ 12.16 hrs, Volume= 0.334 af, Atten= 6%, Lag= 4.5 min

Routing by Stor-Ind+Trans method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.84 fps, Min. Travel Time= 2.5 min

Avg. Velocity = 0.57 fps, Avg. Travel Time= 8.1 min

Peak Storage= 593 cf @ 12.11 hrs

Average Depth at Peak Storage= 0.31'

Bank-Full Depth= 1.00' Flow Area= 14.0 sf, Capacity= 50.43 cfs

4.00' x 1.00' deep channel, n= 0.030 Earth, grassed & winding

Side Slope Z-value= 10.0 ' / ' Top Width= 24.00'


Length= 275.0' Slope= 0.0109 ' / '

Inlet Invert= 99.00', Outlet Invert= 96.00'



### Reach 4R: GRASS LINED SWALE #1

Hydrograph





## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 152

### Summary for Reach 12R: GRASS LINED SWALE #2

Inflow Area = 1.048 ac, 31.03% Impervious, Inflow Depth = 4.00" for 100-YR event  
Inflow = 4.39 cfs @ 12.09 hrs, Volume= 0.350 af  
Outflow = 4.18 cfs @ 12.17 hrs, Volume= 0.350 af, Atten= 5%, Lag= 4.5 min

Routing by Stor-Ind+Trans method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

Max. Velocity= 1.82 fps, Min. Travel Time= 2.5 min

Avg. Velocity = 0.57 fps, Avg. Travel Time= 7.9 min

Peak Storage= 623 cf @ 12.12 hrs

Average Depth at Peak Storage= 0.31'

Bank-Full Depth= 1.00' Flow Area= 15.5 sf, Capacity= 55.70 cfs

4.00' x 1.00' deep channel, n= 0.030 Earth, grassed & winding

Side Slope Z-value= 4.0 19.0 ' Top Width= 27.00'


Length= 270.0' Slope= 0.0111 '/'

Inlet Invert= 99.00', Outlet Invert= 96.00'



### Reach 12R: GRASS LINED SWALE #2

Hydrograph



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC  
 HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 153

**Summary for Pond 8P: DETENTION POND #1**

Inflow Area = 1.189 ac, 42.02% Impervious, Inflow Depth = 4.26" for 100-YR event  
 Inflow = 4.66 cfs @ 12.14 hrs, Volume= 0.422 af  
 Outflow = 2.15 cfs @ 12.46 hrs, Volume= 0.398 af, Atten= 54%, Lag= 19.2 min  
 Discarded = 0.12 cfs @ 12.46 hrs, Volume= 0.186 af  
 Primary = 2.03 cfs @ 12.46 hrs, Volume= 0.212 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 95.69' @ 12.46 hrs Surf.Area= 4,029 sf Storage= 7,488 cf

Plug-Flow detention time= 257.6 min calculated for 0.398 af (94% of inflow)  
 Center-of-Mass det. time= 228.1 min ( 1,031.2 - 803.1 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 93.00' | 8,773 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 93.00               | 1,640                | 257.0            | 0                         | 0                         | 1,640               |
| 94.00               | 2,440                | 276.0            | 2,027                     | 2,027                     | 2,489               |
| 95.00               | 3,381                | 308.0            | 2,898                     | 4,925                     | 4,004               |
| 96.00               | 4,335                | 329.0            | 3,848                     | 8,773                     | 5,115               |

| Device | Routing   | Invert | Outlet Devices                                                                                                                                                                                                                                               |
|--------|-----------|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | Primary   | 95.50' | <b>6.0' long x 3.0' breadth Broad-Crested Rectangular Weir</b><br>Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00<br>2.50 3.00 3.50 4.00 4.50<br>Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68<br>2.72 2.81 2.92 2.97 3.07 3.32 |
| #2     | Primary   | 94.75' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600                                                                                                                                                                                                                     |
| #3     | Discarded | 93.00' | <b>1.080 in/hr Exfiltration over Wetted area</b>                                                                                                                                                                                                             |

**Discarded OutFlow** Max=0.12 cfs @ 12.46 hrs HW=95.69' (Free Discharge)

↑ **3=Exfiltration** (Exfiltration Controls 0.12 cfs)

**Primary OutFlow** Max=2.01 cfs @ 12.46 hrs HW=95.69' (Free Discharge)

↑ **1=Broad-Crested Rectangular Weir** (Weir Controls 1.23 cfs @ 1.07 fps)

↑ **2=Orifice/Grate** (Orifice Controls 0.79 cfs @ 4.00 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 154

### Pond 8P: DETENTION POND #1





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 155

**Summary for Pond 14P: DETENTION POND #2**

Inflow Area = 1.218 ac, 40.62% Impervious, Inflow Depth = 4.29" for 100-YR event  
 Inflow = 4.88 cfs @ 12.15 hrs, Volume= 0.435 af  
 Outflow = 3.20 cfs @ 12.33 hrs, Volume= 0.382 af, Atten= 34%, Lag= 10.4 min  
 Discarded = 0.01 cfs @ 12.33 hrs, Volume= 0.013 af  
 Primary = 3.19 cfs @ 12.33 hrs, Volume= 0.369 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 95.96' @ 12.33 hrs Surf.Area= 3,067 sf Storage= 5,540 cf

Plug-Flow detention time= 117.5 min calculated for 0.382 af (88% of inflow)  
 Center-of-Mass det. time= 63.5 min ( 864.6 - 801.1 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 93.00' | 5,654 cf      | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
|---------------------|----------------------|------------------|---------------------------|---------------------------|---------------------|
| 93.00               | 933                  | 130.0            | 0                         | 0                         | 933                 |
| 94.00               | 1,451                | 245.0            | 1,183                     | 1,183                     | 4,370               |
| 95.00               | 2,221                | 267.0            | 1,822                     | 3,005                     | 5,302               |
| 96.00               | 3,102                | 296.0            | 2,649                     | 5,654                     | 6,632               |

| Device | Routing   | Invert | Outlet Devices                                    |
|--------|-----------|--------|---------------------------------------------------|
| #1     | Primary   | 94.75' | <b>12.0" Vert. Orifice/Grate</b> C= 0.600         |
| #2     | Discarded | 93.00' | <b>0.110 in/hr Exfiltration over Surface area</b> |

**Discarded OutFlow** Max=0.01 cfs @ 12.33 hrs HW=95.96' (Free Discharge)  
 ↳ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=3.19 cfs @ 12.33 hrs HW=95.96' (Free Discharge)  
 ↳ **1=Orifice/Grate** (Orifice Controls 3.19 cfs @ 4.06 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 156

### Pond 14P: DETENTION POND #2



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC  
 HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 157

**Summary for Pond 20P: RECHARGE 1 - 8**

Inflow Area = 0.231 ac, 100.00% Impervious, Inflow Depth = 6.16" for 100-YR event  
 Inflow = 1.46 cfs @ 12.07 hrs, Volume= 0.119 af  
 Outflow = 1.10 cfs @ 12.14 hrs, Volume= 0.109 af, Atten= 25%, Lag= 4.4 min  
 Discarded = 0.01 cfs @ 12.14 hrs, Volume= 0.022 af  
 Primary = 1.09 cfs @ 12.14 hrs, Volume= 0.087 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 100.34' @ 12.14 hrs Surf.Area= 540 sf Storage= 1,155 cf

Plug-Flow detention time= 164.2 min calculated for 0.109 af (91% of inflow)  
 Center-of-Mass det. time= 120.6 min ( 863.9 - 743.3 )

| Volume | Invert | Avail.Storage | Storage Description                                                                                                                                                                                                    |
|--------|--------|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | 96.50' | 646 cf        | <b>12.00'W x 45.00'L x 4.00'H Prismatic</b><br>2,160 cf Overall - 544 cf Embedded = 1,616 cf x 40.0% Voids                                                                                                             |
| #2     | 97.00' | 544 cf        | <b>Cultec R-330XL</b> x 10 Inside #1<br>Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf<br>Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap<br>Row Length Adjustment= +1.50' x 7.45 sf x 2 rows |
|        |        | 1,190 cf      | Total Available Storage                                                                                                                                                                                                |

| Device | Routing   | Invert | Outlet Devices                                   |
|--------|-----------|--------|--------------------------------------------------|
| #1     | Primary   | 98.75' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600         |
| #2     | Discarded | 96.50' | <b>0.440 in/hr Exfiltration over Wetted area</b> |

**Discarded OutFlow** Max=0.01 cfs @ 12.14 hrs HW=100.32' (Free Discharge)  
 ↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=1.09 cfs @ 12.14 hrs HW=100.32' (Free Discharge)  
 ↑ **1=Orifice/Grate** (Orifice Controls 1.09 cfs @ 5.53 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 158

### Pond 20P: RECHARGE 1 - 8



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC  
 HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 159

### Summary for Pond 23P: RECHARGE 15-28

Inflow Area = 0.231 ac, 100.00% Impervious, Inflow Depth = 6.16" for 100-YR event  
 Inflow = 1.46 cfs @ 12.07 hrs, Volume= 0.119 af  
 Outflow = 1.10 cfs @ 12.14 hrs, Volume= 0.109 af, Atten= 25%, Lag= 4.4 min  
 Discarded = 0.01 cfs @ 12.14 hrs, Volume= 0.022 af  
 Primary = 1.09 cfs @ 12.14 hrs, Volume= 0.087 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 100.34' @ 12.14 hrs Surf.Area= 540 sf Storage= 1,155 cf

Plug-Flow detention time= 164.2 min calculated for 0.109 af (91% of inflow)  
 Center-of-Mass det. time= 120.6 min ( 863.9 - 743.3 )

| Volume | Invert | Avail.Storage | Storage Description                                                                                                                                                                                                    |
|--------|--------|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| #1     | 96.50' | 646 cf        | <b>12.00'W x 45.00'L x 4.00'H Prismatic</b><br>2,160 cf Overall - 544 cf Embedded = 1,616 cf x 40.0% Voids                                                                                                             |
| #2     | 97.00' | 544 cf        | <b>Cultec R-330XL</b> x 10 Inside #1<br>Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf<br>Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap<br>Row Length Adjustment= +1.50' x 7.45 sf x 2 rows |
|        |        | 1,190 cf      | Total Available Storage                                                                                                                                                                                                |

| Device | Routing   | Invert | Outlet Devices                                   |
|--------|-----------|--------|--------------------------------------------------|
| #1     | Primary   | 98.75' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600         |
| #2     | Discarded | 96.50' | <b>0.440 in/hr Exfiltration over Wetted area</b> |

**Discarded OutFlow** Max=0.01 cfs @ 12.14 hrs HW=100.32' (Free Discharge)  
 ↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=1.09 cfs @ 12.14 hrs HW=100.32' (Free Discharge)  
 ↑ **1=Orifice/Grate** (Orifice Controls 1.09 cfs @ 5.53 fps)

**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 160

**Pond 23P: RECHARGE 15-28**





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC  
 HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 161

**Summary for Pond 25P: BIORETENTION BASIN**

Inflow Area = 0.133 ac, 70.93% Impervious, Inflow Depth = 5.58" for 100-YR event  
 Inflow = 0.81 cfs @ 12.07 hrs, Volume= 0.062 af  
 Outflow = 0.27 cfs @ 12.36 hrs, Volume= 0.035 af, Atten= 66%, Lag= 17.1 min  
 Discarded = 0.01 cfs @ 12.36 hrs, Volume= 0.013 af  
 Primary = 0.26 cfs @ 12.36 hrs, Volume= 0.022 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 99.87' @ 12.36 hrs Surf.Area= 625 sf Storage= 1,450 cf

Plug-Flow detention time= 346.1 min calculated for 0.035 af (56% of inflow)  
 Center-of-Mass det. time= 238.4 min ( 1,008.6 - 770.3 )

| Volume              | Invert               | Avail.Storage    | Storage Description                                        |                           |                     |
|---------------------|----------------------|------------------|------------------------------------------------------------|---------------------------|---------------------|
| #1                  | 95.50'               | 1,538 cf         | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |                           |                     |
| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Inc.Store<br>(cubic-feet)                                  | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
| 95.50               | 302                  | 122.0            | 0                                                          | 0                         | 302                 |
| 96.00               | 302                  | 122.0            | 151                                                        | 151                       | 363                 |
| 98.75               | 302                  | 122.0            | 831                                                        | 982                       | 699                 |
| 99.00               | 302                  | 122.0            | 76                                                         | 1,057                     | 729                 |
| 100.00              | 685                  | 146.0            | 481                                                        | 1,538                     | 1,258               |

| Device | Routing   | Invert | Outlet Devices                                                                                         |
|--------|-----------|--------|--------------------------------------------------------------------------------------------------------|
| #1     | Primary   | 99.75' | <b>2.0' long x 2.00' rise Sharp-Crested Rectangular Weir</b><br>2 End Contraction(s) 0.7' Crest Height |
| #2     | Discarded | 95.50' | <b>0.440 in/hr Exfiltration over Surface area</b>                                                      |

**Discarded OutFlow** Max=0.01 cfs @ 12.36 hrs HW=99.87' (Free Discharge)  
 ↳ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.26 cfs @ 12.36 hrs HW=99.87' (Free Discharge)  
 ↳ **1=Sharp-Crested Rectangular Weir** (Weir Controls 0.26 cfs @ 1.13 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 162

### Pond 25P: BIORETENTION BASIN



**Prop-Conditions**

Type III 24-hr 100-YR Rainfall=6.40"

Prepared by Cornerstone Land Associates, LLC

Printed 6/1/2023

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Page 163

**Summary for Pond 26P: BIORETENTION BASIN**

Inflow Area = 0.132 ac, 70.92% Impervious, Inflow Depth = 5.58" for 100-YR event  
 Inflow = 0.81 cfs @ 12.07 hrs, Volume= 0.062 af  
 Outflow = 0.41 cfs @ 12.22 hrs, Volume= 0.046 af, Atten= 49%, Lag= 8.8 min  
 Discarded = 0.01 cfs @ 12.22 hrs, Volume= 0.019 af  
 Primary = 0.40 cfs @ 12.22 hrs, Volume= 0.026 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 99.93' @ 12.22 hrs Surf.Area= 1,033 sf Storage= 1,201 cf

Plug-Flow detention time= 315.4 min calculated for 0.045 af (74% of inflow)  
 Center-of-Mass det. time= 230.5 min ( 1,000.7 - 770.3 )

| Volume              | Invert               | Avail.Storage    | Storage Description                                        |                           |                           |                     |
|---------------------|----------------------|------------------|------------------------------------------------------------|---------------------------|---------------------------|---------------------|
| #1                  | 95.50'               | 2,456 cf         | <b>Custom Stage Data (Irregular)</b> Listed below (Recalc) |                           |                           |                     |
| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Perim.<br>(feet) | Voids<br>(%)                                               | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) | Wet.Area<br>(sq-ft) |
| 95.50               | 425                  | 167.0            | 0.0                                                        | 0                         | 0                         | 425                 |
| 96.00               | 425                  | 167.0            | 40.0                                                       | 85                        | 85                        | 509                 |
| 98.75               | 425                  | 167.0            | 30.0                                                       | 351                       | 436                       | 968                 |
| 99.00               | 425                  | 167.0            | 100.0                                                      | 106                       | 542                       | 1,010               |
| 100.00              | 1,088                | 213.0            | 100.0                                                      | 731                       | 1,273                     | 2,413               |
| 101.00              | 1,281                | 181.0            | 100.0                                                      | 1,183                     | 2,456                     | 3,436               |

| Device | Routing   | Invert | Outlet Devices                                                 |  |  |  |  |  |  |  |  |  |  |  |
|--------|-----------|--------|----------------------------------------------------------------|--|--|--|--|--|--|--|--|--|--|--|
| #1     | Primary   | 99.75' | <b>2.0' long x 2.0' breadth Broad-Crested Rectangular Weir</b> |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00  |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | 2.50 3.00 3.50                                                 |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | Coef. (English) 2.54 2.61 2.61 2.60 2.66 2.70 2.77 2.89 2.88   |  |  |  |  |  |  |  |  |  |  |  |
|        |           |        | 2.85 3.07 3.20 3.32                                            |  |  |  |  |  |  |  |  |  |  |  |
| #2     | Discarded | 95.50' | <b>0.440 in/hr Exfiltration over Surface area</b>              |  |  |  |  |  |  |  |  |  |  |  |

**Discarded OutFlow** Max=0.01 cfs @ 12.22 hrs HW=99.93' (Free Discharge)

↑ **2=Exfiltration** (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=0.39 cfs @ 12.22 hrs HW=99.93' (Free Discharge)

↑ **1=Broad-Crested Rectangular Weir** (Weir Controls 0.39 cfs @ 1.08 fps)



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 164

### Pond 26P: BIORETENTION BASIN



**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC  
 HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 165

### Summary for Pond 29P: TREE BOX FILTER

Inflow Area = 0.174 ac, 100.00% Impervious, Inflow Depth = 6.16" for 100-YR event  
 Inflow = 1.10 cfs @ 12.07 hrs, Volume= 0.089 af  
 Outflow = 1.12 cfs @ 12.09 hrs, Volume= 0.088 af, Atten= 0%, Lag= 0.9 min  
 Primary = 1.12 cfs @ 12.09 hrs, Volume= 0.088 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 98.90' @ 12.09 hrs Surf.Area= 60 sf Storage= 93 cf

Plug-Flow detention time= 16.8 min calculated for 0.088 af (99% of inflow)  
 Center-of-Mass det. time= 8.7 min ( 752.0 - 743.3 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.00' | 93 cf         | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Voids<br>(%) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) |
|---------------------|----------------------|--------------|---------------------------|---------------------------|
| 95.00               | 60                   | 0.0          | 0                         | 0                         |
| 95.50               | 60                   | 40.0         | 12                        | 12                        |
| 97.50               | 60                   | 30.0         | 36                        | 48                        |
| 98.25               | 60                   | 100.0        | 45                        | 93                        |

| Device | Routing  | Invert | Outlet Devices                                               |
|--------|----------|--------|--------------------------------------------------------------|
| #1     | Device 2 | 95.00' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600                     |
| #2     | Primary  | 97.50' | <b>1.0" W x 18.0" H Vert. Orifice/Grate X 10.00</b> C= 0.600 |

**Primary OutFlow** Max=1.08 cfs @ 12.09 hrs HW=98.80' (Free Discharge)

↑ **2=Orifice/Grate** (Passes 1.08 cfs of 3.98 cfs potential flow)

↑ **1=Orifice/Grate** (Orifice Controls 1.08 cfs @ 5.50 fps)

# Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 166

## Pond 29P: TREE BOX FILTER





**Prop-Conditions**

Prepared by Cornerstone Land Associates, LLC  
 HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 167

### Summary for Pond 33P: TREE BOX FILTER

Inflow Area = 0.169 ac, 100.00% Impervious, Inflow Depth = 6.16" for 100-YR event  
 Inflow = 1.07 cfs @ 12.07 hrs, Volume= 0.087 af  
 Outflow = 1.11 cfs @ 12.09 hrs, Volume= 0.086 af, Atten= 0%, Lag= 1.1 min  
 Primary = 1.11 cfs @ 12.09 hrs, Volume= 0.086 af

Routing by Stor-Ind method, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs  
 Peak Elev= 98.87' @ 12.09 hrs Surf.Area= 60 sf Storage= 93 cf

Plug-Flow detention time= 17.4 min calculated for 0.086 af (99% of inflow)  
 Center-of-Mass det. time= 8.9 min ( 752.2 - 743.3 )

| Volume | Invert | Avail.Storage | Storage Description                                        |
|--------|--------|---------------|------------------------------------------------------------|
| #1     | 95.00' | 93 cf         | <b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) |

| Elevation<br>(feet) | Surf.Area<br>(sq-ft) | Voids<br>(%) | Inc.Store<br>(cubic-feet) | Cum.Store<br>(cubic-feet) |
|---------------------|----------------------|--------------|---------------------------|---------------------------|
| 95.00               | 60                   | 0.0          | 0                         | 0                         |
| 95.50               | 60                   | 40.0         | 12                        | 12                        |
| 97.50               | 60                   | 30.0         | 36                        | 48                        |
| 98.25               | 60                   | 100.0        | 45                        | 93                        |

| Device | Routing  | Invert | Outlet Devices                                               |
|--------|----------|--------|--------------------------------------------------------------|
| #1     | Device 2 | 95.00' | <b>6.0" Vert. Orifice/Grate</b> C= 0.600                     |
| #2     | Primary  | 97.50' | <b>1.0" W x 18.0" H Vert. Orifice/Grate X 10.00</b> C= 0.600 |

**Primary OutFlow** Max=1.07 cfs @ 12.09 hrs HW=98.78' (Free Discharge)

↑ **2=Orifice/Grate** (Passes 1.07 cfs of 3.87 cfs potential flow)

↑ **1=Orifice/Grate** (Orifice Controls 1.07 cfs @ 5.44 fps)

## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC


HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 168

### Pond 33P: TREE BOX FILTER



## Prop-Conditions

Prepared by Cornerstone Land Associates, LLC

HydroCAD® 10.00 s/n 03735 © 2012 HydroCAD Software Solutions LLC

Type III 24-hr 100-YR Rainfall=6.40"

Printed 6/1/2023

Page 169

### Summary for Link 15L: DP#2-REAR WETLANDS

Inflow Area = 2.406 ac, 41.32% Impervious, Inflow Depth = 2.90" for 100-YR event  
Inflow = 5.09 cfs @ 12.43 hrs, Volume= 0.581 af  
Primary = 5.09 cfs @ 12.43 hrs, Volume= 0.581 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.10-36.00 hrs, dt= 0.05 hrs

### Link 15L: DP#2-REAR WETLANDS

